ADDENDUM



Date: December 4, 2023 Project: NEBRASKA CORRECTIONAL

> CENTER FOR WOMEN BUILDING A WATER HEATER AND NORTH HALL BOILER REPLACEMENT

Project No.: 23095 To:

Addendum No.: 1

CC:

CHANGES TO PROJECT MANUAL

CHANGES TO PROJECT DRAWINGS

Mechanical Review (M1.1, M1.2, M1.3, M1.4, M3.1, AND M4.1)

- M1.1 BLDG "A" NEW AND DEMOLITION FLOOR PLANS MECHANICAL PIPING -**MECHANICAL ROOM**
 - WH-1 has been relocated to meet required 3'-0" clearance around unit.
 - WH-2 has been rotated.
 - P-WH1 and P-WH2 have been relocated for easier access.
 - Humidity drain from WH-1 has been re-routed to specified floor drain.
 - The housekeeping pad has been revised for new location of WH-1.
 - Inline Pump detail has been added to this plan to detail Pump installation.
- M1.2 BLDG "A" NEW AND DEMOLITION FLOOR PLANS GAS PIPING MECHANICAL ROOM Gas serving WH-1 has been revised to match with the new location of WH-1 and WH-2.
- M1.3 BLDG "A" NEW AND DEMOLITION FLOOR PLANS MECHANICAL DUCT MECHANICAL ROOM
 - Intake and Flue ductwork serving WH-1 and WH-2 have been revised to match new locations.
- M1.4 NORTH HALL NEW AND DEMOLITION FLOOR PLANS MECHANICAL MECHANICAL ROOM
 - Notes specifying access to space for boiler have been added.
 - Chase location for new intakes and Flues are now shown under First Floor Chase Location to better show location of chase.
- M3.1 SCHEDULES MECHANICAL
 - AERCO has been specified as only acceptable brand for WH-1, WH-2, and B-1.
 - Note 8 has been added to the "DOMESTIC WATER HEATER SCHEDULE" notes.
 - Note 6 has been added to the "BOILER SCHEDULE" notes.
 - The Duct Material and Insulations Schedule has been revised. The duct type for Flue has been clarified to pertain to "Non-Condensing" Flues.
- **M4.1 SCHEMATICS MECHANICAL**
 - Sequence of Operation for Water Heaters have been updated to specify controls for pumps.

Electrical Review (E1.1, E1.2, E2.1)

- E1.1 BUILDING 'A' NEW/DEMO FLOOR PLANS ELECTRICAL
 - Added existing boiler shutdown toggle switches to Demo floor plan. Added keynote 6 to remove these switches.
 - Added new boiler shutdown buttons to New floor plan. Added keynote 7 to install new shutdown buttons and interlock. Buttons shall shut down all water heaters and boilers in room.
 - Added to keynote 4: "...Modify boiler shutdown wiring as needed during phase 2 to incorporate new water heater".
 - Modified drawings to match new equipment layout.

ADDENDUM



New pump disconnects now shown as motor starters. VFDs to be provided by mechanical contractor. See equipment connection schedule, sheet E2.1.

E1.2 - NORTH HALL NEW/DEMO FLOOR PLANS - ELECTRICAL

- Added existing boiler shutdown toggle switches to Demo floor plan. Added keynote 6 to remove these switches.
- Added new boiler shutdown buttons to New floor plan. Added keynote 7 to install new shutdown buttons and interlock. Buttons shall shut down all water heaters and boilers in room.
- New pump disconnect now shown as motor starter. VFD to be provided by mechanical contractor. See equipment connection schedule, sheet E2.1.

E2.1 – ELECTRICAL SCHEDULES

Changed disconnect info for BFP-1, P-WH1, and P-WH2. Pumps to be served by VFD instead of disconnect switch. Added note 2 to equipment connection schedule: VFD to be provided by mechanical contractor.

By: Spencer Gemmell, Noel Murphy Date: 2023-12-04