



DATE ISSUED	February 27, 2024	ADDENDUM #	2
ENGINEER	Engineering Technologies, Inc. 825 M Street, Suite 200 Lincoln, NE 68508	ETI PROJECT #	2023-193
		PROJECT	Schuyler Central High School – HVAC Upgrades

The Architect issues this Addendum to all known bidders before receipt of proposals. Bidder shall acknowledge the receipt of this addendum on their proposal sheet and all information contained herein shall become a part of the contract documents.

ADDENDUM:**GENERAL ITEMS – MECHANICAL**

1. Unit Pricing and Metal Roofing/Clarifications:

- A. The unit pricing in which the sheet metal contractor shall expect to pay to the metal roofing contractor to install supports and flash the new rooftop unit curbs into the new and existing metal roof shall be as follows:
 - i. \$1,000 per rooftop unit - For labor and material to install support for each of the new roof curbs and seal new metal roofing around the new roof curb.
 - ii. \$2,200 per rooftop unit – For labor and material to remove existing metal panels, install additional roofing supports, reinstall panels and seal around new roof curb.
- B. As a clarification to the timing of the new metal roofing and the installation of rooftop units and ductwork; the metal roofing contractor will remove the existing ballasted roof rock, install roof supports, roof curb supports, and coordinate with the HVAC Contractor to install to the roof curbs before metal panels are installed. This shall allow the HVAC Contractor to install the curbs and return ductwork on the roof prior to the metal panels being installed.

PRIOR APPROVAL – ELECTRICAL

- 1. The following manufacturers have received prior approval for bidding purposes subject to shop drawing review:
 - A. List Equipment Here
Light Fixture #1
Light Fixture X1
 - List Manufacturer Here
Metalux
Sure-Lite

END OF ADDENDUM