

ADDENDUM NO. 1
TO
CONTRACT DOCUMENTS AND SPECIFICATIONS
FOR
BEAL SLOUGH STREAMBANK STABILIZATION PROJECT

DATE OF ISSUE: 22 JULY 2026

TO: PROSPECTIVE BIDDERS AND OTHER INTERESTED PARTIES

THE CONTRACT DOCUMENTS AND SPECIFICATIONS, INCLUDING THE CONTRACT DRAWINGS, ARE HEREBY MODIFIED BY THE FOLLOWING ITEMS:

CHANGES TO DRAWINGS

AD-1 Item 1 – DRAWING SHEET 00CS-103 SURFACE RESTORATION PLAN

A. Amended the 'Planting Schedule' with the following plant size information:

PLANTING SCHEDULE - REVISED			
Common Name	Botanical Name	Quantity	Size / Height
Elderberry	Sambucus canadensis	19	#3 AIR POT/18" MIN.
Black Chokeberry	Aronia melanocarpa var. elata	29	#3 AIR POT/18" MIN.
Isanti Red-twig Dogwood	Cornus sericea 'Isanti'	22	#3 AIR POT/18" MIN.
Coralberry	Symphoricarpos orbiculatus	25	#3 AIR POT/18" MIN.
Live Stake – Sandbar Willow	Salix exigua	150	6 FOOT
Pioneer Elm	Ulmus x hollandica	3	#7 RT BAG/1.25" CAL.
American hophornbeam	Ostrya virginiana	2	#7 RT BAG/1.25" CAL.
Chinkapin oak	Quercus muehlenbergii	2	#7 RT BAG/1.25" CAL.
Northern Catalpa	Catalpa speciosa	1	#7 RT BAG/1.25" CAL.


CHANGES TO SPECIFICATIONS

NONE

ALL ITEMS IN CONFLICT WITH THE ADDENDA ARE HEREBY DELETED.

THIS ADDENDUM IS MADE PART OF THE CONTRACT DOCUMENTS AND SHALL BE NOTED ON THE PROPOSAL.

HDR Engineering, Inc.


Creighton R. Omer, PE

