

## ADDENDUM NO. 2

**PROJECT NAME:** City Campus Utility Plant Chiller Replacement Project  
General Installation Contract Package

**UNL PROJECT NUMBER:** C028P232

DATE OF ISSUANCE: December 13, 2011  
DATE PROPOSALS DUE: December 20, 2011 2PM CST

The bid documents dated November 23, 2011 for the above referenced project are amended by this addendum.

**NOTICE:** This Addendum is issued to all interested prospective proposers as an amendment to the Project Manual or other parts of the bidding (contract) documents for the above named project. Reference to this Addendum must be included in the Bid proposal. The information contained herein shall be fully incorporated into the contract documents as though originally included therein.

### **GENERAL INFORMATION:**

1. **Shoring:** The existing floors are not suitable for supporting the weight of the chillers. If the chillers are to be brought into the building prior to permanent structural modifications being complete, then temporary shoring/support will be necessary.
2. **Electrical Switchgear:** The switchgear bid information is available for reference at <http://procurement.unl.edu/bids/> and is #285256-11.

### **MODIFICATIONS TO THE PROJECT SPECIFICATIONS:**

1. **Table of Contents:** Delete Specification Section 08 41 13 Aluminum Storefront Framing.
2. **Approved Piping Fabricator:** The piping fabricator addressed in Specification Section 40 05 13 Process Piping will be reviewed with the Post Bid submittal outlined in Specification Section 00 21 13 Instructions to Bidders. No prior approval is required.

### **MODIFICATIONS TO THE PROJECT DRAWINGS:**

1. **MN105:** Existing piping located west of gridline C is not shown on the plan or model. The 30" tower water piping was designed around the existing piping and drops to go under it. New electrical conduit will also need to be routed around this existing piping.

END OF ADDENDUM NO. 2