

ADDENDUM NO. 1

PROJECT NAME: East Stadium Bid Package 5
UNL PROJECT NUMBER: C049P136

CONSULTANT: The Clark Enersen Partners
1010 Lincoln Mall, Suite 200
Lincoln, NE 68508

HNTB Corporation
715 Kirk Drive
Kansas City, Missouri 64105

DATE OF ISSUANCE: December 28, 2011
DATE OF BID OPENING:

The bid documents dated December 16, 2011 for the above referenced project are amended by this addendum.

NOTICE: This Addendum is issued to all interested prospective bidders as an amendment to the project manual or other parts of the bidding (contract) documents for the above named project. Reference to this Addendum must be included in the Bid proposal. The information contained herein shall be fully incorporated into the contract documents as though originally included therein.

MODIFICATIONS TO THE SPECIFICATIONS:

Item #1-1 Refer to the Specifications, Section 00 1116 – Invitation to Bid

- a. Add this section in its entirety to the Project Manual.

Item #1-2 Refer to the Specifications, Section 01 1200 – Summary of Multiple Subcontracts – Bid Packages

- a. Add this section in its entirety to the Project Manual.

END OF ADDENDUM NO. 1

SECTION 00 11 16 – INVITATION TO BID

THE UNIVERSITY OF NEBRASKA INVITATION TO BID

1.0 INVITATION

- A. Sampson Construction, acting as Construction Manager for the Board of Regents of the University of Nebraska, invites Bids for the following project, Contingent on Board of Regents Approval:

Project Name: East Stadium Improvements **Bid Package 5 - Finishes,**

Campus: City Campus

Project Address: UNL Memorial Stadium (east)
Stadium Drive, Lincoln NE

Architect : The Clark Enersen Partners

Identification of Contract(s) to be Awarded: Subcontracts/Material Supplier to Construction Manager

2.0 TIME AND PLACE FOR RECEIPT OF BIDS

- A. Sealed Bid Proposals will be received privately:

Closing Date and Time for Receipt of Bids: Wednesday, January 11, 2012 at 2:00PM CDT

Place for Receipt of Hand-Carried Bids:

Sampson Construction
3730 South 14th Street
Lincoln, NE 68502

Address for Delivery of Mailed Bids:

Same as above

Electronic Submission:

FAX: (402) 434-5466

E-mail: UNLeaststadium@sampson-construction.com

Opening Place:

Private opening with UNL Facility Management and others at Sampson Construction office.

3.0 BOND

- A. Successful Bidder may be required to furnish an Owner's Protective Bond (University of Nebraska Standard Form) in the amount of 100% of the Contract Amount. All bids shall include an add alternate for the inclusion of the performance and payment bond as a percentage.

SECTION 00 11 16 – INVITATION TO BID

4.0 BID DOCUMENTS

- A. Bidding Documents may be examined at the following locations:
1. A & D Technical Supply Co., 1822 “N” St., Lincoln, NE 68508, (402) 474-5454
 2. A & D Technical Supply Co., 4320 S. 89th St., Omaha, NE 68127, (402) 592-4950
 3. Plan Services:
 - a. Lincoln Builders Bureau, 5910 South 58th Street, Suite “C”, Lincoln, NE 68516 (402) 421-8332, FAX (402) 421-8334
 - b. F. W. Dodge Information Services, F. W. Dodge Information Services, 2507 Ingersoll Avenue, Des Moines, IA 50312 (515) 223-1046. FAX (515)-223-8564
 - c. Omaha Builders Bureau, 4255 South 94th Street, Omaha, NE 68127 (402) 593-6908, FAX (402) 593-6912
- B. Bid Documents may be obtained from **A & D Technical Supply Co.** listed above, upon payment of a refundable deposit check in the amount of \$100 deposit for each set of documents, in the form of a check made payable to **A & D Technical**. If documents are to be transmitted by mail or a parcel delivery service, check with A&D Technical Supply for the amount required.
1. Only Drawings Volume 1 – Civil, Landscape, and exterior Architecture, and Volume 2 – Interior Architecture and Interior Finishes of Bid Documents will be issued. Volume 3 – Structural, Volume 4 - Mechanical Plumbing and Fire Protection, and Volume 5 – Electrical and Scoreboard Audio System Upgrade will be available for review in PDF format on Sampson’s Plan room website, and at Sampson’s Main Office Plan Room.
 2. Only Specifications/Project Manual Book 1 and Book 2 of Bid Documents will be issued. Book 3 will be available for review in PDF format on Sampson’s Plan room website, and at Sampson’s Main Office Plan Room.
 3. Deposit will be refunded upon return of usable and complete set of Bidding Documents within 45 days following receipt of bids to **A & D Technical Supply Co.** Documents returned by mail or parcel service shall be shipped postpaid.
 4. Check deposits by successful low bidder will be returned.

5.0 INFORMALITIES AND REJECTION OF BIDS

- A. Construction Manager/Owner reserves the right to waive any informality or irregularity, in any Bid, which does not materially affect the integrity or effectiveness of the competitive bidding process. Construction Manager/Owner further reserves the right to reject any or all bids and to re-advertise for Bids.

6.0 PRE-BID MEETING

- A. Prospective Bidders and Sub-bidders are invited to attend a pre-Bid meeting at the time and place indicated below:
1. Date and Time of Meeting: Thursday, January 5, 2012 at 1:30 PM CDT
 2. Place: UNL West Stadium 6th floor

END OF SECTION

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

UNL East Stadium

Bid Packages/Scope of work

Extent of Contract: Unless the Agreement contains a more specific description of the Work, names and terminology on Drawings and in Specification Sections determine which contract includes a specific element of Project.

1. Unless otherwise indicated, the Work described in this Section for each contract shall be complete systems and assemblies, including products, components, accessories, and installation required by the Contract Documents.
2. Local custom and trade-union jurisdictional settlements do not control the scope of the Work of each contract. When a potential jurisdictional dispute or similar interruption of work is first identified or threatened, affected contractors shall negotiate a reasonable settlement to avoid or minimize interruption and delays.
3. Trenches for the Work of each contract shall be provided by each contract for its own Work.
4. Within five (5) working days after preliminary horizontal bar-chart-type construction schedule submittal has been received from Project Coordinator, submit a matching preliminary horizontal bar-chart schedule showing construction operations sequenced and coordinated with overall construction.
5. Project closeout requirements.

Bid Package 5 –

NOTE TO ALL BIDDERS – Each bid package includes a complete scope of work.

Bidders will be responsible to include those items that can be reasonably inferred from this set of documents to provide a complete system and installation that is consistent with current codes, industry standards, and quality workmanship.

Bidders are welcome to submit details with their proposal to clarify systems or materials and products when more than one acceptable product or system may exist.

Bid Package 5A Exterior Improvements - Site PCC paving and sidewalks (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete exterior concrete paving, sidewalks and curb and gutter per the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Section 321313 Portland Cement Concrete Paving
- 321726 Tactile Warning Surfacing
- 033000 Reinforcing

Contract specifically includes, but is not limited to the following:

- Provide and install all fill material, reinforcing steel, concrete and expansion joints for exterior paving & sidewalks, integral curb. CIP steps, ADA ramps at building entrances are excluded. Please note that sidewalks north of approximately grid line 12.5 was bid in Bid package 3. This area should be excluded from this scope.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

- Provide all surveying, layout and staking as required
- Provide all grading to adjust from rough grading and provide all fill material required. Grade will be $\pm .2'$.
- Furnish and install bolsters or other accessories for reinforcing support as required for proper installation.
- Install all embedded items shown on drawings.
- Install Bollards as shown on the drawings (provided by others). Some bollards may be removable.
- Detectable warning pads to be provided and installed as specified. This contractor to ensure that ADA ramps meet current guidelines during layout and install.
- Provide clean-up of all materials and debris.
- Coordinate inspections and testing with inspection / testing agency.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5B Landscape (fine grade, trees and irrigation) (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete landscaping package, per the following:

Division 0 - as applicable
Division 1 - General Requirements of the contract as applicable
Sections 312219 Finish Grading
328400 Underground Sprinkler System
329200 Turf and Grasses
329300 Plant Materials

Contract specifically includes a complete landscape package, including but not limited to the following:

- A complete landscape package
- This scope of work includes all fine grading (including stone and rock removal from surface if required) for project site.
- Import of top soil for turf areas is required to achieve final grades.
- Soil amendments
- All decorative landscape materials
- Connection to existing UNL irrigation system is anticipated – see plans for locations and bidder/subcontractor is responsible to coordinate with UNL, understand connection points location, and requirements. This contractor will be responsible for any concrete removal /replacement or boring under existing walks or drives to connect to existing systems.
- Complete maintenance of landscape package as required by specifications.

Bid Package 5C Rough Carpentry (Labor and Materials)

Provide all labor, equipment, fasteners and supervision for:

Division 0 - as applicable
Division 1 - General Requirements of the contract as applicable
Sections 061000 Rough Carpentry

Contract specifically includes, but is not limited to the following:

- Provide all unloading, material handling except that hoisting of materials to the building floor levels will be provided by the construction manager.
- Provide all blocking and backing and fasteners as required for installation of other items required in the contract. This includes but not limited to backing for casework, counter top supports, TV/monitor locations, specialties, wall panels and wood trim.
- Furnish and install all roof blocking and backing for roof edges, mechanical curbs, and any roof openings to bring the installed item to the level of the roof insulation.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

Bid Package 5D Millwork/casework (Materials only)

Provide all material, fasteners and all other items necessary for:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 064023 Interior Architectural Woodwork
- 099300 Staining and Transparent Finishing

Contract specifically includes but is not limited to the following:

- Provide all Millwork, casework, and wall panel system and other items specified, delivered to job site to be unloaded and installed by others. From the specification summary paragraph 1.2 A, furnish items 1, 2, 3, 4, 9, 10, 11, 12, 13, 14, and 15.
- Includes counter top supports for all lavs, (tops may be granite, Plam, or solid surface as indicated on the drawings.)
- Note that shop finishing on interior woodwork is required per the specifications
- Includes stainless steel bar counter supports (Granite tops) in suites as shown on the drawings
- Fabricator required to field verify or be provided guaranteed dimensions as needed to meet project schedules.
- Provide onsite inventory of all materials when delivered to jobsite. Coordinate delivery with Finish Carpentry Contractor.

Bid Package 5E Finish Carpentry- Millwork, casework, Doors and hardware, Specialties (labor only)

Provide all labor, equipment, typical fasteners, supervision and other items necessary to install the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 064023 Interior Architectural Woodwork (install for all materials specified in this section excluding Solid Surface, Quartz Surfaces, Granite surfaces, and Stainless steel tops- these items to be installed by the provider in separate bid scopes)
- 079500 Interior Expansion Joint Cover assemblies
- 079513 Exterior Expansion Control
- 081113 Standard Steel Doors and Frames (install doors only)
- 081416 Flush Wood Doors (install doors only)
- 083113 Access Doors (install only)
- 087100 Door Hardware (install only for doors/frames in section 081113 and 081416)
- 102113 Toilet Compartments
- 102600 Wall and Door Protection
- 102800 Toilet and Bath Accessories
- 104413 Fire Extinguisher Cabinets
- 107516 Flagpoles
- 115213 Projection Screen

Contract specifically includes, but is not limited to the following:

- Provide all unloading, material handling except that hoisting of materials to the building floors will be provided by Construction Manager. Coordinate delivery of material with supplier for unloading and installing.
- Includes installation of counter top supports, and stainless steel bar top supports
- Receive, inventory and unload doors and hardware, millwork and casework, and all specialties provided by others. Provide signed inventory to Construction Manager that materials received match shop drawings and bill of lading.
- Install materials specified in sections above.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

Bid Package 5F Granite tops and sills (Labor and Materials)

Provide all labor, equipment, typical fasteners, supervision and other items necessary for the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 064023 Interior Architectural Woodwork

Contract specifically includes, but is not limited to the following:

- Furnish and install all granite tops and benches as shown on the drawings and specified in section referenced.
- Provide all unloading, material handling. Coordinate delivery of material with supplier for unloading and installing.
-
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5G Solid Surface and Quartz tops and sills (Labor and Materials)

Provide all labor, equipment, typical fasteners, supervision and other items necessary for the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 064023 Interior Architectural Woodwork

Contract specifically includes, but is not limited to the following:

- Furnish and install all Solid surface and Quartz tops, sills and benches as shown on the drawings and specified in section referenced.
- Provide all unloading, material handling. Coordinate delivery of material with supplier for unloading and installing.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5H Stainless Steel Tops (Labor and Materials)

Provide all labor, equipment, typical fasteners, supervision and other items necessary for the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 123553 Stainless Steel Work Surfaces

Contract specifically includes, but is not limited to the following:

- Furnish and install all stainless steel counter tops as shown on the drawings and specified in section referenced.
- Provide all unloading, material handling. Coordinate delivery of material with supplier for unloading and installing.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5I Waterproofing for split slab system (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 071326 Sheet Membrane Waterproofing

Contract specifically includes, but is not limited to the following:

- Provide waterproofing for split slab system as indicated on the drawings and specifications.
- Provide all unloading, material handling and hoisting of own materials.
- Provide clean-up of all materials and debris.
- Conduct water test to ensure system integrity prior to placement of topping slab.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

Bid Package 5J Insulation (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 072100 Thermal Insulation

Contract specifically includes, but is not limited to the following:

- This scope of work includes spray insulation as show on the contract drawings. This is insulation type 5 from the specifications
- Provide minor touch-up for damage during construction
- Coordinate work with all other Contractors
- Provide all unloading, material handling and hoisting of own materials.
- Provide clean-up of all materials and debris and protection of surfaces not to receive product.
- Conduct water test to ensure system integrity prior to placement of topping slab.

Superintendents or project managers will be required to attend weekly coordination meetings with other contractors

Bid Package 5K Joint sealants (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 079200 Joint Sealants

Contract specifically includes, but is not limited to the following:

- All building interior and exterior sealants, as well as all paving and sidewalk sealants.
- Sealants relating to aluminum/glass systems done by others.
- Provide all unloading, material handling and hoisting of own materials.
- Provide clean-up of all materials and debris.
- All color samples and color selections must be approved prior to commencing on site work
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5L Expansion Joints(interior & exterior) (material only)

Provide all material, fasteners and all other items necessary for:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 079500 Interior Expansion Joint Cover assemblies
- 079513 Exterior Expansion Control

Contract specifically includes but is not limited to the following:

- Provide all expansion joint materials for complete systems for interior and exterior, delivered to job site to be unloaded and installed by others (Installed under finish carpentry section).
- Coordinate delivery with Construction Manager and Finish Carpentry Contractor.

Bid Package 5M Doors/Frames and Hardware (includes hardware for Aluminum)(Material Only)

Provide all material, fasteners and all other items necessary for:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 081113 Standard Steel Doors and Frames (furnish only)
- 081416 Flush Wood Doors (furnish only)
- 087100 Door Hardware (furnish only. Includes hardware for Aluminum doors)

Contract specifically includes but is not limited to the following:

- Provide all hollow metal doors, frames, wood doors and hardware delivered to job site. To be unloaded and installed by others.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

- Include hardware for aluminum entrances and storefronts. Coordinate delivery of aluminum hardware with aluminum contractor, separate from other hardware.
- Provide all keying and coordinate keying with Owner.
- Provide onsite inventory of all finish hardware when delivered to jobsite. Coordinate Hardware delivery with Finish Carpentry Contractor. Signed inventory shall be provided to the Construction Manager at time of delivery
- Coordinate delivery of frames with drywaller and mason. Deliveries for frames in masonry walls to be separate from delivery of frames in metal stud walls.
- Coordinate delivery of Doors with Finish Carpentry Contractor.
- Coordinate hardware with power door operators (provided by glazing contractor).
- Coordinate hardware for access controlled door with Electronics Contractor (Electrical Contractor) for card access doors and monitored doors

Bid Package 5N Glass for borrowed lites (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

Division 0 - as applicable

Division 1 - General Requirements of the contract as applicable

Sections 079200 Joint Sealants (as it relates to borrowed lite installation)

088001 Interior Glass and Glazing

Contract specifically includes, but is not necessarily limited to the following:

- This scope includes all interior glass for doors and borrowed lites.
- Provide all layout of own work.
- Provide all caulking and sealants in the window system required
- Provide all equipment necessary for unloading and installation of this scope.
- Provide final cleaning of all surfaces at the completion of all construction activities.
- Clean-up of all materials and debris no less than every week (Friday).
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5P Coiling and Overhead Doors (Labor and Materials)

Provide all labor, material, equipment supervision and other items necessary for:

Division 0 - as applicable

Division 1 - General Requirements of the contract as applicable

Sections 083323 Rolling Counter Doors

083330 Insulated Overhead Coiling Service Doors

Contract specifically includes, but is not limited to the following:

- Provide all layout of own work.
- Provide all unloading, material handling and hoisting of own materials.
- Furnish and install any additional steel jambs or support /etc as recommended by the manufacturer for a complete system. If supports or framing are shown on contract drawings then this scope must coordinate to ensure that they are located correctly for the doors provided.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Coordinate all electrical work with Electrical Contractor. Provide any transformers or power supplies to ensure that doors and accessories work within building power and control systems.
- Provide fire alarm release devices as required by code to operate with building fire alarm system.
- Coordinate work with other trades.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

Bid Package 5Q Acoustical Ceilings (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

Division 0 - as applicable
Division 1 - General Requirements of the contract as applicable
Sections 095113 Acoustical Panel Ceilings

Contract specifically includes, but is not limited to the following:

- Provide all unloading, material handling and hoisting of own materials.
- Provide all layout of own work
- Coordinate installation of lay-in ceiling with all other trades.
- Provide clean-up of all materials and debris.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors

Bid Package 5R Tile (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

Division 0 - as applicable
Division 1 - General Requirements of the contract as applicable
Sections 093000 Tiling
079200 Joint Sealants

Contract specifically includes, but is not limited to the following:

- Provide and install all setting and grouting materials for floor and wall installation. Include filling joints in substrate for tile installation.
- Provide joint sealants in tile joints as required
- Provide /coordinate transitions between flooring as required. Each trade is responsible for their side of the transition.
- Provide all unloading, material handling and hoisting of own materials.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Coordinate layout of recessed slab with interior slab contractor.
- Coordinate layout of floor drains with Plumbing Contractor
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5S Carpet, Resilient Flooring, Linoleum Floor Coverings and Base (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

Division 0 - as applicable
Division 1 - General Requirements of the contract as applicable
Sections 096500 Resilient Flooring
096513 Resilient Base
096516 Linoleum Floor Coverings
096813 Tile Carpeting

Contract specifically includes, but is not limited to the following:

- Provide all unloading, material handling and hoisting of own materials.
- Provide floor prep required for installation of materials. Insure that all substrates are acceptable before installation of products.
- Provide or coordinate transition between flooring as required. Each trade is responsible for their side of the transition.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

Bid Package 5T Resinous Matrix Terrazzo Flooring (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 096623 Resinous Matrix Terrazzo Flooring

Contract specifically includes, but is not limited to the following:

- Provide all unloading, material handling and hoisting of own materials.
- Provide floor prep required for installation of materials
- Provide/ coordinate transition between flooring as required. Each trade is responsible for their side of the transition.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.
-

Bid Package 5U High performance coatings – wall and floor/Concrete Sealers (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 099601 Interior High-Performance Coatings
- 03 3000 Cast-in-Place Concrete (as it relates to concrete floor sealers)

Contract specifically includes, but is not limited to the following:

- Provide all unloading, material handling and hoisting of own materials.
- Provide floor prep required for installation of materials
- Provide/ coordinate transition between flooring as required. Each trade is responsible for their side of the transition.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5V Paint (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary to complete the following:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 099100 Painting
- 099300 Staining and Transparent Finishing
- 099600 High Performance Coatings

Contract specifically includes, but is not limited to the following:

- This package is for a complete wall and ceiling finish package and includes all painting or high performance coatings (excluding those specified in 099601 Interior High-Performance Coatings). This bidder/subcontractor should review other section to determine if items are shop finished or field finished.
- Lighting Fixture type HHH requires field finish of wood insert.
- This package includes painting and repainting of approximately 5500LF existing and revised guard rails at the existing Vomitories in east stadium concourse. Original color is gray, new color will be black.
- Provide all unloading, material handling and hoisting of own materials.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

Bid Package 5W Specialties (Materials)

Provide all material, fasteners and all other items necessary for:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 083113 Access Doors
 - 102113 Toilet Compartments
 - 102600 Wall and Door Protection
 - 102800 Toilet and Bath Accessories
 - 104413 Fire Extinguisher Cabinets
 - 107500 Flagpoles
 - 115213 Projection Screen

Contract specifically includes but is not limited to the following:

- Furnish all specialties as listed above. Bidders may submit by individual specification section or as packages. Insure that proposal is complete as contract will be written to supply per drawings and specifications, and not by specific quantity.
- Provide all access doors as indicated on plans, delivered to job site to be unloaded and installed by others (Installed under finish carpentry section).
- Ensure that any typical fasteners provided are compatible with the substrate materials are mounted to.
- Coordinate delivery with Finish Carpentry Contractor. Finish Carpentry Contractor will be responsible to conduct an inventory at delivery to ensure that quantities delivered match shop drawings and bill of laden. Any discrepancies will be reported for correction.

Bid Package 5X Signage (Labor and Materials)

Provide all labor, material, equipment supervision and other items necessary for:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Section 101400 Signage

Contract specifically includes, but is not limited to the following:

- Provide all unloading, material handling and hoisting of own materials.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5Y Dock Equipment (Labor and Materials)

Provide all labor, material, equipment supervision and other items necessary for:

- Division 0 - as applicable
- Division 1 - General Requirements of the contract as applicable
- Sections 111300 Loading Dock Equipment
 - 111319 Air Powered Levelers

Contract specifically includes, but is not limited to the following:

- This scope shall include all dock equipment shown and additional equipment as necessary to provide a complete, safe and operational dock including dock bumpers, dock lift, and necessary safety equipment.
- Provide all layout of own work.
- Provide all unloading, material handling and hoisting of own materials.
- Furnish and install any additional steel jambs/etc as recommended by the manufacturer for a complete system
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Coordinate all electrical work with Electrical Contractor.
- Coordinate work with other trades.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

SECTION 011200 – Summary of Multiple Subcontracts- Bid Packages

Bid Package 5Z Window Coverings (Labor and Materials)

Provide all labor, material, equipment, supervision and other items necessary for:

Division 0 - as applicable
Division 1 - General Requirements of the contract as applicable
Sections 122413 Roller Window Shades

Contract specifically include, but is not necessarily limited to the following:

- Provide all unloading, material handling and hoisting of own materials. Provide all field verification and coordination with other trades.
- Coordinate motorized shades with building power and controls systems. This contractor to provide transformers or power supplies to ensure that systems will function within the building systems.
- Provide clean-up of all materials and debris created during this scope to dumpster provided by others.
- Superintendents or project managers will be required to attend weekly coordination meetings with other contractors.

Bid Package 5AA Site Improvements (Bike loops) (material Only)

Provide all labor, material, equipment, supervision and other items necessary to complete landscaping package, per the following:

Division 0 - as applicable
Division 1 - General Requirements of the contract as applicable
Sections 129300 Site accessories

Contract specifically includes but not limited to the following:

- Furnish all site accessories as specified for installation by others
- Provide onsite inventory of all materials when delivered to jobsite. Coordinate delivery with Site Paving and Sidewalk contractor.

END OF SECTION