

## **ADDENDUM NO. 1**

Project: YRTC Boiler House Floor Replacement

Issued: January 11, 2012

This Addendum is issued to all known plan holders before receipt of proposals.

The following shall be included with, and considered a part of, the original contract documents to the same extent as if they were included therein, for the construction of the above mentioned project. The Project Manual and Drawings shall be modified or revised as herein described. Where at variance with the original work, this Addendum shall have precedence.

This Addendum modifies the original Bidding Documents. The Bidder must acknowledge receipt of this Addendum in the space provided on the Proposal Form. Failure to do so may subject bidder to disqualification.

**AD1-1:** Use of a curing compound is acceptable in lieu of wet curing if compound does not compromise the installation of the final sealant.

**AD1-2:** Clarification Sheet A1.0, Plumbing Fixture Schedule: Waste piping size shall be 3" at FD-1 and FS-1.

**AD1-3:** Remove existing light fixtures and conduit, protect and store in secure area. Reinstall light fixtures in new conduit after new concrete slab is set in place.

**AD1-4:** See attached page for Structural Addendum Items.

General Contractor shall acknowledge receipt of this Addendum on the Proposal Form in the space provided.

**END OF ADDENDUM NO. 1**

# ADDENDUM

---

**Date:** January 10, 2012

**Project:** Kearney YRTC Boiler Building Floor Replacement

---

The following items shall be included in the next addendum:

1. Reference detail A1/S1.0: Omit note "ON SELECTED SHORING METHOD" located above boxed note.
2. Reference detail A1/S1.0 – Shoring Detail: (2) ½" Epoxy Anchors shall be changed to **(2) ½" dia x 4" Simpson Titen HD Anchors, or equal.**
3. Reference detail A1/S1.0 – Base Plate Detail: 3/4" Epoxy Anchors shall be changed to **3/4" dia x 5" Simpson Titen HD Anchors, or equal.**
4. Reference detail A1/S1.0: Add the following note: **"ANCHOR HOLES IN FLOOR AND WALLS SHALL BE FILLED WITH NON-METALLIC, NON-SHRINK GROUT AFTER SHORING ANCHORS HAVE BEEN REMOVED"**
5. Reference detail A9/S1.0: Change note pointing to existing beam to **"EXISTING GIRDER"**.



**R. O.  
YOUKER  
INC.**

CONSULTING  
ENGINEERS

Michael D.  
Eisenbarth, P.E., S.E.

1201 O STREET  
SUITE 310  
LINCOLN, NE  
68508

PHONE  
402.477.7640  
FAX  
402.477.7631  
E-MAIL  
info@royouker.com