

Albion Maintenance Facility Re-Roof  
NDOR Building NO. 30501  
NDOR PN: AFE I-374 / APMA PN: 11109  
15 March 2012

2664 State Highway 39

This addendum is issued by the Owner to all known bidders prior to receipt of Proposal. Bidders shall acknowledge receipt of this Addendum by so indicating on the Proposal Form. All information and instruction given herein shall become a part of the Contract Documents.

This addendum contains the following information:

Addendum 001	8x11	1	Sheet
	Total	1	Sheet

If this addendum appears incomplete, notify the architect immediately.

### GENERAL INFORMATION

- A. Roofing makeup is noted on Detail F5/A4.1. Roof must have a minimum of 6" continuous insulation plus tapered insulation as required.
- B. Base layer of insulation must be mechanically fastened. Additional layers can be mechanically fastened OR adhered as indicated in the specification. The top layer of insulation and the membrane must be fully adhered using a manufacturer approved adhesive system. No Mechanical fasteners shall penetrate the roof. Installation must meet all performance requirements of specification.
- C. Based on meeting all specification requirements, Versico Versigard is an acceptable product.
- D. Based on meeting all specification requirements, UnaClad Delta panel CFP-16F is an acceptable product.

### PROJECT MANUAL

1. **SECTION 075323-2.4-D** thru **075323-2.4-G**. Remove references to fabric backed membrane. Membrane is not required to be fabric backed.
2. **SECTION 075323-2.4-F**. Revise references the term water based to read Low VOC adhesive.
3. **SECTION 075323-3.4-H**. Remove item #3 completely. All adhesive must be full spread or mopped on.
4. **SECTION 075323-3.4-H**. See General information for acceptable fastening / adhering of insulation layers. All installations must meet manufacturers standards for maintain warranties and meet all performance requirements of the specification.

### Drawings

1. None Required

### End of Addendum