

**ADDENDUM NO. 2**

**PROJECT NAME:** Manter Hall Window Replacement  
**UNL PROJECT NUMBER:** C101P113

**DATE OF ISSUANCE:** April 3, 2012

**DATE OF BID OPENING:** April 10, 2012

The bid documents dated **March 5, 2012** for the above referenced project are amended by this addendum.

NOTICE: This Addendum is issued to all interested prospective bidders as an amendment to the project manual or other parts of the bidding (contract) documents for the above named project. Reference to this Addendum must be included in the Bid proposal. The information contained herein shall be fully incorporated into the contract documents as though originally included therein.

---

**Additions:**

1. Technical Specifications; add Section 004513 that are attached.

**Specifications:**

2. Reference 015000, 1.2.B; Add the following:
  - a. 5. Entrances
3. Reference 015000, 2.2; Add the following:
  - a. K. ENTRANCE PROTECTION & EGRESS MAINTENANCE: Provide and maintain safe access and egress to and from the facility throughout project.
4. Reference 079200, 1.2, A, 1, a; Delete terracotta cornice and replace with Aluminum framing & perimeter conditions.
5. Reference 084113, 1.6, A; Replace with the following: Installer Qualifications: An installer which has had minimum 5 years successful experience with installation of the same or similar units required for the project and other projects of similar size and scope. Submit qualifications per Section 004513.
6. Reference 084113, 2.1, B, 084433, 2.1, B; Add Manko Window Systems.

ADDENDUM NO.

Project Name:

Project Number:

2 of 2

7. Reference 084113, 3.3, A, 084413, 3.3, A, 084432, 3.3, A; Replace with the following: Field Tests: Owners representative shall select curtain wall units to be tested as soon as a representative portion of the project has been installed, glazed, perimeter caulked and cured. Conduct tests for air infiltration and water penetration with manufacturer's representative present. Tests not meeting specified performance requirements and units having deficiencies shall be corrected as part of the contract amount.
  1. Testing: Testing shall be performed by a qualified vendor representative.
    - a. Water Infiltration Tests: Conduct field tests in accordance with AAMA 501.2-03. No uncontrolled water leakage is permitted when tested at 30 psi.

Include these documents and revisions to evaluate and present your Bid Proposals for the Manter Hall Window Replacement Project (C101P113).

END OF ADDENDUM NO. 2