

- 5) Remove 20'-0" x 37'-0" existing concrete slab up to the existing building on north side of existing building. Replace with 4'-1" x 37'-0" new concrete sidewalk paving next to existing building. Include an expansion joint at each end where new concrete abuts existing concrete sidewalks. Include expansion joint adjacent to existing building. See sheet A100 for location.

BB-3, ITEM #3: Drawing Sheet A100

ALTERNATE NO. 1 CONDITION:

- 1) Demolition Notes #1 through #6 and Note #8 pertain to Alternate No. 1 only.

MECHANICAL AND ELECTRICAL BID BULLETIN ITEMS WILL FOLLOW THE ARCHITECTURAL AND ARE FORMATTED SEPERATLY.

END OF BB-3, See Attached

Date: June 11, 2012 **Date of Issuance:** May 2012
Project Name: Mullen High School / Jr. High 2012 Gymnasium Additions, Mullen, Nebraska **Date of Opening:** June 14, 2012
FE Project No.: 124007

NOTICE: This addendum is applicable to the referenced project and is issued to all known planholders prior to receipt of proposals. The information contained herein shall be fully incorporated into the Bid Contract Documents as though originally incorporated. Failure to acknowledge all amendments may be cause for rejection of the bid.

TO: Bidders and Others Concerned

Changes to the Project Manual

No Changes to the Project Manual

Changes to the Drawings

1. SHEET NUMBER M600 – MECHANICAL SCHEDULES: GAS FIRED ROOFTOP UNIT SCHEDULE -
 - A. Add Remark No. 13 to read as follows:

13. Furnish a 24-inch vibration isolation roof curb with 2-inch deflection springs, for rooftop units RTU-1 and RTU-2.

2. SHEET NUMBER P100 – PLUMBING RENOVATION PLAN:
 - A. Under the base bid and alternate bid, all sanitary sewer and vent piping shown in the areas of the present/future corridor and locker rooms shall conform to the piping material requirements in specifications section 22 10 00-3.B Underground Building Drain and Storm Piping.

3. SHEET NUMBER P101 – STORM DRAINAGE RENOVATION PLAN:
 - A. Under the base bid and alternate bid, all storm piping shown in the areas of the present/future corridor and locker rooms shall conform to the piping material requirements in specifications section 22 10 00-3.B Underground Building Drain and Storm Piping.

Clarifications

1. N/A.

Attachments

1. N/A.

Miscellaneous

1. N/A.

--END--