
ADDENDUM NO. 2

PROJECT NAME: Center for Brain, Biology and Behavior

UNL PROJECT NUMBER: C049P137

DATE OF ISSUANCE: July 17, 2012

DATE OF BID OPENING: July 24, 2012

The bid documents dated **June 28, 2012** for the above referenced project are amended by this addendum.

NOTICE: This Addendum is issued to all interested prospective bidders as an amendment to the project manual or other parts of the bidding (contract) documents for the above named project. Reference to this Addendum must be included in the Bid proposal. The information contained herein shall be fully incorporated into the contract documents as though originally included therein.

GENERAL:

Item 2-1: Work Schedule

Work for the CB3 project will need to coincide with the schedule of Sampson Construction to complete the East Stadium Addition. A copy of that Schedule will be provided to the contractor awarded the work for the CB3 area. The Contractor will not be allowed to work on UNL home football game days nor the afternoon before the home game. Work on the CB3 area is expected to start around August 15th, 2012. The south dock is planned to be completed by mid-August and the entire east stadium addition will be enclosed by November 1, 2012. Delays caused by Sampson Construction may justify delays in the CB3 project.

Item 2-2: MRI Coordination

Final MRI Installation Drawings are attached for the purpose of coordination. The Contractor will be responsible to coordinate delivery and installation, including, but not limited to, sequencing of building construction, removal of barriers, and construction of temporary ramps and access (if required) necessary for the delivery and placement of the unit. The Contractor shall provide and install equipment as indicated in the contract documents in support of the MRI installation. Additionally, the Contractor shall ensure that Site Readiness Guidelines as set forth in the attached document are met.

Item 2-3: General Note for All Specifications

It shall be the responsibility of all manufacturers listed within the project manual to provide documentation that they meet all specification requirements as part of the shop drawing process. If manufacturer cannot meet all requirements, manufacturer shall either manufacture custom products to do so or not bid on the work. By bidding the

work, it shall indicate that manufacturer is aware of all requirements and agree to be in full compliance with all specification and drawing requirements. This shall include all manufacturers approved by addendum.

Item 2-4: General Note for all Partition and Dimension Plans (A1.2, A1.7, A1.10)

Walls indicated as half-tone and without wall type designation are provided under previous project. Painting and installation of finishes are provided under this contract in accordance with sheets F1.1 through F1.4.

The walls along the interior atrium (west walls of the CB#3 area will need to be designed for wind loads.

Item 2-5: GENERAL ELECTRICAL QUESTIONS

Is there a fire alarm specification?

No, there is no specification. All fire alarm devices must be compatible with the Siemens fire alarm system which is installed in the East Stadium Bid Package #4.

Where is the existing Generator located?

The Generator provided under the East Stadium Bid Package #4 is located southeast of South Stadium.

What type of gear are they installing under the East Stadium Bid Package #4? The drawings call for a 225 3P circuit breaker in existing distribution panel 'DP-SER'.

The circuit breaker being added must be fully compatible with the GE SBO Panelboard. Verify the circuit breaker does not void the UL listing or the fault current rating of the panelboard.

SPECIFICATION CHANGES:

Volume 1 of 2:

Item 2-6: Section 00 41 13 – BID PROPOSAL FORM

Contractor shall indicate either "ADD" or "DEDUCT" in addition to dollar amount for each Addendum indicated on the Bid Proposal Form.

CLARIFICATION- Alternate No. 1 involves only the modifications to the NORTH COORIDOR 300A. The West and North walls are modified as well as removal of door 300A.1 and the wall separating the SKYBRIDGE 300 area.

Item 2-7: Section 06 40 23 – INTERIOR ARCHITECTURAL WOODWORK

2.1.G Quartz-Surfacing Material.

Approved Products. Subject to compliance with all specified requirements and approval of samples, the following are approved manufactures for Quartz-Surfacing Material:

- Silestone, (866)801-2425

Item 2-8: Section 08 14 16 – FLUSH WOOD DOORS

2.1.A Approved Products. Subject to compliance with all specified requirements and approval of samples, the following are approved manufactures for Flush Wood Doors:

- Oshkosh Door Company, Oshkosh, WI, (920)233-6161

Item 2-9: Section 09 29 00 – GYPSUM DRYWALL

2.10.A Gypsum Board Screws. Add the following subparagraph:

1. Provide non-ferromagnetic fasteners appropriate for use in an MRI room for areas contained within MRI RF-Shielded Enclosure (MRI EXAM 180AA)

Item 2-10: Section 10 28 00 – TOILET AND BATH ACCESSORIES

2.1.A Approved Products. Subject to compliance with all specified requirements and approval of samples, the following are approved manufactures for Toilet and Bath Accessories:

- American Specialties, Inc. Yonkers, NY, (914) 476-9000

Item 2-11: Section 10 50 50 – PHENOLIC LOCKERS

2.1.A Approved Manufacturers. Subject to compliance with all specified requirements and approval of samples, the following are approved manufactures for Phenolic Lockers:

- PSISC. Columbia, SC, (866) 337-7286.
- ASI Storage Solutions. Eastonollee, GA, (706) 827-2720
- Summit Lockers, Columbia, SC, (888) 310-7149

Item 2-12: Section 12 24 13 - ROLLER WINDOW SHADES

2.2.I Refer to paragraph 2.2.I Shadecloth materials:
Replace subparagraphs 1.a with the following

a. Style: Eurotwill Reversible Weave 6000 Series (+/- 3% Openess) Color: 6009 Dove Grey.

Item 2-13: Section 12 24 13 - ROLLER WINDOW SHADES

2.2.I Refer to paragraph 2.2.I Shadecloth materials:
Replace subparagraphs 2.a with the following

a. Style: Equinox Blackout 0100 Series (opaque) Color: 0106 Dusk.

Item 2-14: Section 12 35 54 – WOOD LABORATORY CASEWORK AND FIXTURES

2.1.A Approved Manufacturers. Subject to compliance with all specified requirements and approval of samples, the following are approved manufactures for Wood Laboratory Casework and Fixtures:

- Mott Manufacturing, Maxwelton, WV, (304) 497-2115
- Diversified Woodcrafter, Inc., Suring, WI, (877) 348-9663

Item 2-15: Section 13 34 01 – MRI, RF SHIELDED ENCLOSURE

2.1 Approved Manufacturers. Subject to compliance with all specified requirements and approval of samples, the following are approved manufactures for MRI RF Shielded Enclosure:

- Universal Shielding Corp., Deer Park, NY, (631) 667-7912
- MRI Corporation, Costa Mesa, CA, (714) 545-7701
- Shielding Dynamics Inc., Tomball, TX, (281) 290-8351

Item 2-16: Section 13 34 01 – MRI, RF SHIELDED ENCLOSURE

2.3 Refer to Paragraph 2.3 MAGNETIC MATERIALS. Magnetic Shielding shall be provided and installed by RF shielding supplier per attached calculations provided by MR vendor.

Volume 2 of 2:

Item 2-17: Section 26 51 00 – LIGHTING FIXTURES

The following lighting fixtures have been reviewed in accordance with paragraph 2, and are included in the Contract Documents for bidding purposes. All fixtures, lamps, and ballasts are required to meet the specification requirements regardless of prior approval. Prior approval does not waive any requirements indicated on the drawings or the specifications. Some fluorescent fixtures require dimming or multiple levels of switching. The required number and types of ballasts shall be provided to meet the switching requirements shown on the drawings.

<u>Type</u>	<u>Manufacturer and Catalog Number</u>	
Type A	COLUMBIA	SER24-232G-RF-11EU
Type B	COLUMBIA	SER24-332G-RF-EU
Type K	WILLIAMS	20-4-232-A-EB8P2-UNV
	COOPER	BC-232-UNV-ER81-U
Type L	LITHONIA	WC232-MVOLT-GEB10PS
	AXIS	BBR-S-FL-8-T8-2-W-UNV-ERS-1-TB9
	LITE CONTROL	LG-D-4424T8-SGL-CWM-IND-ELB-1CWQ
Type M	CORELITE	Z3-WD-1L35-1C-UNV-24-T9
Type N	KIRLIN	MRR 06216 W/LPS 1220A W/RFI 3100D
Type T	COLUMBIA	SER22-217G-RF-EU

ADDENDUM NO. 2

Project Name: Lied Center HVAC Improvements

Project Number: C131P037

5 of 7

Item 2-18: Section 26 51 01 – LIGHTING CONTROL SYSTEM

HUBBELL is the only allowed manufacturer.

DRAWING CHANGES:

Item 2-19: Sheet G1.1 – CONCOURSE LEVEL LIFE SAFETY PLAN, MEZZANINE LEVEL LIFE SAFETY PLAN AND CODE DATA

Refer to CODE REQUIREMENTS

Add General Note. "Existing structural frame includes spray applied fire protection. Contractor shall be responsible to repair or replace areas of spray applied fireproofing damaged or compromised as a result of work of this contract. Rating of system shall be as indicated in CODE REQUIREMENTS table."

Item 2-20: Sheet A1.2 – CONCOURSE LEVEL PARTITION AND DIMENSION PLAN

Refer to WALL TYPE SCHEDULE. Refer to wall type tag 6A. In description delete reference to 20 GA studs. Studs shall be sized to accommodate lateral wind load of 10 PSF. Change shall apply to all instances of wall type "6A"

Item 2-21: Sheet A1.4 – MECHANICAL MEZZANINE PLAN

Refer to PARTIAL MECHANICAL MEZZANINE PLAN. Locate MRI quench vent and louver as indicated in attached supplemental drawing SDA-1, dated July 17, 2012. Coordinate requirements with mechanical plans.

Item 2-22: Sheet A1.4 – MECHANICAL MEZZANINE PLAN

Add detail 2 – QUENCH VENT DISCHARGE SECTION as indicated in attached supplemental drawing SDA-2, dated July 17, 2012.

Item 2-23: Sheet A1.4 – MECHANICAL MEZZANINE PLAN

Add detail 3 – MECHANICAL PENETRATION DETAIL as indicated in attached supplemental drawing SDA-3, dated July 17, 2012.

Item 2-24: Sheet A5.1 – ENLARGED STAIR PLAN, SECTIONS, AND DETAILS

Refer to detail 1 SECOND LEVEL STAIR PLAN. Add supplemental support framing as indicated in attached supplemental drawing SDA-4, dated July 16, 2012.

Item 2-25: Sheet A5.1 – ENLARGED STAIR PLAN, SECTIONS, AND DETAILS

Refer to detail 2 STAIR SECTION. Add annotations as indicated in attached supplemental drawing SDA-5, dated July 17, 2012.

ADDENDUM NO. 2

Project Name: Lied Center HVAC Improvements

Project Number: C131P037

6 of 7

Item 2-26: Sheet A5.1 – ENLARGED STAIR PLAN, SECTIONS, AND DETAILS

Add detail 9 – STRINGER SUPPORT DETAIL as indicated in attached supplemental drawing SDA-6, dated July 17, 2012.

Item 2-27: Sheet A5.1 – ENLARGED STAIR PLAN, SECTIONS, AND DETAILS

Add detail 10 – LANDING SUPPORT DETAIL as indicated in attached supplemental drawing SDA-7, dated July 17, 2012.

Item 2-28: Sheet A5.1 – ENLARGED STAIR PLAN, SECTIONS, AND DETAILS

Add detail 12 – LANDING SUPPORT DETAIL as indicated in attached supplemental drawing SDA-8, dated July 17, 2012.

Item 2-29: Sheet A6.1 – CONCOURSE LEVEL ENLARGED PLANS AND INTERIOR ELEVATIONS

Refer to Detail 2 MRI SUITE RF ENCLOSURE SECTION.

Refer to note “RF SHIELD ENCLOSURE, SEE SPECIFICATIONS” Leader arrow indicated at finished ceiling shall point to upper plane, designated as T.O. RF ENCLOSURE – El. 10'-0" AFF.

Add Note: “All ceiling hangers and supports shall be non-ferromagnetic as appropriate for installation in an MRI room.”

Item 2-30: Sheet A6.7 – ENLARGED RESTROOM PLANS AND INTERIOR ELEVATIONS

Refer to detail 1 – ENLARGED RESTROOM PLAN – CONCOURSE LEVEL. Relocate wall hung lavs to ensure ADA clear floor clearances as indicated in attached supplemental drawing SDA-9, dated July 17, 2012.

Item 2-31: Sheet A9.2 – ALUMINUM STOREFRONT ELEVATIONS. INTERIOR ALUMINUM FRAMING SYSTEMS (ALTERNATE #4) AND DETAILS

Refer to 1-HOUR RATED ALUMINUM STOREFRONT ELEVATIONS. Delete reference to “1-HOUR”. Aluminum storefront system is not fire rated. Refer to Section 08 41 13 ALUMINUM ENTRANCES AND STOREFRONTS.

Item 2-32: Sheet A9.2 – ALUMINUM STOREFRONT ELEVATIONS. INTERIOR ALUMINUM FRAMING SYSTEMS (ALTERNATE #4) AND DETAILS

Refer to INT. ALUM. FRAME AL-20. Change dimension above door opening from “4-10” to “7'-0”.

Delete reference to “ALUMINUM TOP HUNG BARN DOOR. Add note “PROVIDE STANDARD TOP HUNG ALUMINUM SLIDING DOOR (7'-0” W x 8'-0” H) WITH TYPICAL HARDWARE BY WILSON PARTITIONS OR APPROVED EQUAL”

ADDENDUM NO. 2

Project Name: Lied Center HVAC Improvements

Project Number: C131P037

7 of 7

Item 2-33: Sheet M6.2 – MECHANICAL SCHEDULES

Refer to Pump Schedule. Change the following items:

Motor RPM: 1750

HP: 3

Mfr & Model: B&G SERIES 80

Size: 1-1/2 x 1-1/2 x 9-1/2

Remark 4: BRONZE-FITTED CONSTRUCTION

Item 2-34: Sheet E2.1 – MAIN CONCOURSE POWER & AUXILIARY SYSTEMS PLANS

Refer to the "Enlarged MRI Suite Plan.

Transformer 'T-SBMRI' shall be moved to behind the door of Instrumentation Room 180BA.

The transformer shall be located 6" off the east wall and 6" off the north wall.

Panelboard 'L-SBMRI shall be moved to the north wall of Instrumentation Room 180BA.

The panel shall be located 4" to the east of the moved Transformer 'T-SBMRI'.

Item 2-35: Sheet E4.1 – ELECTRICAL SCHEDULES

Refer to Light Fixture Schedule:

Change Type U to a Columbia catalog number: LF6LED277V-6FLED735K-B24

END OF ADDENDUM NO. 2

E-Mail

USA, Malvern
SMS, SI PROJECT PLANNING

Mr. Caruso

Phone : +1 (440) 357-8842
FAX : +1 (440) 357-8850

frank.caruso@siemens.com

intern

Healthcare Sector

Name Klaus Probst
Department H CX CRM-VA TP PM
Location Erl N
Phone ++49 9131 84 7594
FAX ++49 9131 8413 7594
E-Mail Klaus.Probst@siemens.com
Code
Date 25.06.2012

LINCOLN (NE), Univeristy of Nebraska
400-9000001917-MR01-FKP-01 OR99 Skyra

- Magnet support on Stop-Choc
- Magnet support on Sylomer



Dear Mr. Caruso,


enclosed you can find the shield dimensions and fringe field distribution for a. m. project.
The total weight of the shield without joints and support frame is 3651 lbs M36 .
The enclosed txt or dwg files can be used to import the fringe field distribution into a CAD drawing.

Best regards

K. Probst

internal remarks

Probst 25.06.2012	Probst 25.06.2012		RMS = 0.938998%	Heinrich 25.06.2012	
Bearbeiter	Review	Sign.	Estimated error in B Field	Freigabe	Sign.
Forces on all coils in X : 0 N in Y : -1124 N in Z : -1117 N					



UNITS	
Length	m
Magn Flux Density	T
Magn Field	A m ⁻¹
Magn Scalar Pot	A
Magn Vector Pot	Wb m ⁻¹
Elec Flux Density	C m ⁻²
Elec Field	V m ⁻¹
Conductivity	S m ⁻¹
Current Density	A m ⁻²
Power	W
Force	N
Energy	J
Mass	kg


MODEL DATA	
OR99_Lincoln_Un0n_01-1.op3	
TOSCA Magnetostatic	
Nonlinear materials	
Simulation No. 1 of 1	
300672 elements	
583157 nodes	
12 conductors	
Nodally interpolated fields	
Activated in global coordinates	
Reflection in YZ plane (X field=0)	

Field Point Local Coordinates	
Local = Global	

FIELD EVALUATIONS	
Cartesian (nodal)	100x150 Cartesian
x=0.0	y=6.0 to -6.0
z=9.0 to -9.0	
Fit	FIT (integral) 32x32 Spherical
r=0.25	φ=0.0 to φ=0.00429792 to 6.283185 3.137295


OR99_Lincoln_UoN_01-1.op3
Fringe Field Lines :

- 0,05 mT
- 0,15 mT
- 0,2 mT
- 0,5 mT
- 1 mT
- 5 mT
- 10 mT




OR99_Lincoln_UoN_01-1.op3
Fringe Field Lines :

- 0,05 mT
- 0,15 mT
- 0,2 mT
- 0,5 mT
- 1 mT
- 5 mT
- 10 mT



OR99_Lincoln_UoN_01-1.op3
Fringe Field Lines :

- 0,05 mT
- 0,15 mT
- 0,2 mT
- 0,5 mT
- 1 mT
- 5 mT
- 10 mT




Rearwall at Z = -230 cm (-7'-6 1/2")

magnetic flux in XY direction

Material : M36

Weight : 1272 kg (2804 lbs)





Floorplate at Y = -110 cm (-3'-7 1/4")

magnetic flux in Z direction

Material : M36

Weight : 384 kg (847 lbs)





PARTIAL MECHANICAL MEZZ. PLAN REV.

SCALE: 1/8" = 1'-0"



The
Clark
Enersen
Partners

Architecture + Landscape Architecture + Engineering + Interiors
1010 Lincoln Mall, Suite 200 Lincoln, NE 68508-2883
402 477.9291 Fax 402 477.6542
Kansas City, Missouri

www.clarkenersen.com

UNL East Stadium Center for Brain, Biology and Behavior
Lincoln, NE
TCEP No: 018-184-11

Addendum #2
Supplemental Drawing: SDA-1
Revision of Sheet: A1.4
Date: 07/17/12

A
002

CUT REGLET INTO EXISTING
PRECAST MANEL TO
RECEIVE TRIM FLASHING


SEALANT AT TRIM PERIMETER

PREFINISHED ALUMINUM
FLASHING/TRIM WITH MITERED
CORNERS ALL SIDES OF OPENING

⊕ CENTER OF LOUVER
EL. 107'-6 3/4"

PREFINISHED ALUMINUM LOUVER
SEE MECHANICAL DRAWINGS

EXISTING PRECAST CONCRETE
WALL PANEL. MODIFY AS
REQUIRED TO RECEIVE NEW
LOUVER



EXISTING WALL CONSTRUCTION.
MODIFY AS REQUIRED FOR
INSTALLATION OF LOUVER AND
QUENCH VENT DISCHARGE
ASSEMBLY

QUENCH VENT DISCHARGE OUTLET.
COORDINATE REQUIREMENTS WITH
QUECN VENT SUPPLIER

SEALANT WITH BACKER ROD AT
PERIMETER OF PENETRATION

DIMENSIONS LOCATING LOUVER ARE
APPROXIMATE. CENTER LOUVER BETWEEN
RUSTICATION/PANEL JOINTS IN BOTH DIRECTIONS

2 QUENCH VENT DISCHARGE SECTION

SCALE: 1" = 1'-0"



The
Clark
Enersen
Partners

Architecture + Landscape Architecture + Engineering + Interiors
1010 Lincoln Mall, Suite 200 Lincoln, NE 68508-2883
402 477.9291 Fax 402 477.6542
Kansas City, Missouri

www.clarkenersen.com

UNL East Stadium Center for Brain, Biology and Behavior
Lincoln, NE

TCEP No: 018-184-11

Addendum #2
Supplemental Drawing: SDA-2
Revision of Sheet: A1.4
Date: 07/17/12

NOTE:

COORDINATE ALL MECHANICAL OPENING SIZES, LOCATIONS, AND QUANTITIES WITH ARCHITECTURAL FLOOR PLANS AND MECHANICAL CONTRACTOR




VERIFY OPENING WITH MECH.

NOTE:

INSTALL 5"x5" ANGLES CENTERED BENEATH NEAREST DECK VALLEY TO EDGE OF SLAB PENETRATION

EXISTING CONCRETE SLAB. INSTALL ALL ANGLES BENEATH SLAB BEFORE CORE DRILLING SLAB



3 MECH PENETRATION DETAIL

SCALE: 1 1/2" = 1'-0"




The Clark Enersen Partners

Architecture + Landscape Architecture + Engineering + Interiors
1010 Lincoln Mall, Suite 200 Lincoln, NE 68508-2883
402 477.9291 Fax 402 477.6542
Kansas City, Missouri

www.clarkenersen.com

UNL East Stadium Center for Brain, Biology and Behavior
Lincoln, NE
TCEP No: 018-184-11

Addendum #2
Supplemental Drawing: SDA-3
Revision of Sheet: A1.4
Date: 07/17/12




2 PARTIAL STAIR SECTION - REVISED

SCALE: 1/2" = 1'-0"

UNL East Stadium Center for Brain, Biology and Behavior
UNL City Campus
Lincoln, NE
TCEP No.: 018-184-11

Addendum #2
Supplemental Drawing: SDA-5
Revision of Sheet: A5.1
Date: 07/16/12

A
002



9 STRINGER SUPPORT DETAIL

SCALE: 1 1/2" = 1'-0"




The
Clark
Enersen
Partners

Architecture + Landscape Architecture + Engineering + Interiors
1010 Lincoln Mall, Suite 200 Lincoln, NE 68508-2883
402 477.9291 Fax 402 477.6542
Kansas City, Missouri

www.clarkenersen.com

UNL East Stadium Center for Brain, Biology and Behavior
Lincoln, NE
TCEP No: 018-184-11

Addendum #2
Supplemental Drawing: SDA-6
Revision of Sheet: A5.1
Date: 07/17/12




The
Clark
Enersen
Partners

Architecture + Landscape Architecture + Engineering + Interiors
1010 Lincoln Mall, Suite 200 Lincoln, NE 68508-2883
402 477.9291 Fax 402 477.6542
Kansas City, Missouri

www.clarkenersen.com

UNL East Stadium Center for Brain, Biology and Behavior
Lincoln, NE
TCEP No: 018-184-11

Addendum #2
Supplemental Drawing: SDA-7
Revision of Sheet: A5.1
Date: 07/17/12



12

LANDING SUPPORT CONNECTION DETAIL

SCALE: 1 1/2" = 1'-0"




The
Clark
Enersen
Partners

Architecture + Landscape Architecture + Engineering + Interiors
1010 Lincoln Mall, Suite 200 Lincoln, NE 68508-2883
402 477.9291 Fax 402 477.6542
Kansas City, Missouri


www.clarkenersen.com

UNL East Stadium Center for Brain, Biology and Behavior
Lincoln, NE
TCEP No: 018-184-11

Addendum #2
Supplemental Drawing: SDA-8
Revision of Sheet: A5.1
Date: 07/17/12



4 **REVISED INTERIOR ELEVATION - T/C 180 E - A**
 SCALE: 3/8" = 1'-0"



1 **REVISED ENLARGED RESTROOM PLAN - CONCOURSE LEVEL**
 SCALE: 1/4" = 1'-0"



The Clark Enersen Partners
 Architecture
 Landscape Architecture
 Engineering
 Interiors

www.clarkenersen.com

Lincoln, Nebraska
 1010 Lincoln Mall, Suite 200
 Lincoln, NE 68508-2883
 402 477.9291 Fax 402 477.6542

Kansas City, Missouri

UNL East Stadium Center for
 Brain, Biology and Behavior
 UNL City Campus
 Lincoln, NE
 TCEP No.: 018-184-11

Addendum #2
 Supplemental Drawing: SDA-9
 Revision of Sheet: A6.7
 Date: 07/17/12

UNIVERSITY OF NEBRASKA - LINCOLN

Memorial Stadium - East Addition

Lincoln, NE 68583

MAGNETOM SKYRA W/FIXED TABLE



Contents:

Sheet No.	Description
A-101	EQUIPMENT PLAN - DETAILS, LEGEND AND NOTES
A-102	SAFETY / SERVICE CLEARANCE PLAN
A-501	FILTER PANEL / CABINET DETAILS
A-502	DETAILS AND NOTES
S-101	STRUCTURAL PLAN - DETAILS AND NOTES
E-101	ELECTRICAL PLAN - LEGEND AND NOTES
E-102	ELECTRICAL PLAN
E-501	ELECTRICAL DIAGRAMS, DETAILS AND NOTES
M-101	MECHANICAL PLAN - CHILLED WATER AND ENVIRONMENTAL
M-501	QUENCH VENT SPECIFICATIONS

Project Contacts:

Siemens
Project Manager
Jim Wilthrow
Phone: (402) 960-7654
Voice Mail: (800) 228-5462 Ext: 1227
jwilthrow@cassling.com

Planner
Dwayne Bristoe

Project #: 1201431

SIEMENS
SIEMENS MEDICAL SOLUTIONS
51 Valley Stream Parkway
Malvern, PA 19355
www.usa.siemens.com/medical


THIS SET OF FINAL DRAWINGS IS REFLECTIVE OF THE LATEST SALES CONFIGURATION. ANY CHANGES TO THIS SALES CONFIGURATION MAY REQUIRE A REVISION TO THIS PROJECT PLAN. IF REQUESTED, SIEMENS WILL PRODUCE A REVISED SET OF FINAL DRAWINGS TO REFLECT THE CHANGES, HOWEVER SIEMENS IS NOT RESPONSIBLE FOR ANY CONSTRUCTION COSTS ASSOCIATED WITH THE CHANGES THAT OCCUR FROM THIS PLAN MODIFICATION.

QUENCH VENT SPECIFICATIONS:
THE QUENCH VENT REQUIREMENTS AND SPECIFICATION DETAILED ON SHEET M-501 MUST BE MET.

IF A CLOSET IS DESIRED TO CONCEAL THE FILTER PLATE ITEM #9 AND CABLE CONNECTIONS, IT IS TO BE DESIGNED, SPECIFIED AND PROVIDED BY THE CUSTOMER OR THEIR REPRESENTATIVE. A 30 1/4" CLEARANCE IS REQUIRED FOR SERVICE AND CABLING. COORDINATE WITH SIEMENS PROJECT MANAGER.

CHILLER TO BE SUPPLIED, LOCATED AND INSTALLED BY CUSTOMER/CONTRACTOR. REFER TO MANUFACTURER'S INFORMATION.

TABLE OR SHELF TO SUPPORT 200 POUNDS TO BE DESIGNED, SUPPLIED AND INSTALLED BY THE CUSTOMER/CONTRACTOR.



THE 0.5mT FIELD SHOULD BE RESTRICTED FROM INDIVIDUALS WITH PACEMAKERS AND INSULIN PUMPS. IT IS NECESSARY TO DISPLAY WARNING SIGNS AND RESTRICT ACCESS IN ACCORDANCE WITH LOCAL REGULATIONS.

IT IS THE RESPONSIBILITY OF THE CUSTOMER/CONTRACTOR TO PROVIDE A MEANS OF MOUNTING THE PC TOWER OFF OF THE FINISHED FLOOR FOR DAMAGE PROTECTION AGAINST TIP OVER, FLUIDS, IMPACT, ETC. ADDITIONAL MOUNTING IS NOT NECESSARY IF SIEMENS CONTAINER IS UTILIZED.

ARCHITECTURAL EQUIPMENT PLAN

SCALE: 1/4" = 1'-0"

ROOM MEASUREMENTS
ALL ROOM MEASUREMENTS AND ROOM DETAIL SPECIFICATIONS MUST BE VERIFIED ON SITE PRIOR TO BEGINNING ANY CONSTRUCTION WORK.

STATIC DISSIPATIVE FLOORING
SIEMENS RECOMMENDS "STATIC DISSIPATIVE" FLOOR COVERING WITH AN ELECTRICAL RESISTANCE OF $\times 10^9$ OHMS IN ALL AREAS WHERE SIEMENS EQUIPMENT IS INSTALLED. A STATIC DISSIPATIVE FLOOR REDUCES THE RISK OF STATIC ELECTRIC DISCHARGES THAT MAY DAMAGE SENSITIVE EQUIPMENT AND COMPONENTS.

NOISE LEVELS

SYSTEM ROOM	NOISE LEVEL / dB(A)
CONTROL ROOM	<55
EXAMINATION ROOM	88.3 dB(A) - 8 HOUR AVERAGE 106 dB(A) MAXIMUM
EQUIPMENT ROOM	<65

STATE AGENCY REVIEW
PRIOR TO SIEMENS EQUIPMENT INSTALLATION, APPROVAL OF CONSTRUCTION OR STRUCTURAL MODIFICATIONS UTILIZING X-RAY FOR DIAGNOSTIC OR THERAPEUTIC PURPOSES, MUST BE OBTAINED BY THE CUSTOMER FROM THE APPROPRIATE STATE AGENCY, IF APPLICABLE.

TRANSPORTING REQUIREMENTS
LARGEST ITEM - MAGNET - 15,652 LBS.
MAGNET DIMENSIONS WITH TRANSPORT DEVICE:
7'-7" HIGH x 7'-7" WIDE x 5'-11" DEEP (6'-10" WITH SUPPORT)
THE ROOF HATCH/DELIVERY OPENING SHOULD BE 4" LARGER.

IT IS THE CUSTOMER'S RESPONSIBILITY TO ENSURE THAT ALL LOCAL/STATE/OSHA NOISE REGULATIONS ARE ADHERED TO. ADDITIONAL NOISE DATA MAY BE PROVIDED BY SIEMENS PROJECT MANAGER UPON REQUEST.

CEILING HEIGHTS
MAGNET EXAMINATION ROOM: 7'-11" MINIMUM
EQUIPMENT ROOM: 7'-3" MINIMUM WITH RESTRICTION
ALL ANCILLARY AREAS: 6'-11" MINIMUM

CASEWORK & ACCESSORY NOTES

- ALL CASEWORK IS EITHER EXISTING OR IS TO BE DESIGNED, DETAILED, FURNISHED AND INSTALLED BY THE CUSTOMER AND/OR CONTRACTOR. FOLLOW DESIGN RECOMMENDATIONS INCLUDED HEREWITH, AS THEY ARE ESSENTIAL FOR THE SUCCESSFUL INSTALLATION & OPERATION OF THE SIEMENS EQUIPMENT.
- ALL FURNITURE (CHAIRS, ETC.) FOR THE CONTROL ROOM ARE TO BE PROVIDED BY THE CUSTOMER.

IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

EQUIPMENT LEGEND

NO	DESCRIPTION	SMS SYM	WEIGHT (LBS)	BTU/HR TO AIR	DIMENSIONS (INCHES)			REMARKS
					W	D	H	
1	MRC OPERATING CONSOLE	Ⓢ	127	---	45 11/16	35 1/4	28 3/8	
2	MRC KEYBOARD	Ⓢ	5	---	27 1/4	10 1/8	1 3/4	ON CONSOLE ITEM #1
3	COLOR MONITOR FOR MRC	Ⓢ	22	239	18 5/16	16 15/16	4 3/4	ON CONSOLE ITEM #1
4	HOST PC MRC	Ⓢ	49	2,389	11	27	18 1/8	IN CONTAINER ITEM #5
5	CONTAINER FOR HOST PC 500	Ⓢ	238	---	19 5/8	31 1/2	28 3/8	
6	ALARM BOX	Ⓢ	2	---	9	4	9	WALL MOUNTED
7	3T MAGNET WITH COVERS , COILS, ELECTRONICS	Ⓢ	15,652	9,383	91	181 1/4	86	
8	PATIENT TABLE (FIXED)	Ⓢ	529	---	29 1/2	97 1/4	21-41	
9	RF-FILTER PLATE (HORIZONTAL)	Ⓢ	287	853	46 1/2	35 1/8	21 5/8	WALL MOUNTED
10	MAGNET STOP	Ⓢ	1	---	3	5	3	WALL MOUNTED
11	ELECTRONICS CABINET (GPA/EPC CABINET)	Ⓢ	3,307	---	61 1/2	26	77 1/2	
12	SEP CABINET	Ⓢ	701	3,415	25 5/8	25 5/8	73 5/8	
13	POWERWARE 9130 UPS WITH EBM	Ⓢ	186	1,257*	16 7/8	12 7/8	16 1/4	*1,755 ON BATTERIES

PROTECTING THE MAGNETIC FIELD
THE SIEMENS MAGNETOM UTILIZES A SUPERCONDUCTIVE MAGNET WITH AN EXTREMELY HOMOGENEOUS FIELD WITHIN THE MAGNET TO PROVIDE DISTORTION-FREE IMAGING. THE PRESENCE OF FERROMAGNETIC MATERIAL WITHIN THE VICINITY OF THE MAGNET CAN ADVERSELY AFFECT THE UNIFORMITY OF THE USEFUL MAGNETIC FIELD. THIS APPLIES TO STATIONARY FERROUS MATERIAL (STRUCTURAL STEEL) WHICH IS TO BE MINIMIZED. STATIONARY STEEL COMPENSATION MAY BE ACHIEVED BY MAGNET POSITIONING AND SELECTIVE USE OF SHIMS. FIELD DISTORTION ENCOUNTERED BY MOVING FERROMAGNETIC OBJECTS IS MORE DIFFICULT TO COMPENSATE AND MAY REQUIRE THE USE OF MAGNETIC SHIELDING.

PROTECTING THE ENVIRONMENT
PROTECTING THE IMMEDIATE ENVIRONMENT FROM THE EFFECT OF THE MAGNETIC FIELD REQUIRES CONSIDERATION. INFORMATION STORED ON MAGNETIC DATA CARRIERS SUCH AS DISKS, TAPES, AND CREDIT CARDS MAY BE ERASED IF IN CLOSE PROXIMITY. CAUTION WITH REGARD TO HEART PACEMAKERS MUST BE EXERCISED. MOST PACEMAKER UNITS EMPLOY A REED RELAY WHICH MAY CHANGE OPERATING MODE WHEN EXPOSED TO AN EXTERNAL MAGNETIC FIELD. THEREFORE, PACEMAKER USERS MUST BE KEPT AT A SPECIFIED DISTANCE FROM THE MAGNET WHICH IS DETERMINED BY THE MAGNETIC FIELD STRENGTH.

MAGNET SITING REQUIREMENTS
IT MUST BE ENSURED THAT THE MAGNET IS LOCATED SO THAT THE STABILITY AND HOMOGENEITY OF THE MAGNETIC FIELD ARE NOT ADVERSELY AFFECTED BY EXTRANEOUS FIELDS AND STATIC OR DYNAMIC FERROMAGNETIC OBJECTS.

X/Y AND Z AXIS	SOURCE OF INTERFERENCE
4'-0"	FLOOR STEEL REINFORCEMENT < 20 LBS./ FT ² IRON BEAMS < 66 LBS./FT.
18'-0" / 21'-3"	STRETCHERS UP TO 110 LBS.
13'-1"	A/C CHILLERS
19'-8" / 22'-11"	TRANSPORT DEVICES UP TO 440 LBS.
21'-3" / 26'-2"	VEHICLES UP TO 2,000 LBS.
22'-11" / 31'-2"	ELEVATORS, TRUCKS UP TO 10,000 LBS.
39'-4" / 26'-2"	AC TRANSFORMERS LESS THAN 100 KVA
41'-0" / 32'-9"	AC TRANSFORMERS LESS THAN 250 KVA
42'-7" / 39'-4"	AC TRANSFORMERS LESS THAN 650 KVA
45'-11" / 49'-2"	AC TRANSFORMERS LESS THAN 1600 KVA
9'-10" / 6'-6"	AC CABLES, MOTORS LESS THAN 100 AMPS
22'-11" / 9'-10"	AC CABLES, MOTORS LESS THAN 250 AMPS
39'-5" / 16'-5"	AC CABLES, MOTORS LESS THAN 1000 AMPS

FOR IRON OBJECTS LOCATED UP TO 45' FROM THE Z AXIS, THE DISTANCES FOR THE Z AXIS MUST BE USED. REDUCTION IS POSSIBLE WITH STEEL SHIELDING.

MAGNETIC FRINGE FIELDS
MAGNETIC FIELDS MAY AFFECT THE FUNCTION OF DEVICES IN THE VICINITY OF THE MAGNET. THESE DEVICES MUST BE OUTSIDE CERTAIN MAGNETIC FIELDS. THE DISTANCES LISTED ARE FROM THE MAGNET ISOCENTER AND DO NOT CONSIDER ANY MAGNETIC ROOM SHIELDING.

X/Y AND Z AXIS	DEVICES
6'-11" / 10'-6"	SMALL MOTORS, WATCHES, CAMERAS, CREDIT CARDS, MAGNETIC DATA CARRIERS (SHORT-TERM EXPOSURE)
3.0mT	
7'-7" / 13'-2"	COMPUTERS, MAGNETIC DISK DRIVES, OSCILLOSCOPES, PROCESSORS
1.0mT	
8'-7" / 15'-2"	CARDIAC PACEMAKERS, X-RAY TUBES, INSULIN PUMPS, B/W MONITORS, MAGNETIC DATA CARRIERS (LONG-TERM STORAGE)
0.5mT	
11'-2" / 20'-1"	COLOR MONITORS, SIEMENS CT SCANNERS
0.15mT	
12'-6" / 22'-4"	SIEMENS LINEAR ACCELERATORS
0.1mT	
16'-1" / 26'-11"	X-RAY IMAGE INTENSIFIERS, GAMMA CAMERAS, PET/CYCLOTRON ELECTRON MICROSCOPES, LINEAR ACCELERATORS
0.05mT	

THE OWNER/USER IS TO VERIFY THE LOCATION OF THE 0.5mT FIELD AND ENSURE THAT IT IS MAINTAINED AS A RESTRICTED AREA.

ENVIRONMENTAL/POWER AUDIT
AS AN INDICATION OF OUR COMMITMENT TO QUALITY, SIEMENS MAY, AT NO COST TO YOUR FACILITY, CHECK THE OPERATING ENVIRONMENT AFTER SYSTEM TURNOVER TO DETERMINE IF THE REQUIREMENTS FOR TEMPERATURE, HUMIDITY, POWER, AND GROUNDING ARE MET AS PER SIEMENS' PUBLISHED SPECIFICATIONS. SIEMENS WILL GENERATE A WRITTEN REPORT DETAILING THE ENVIRONMENTAL AND ELECTRICAL CONDITION OF THE SITE AFTER TURNOVER AND WILL SHARE THE REPORT WITH YOU. IN THE EVENT WE IDENTIFY ANY ENVIRONMENTAL/POWER DEFICIENCIES AT THE SITE, YOUR FACILITY WILL BE REQUESTED TO CORRECT DEFICIENCIES WITHIN THIRTY (30) DAYS. SHOULD ANY CORRECTIVE ACTIONS BE NECESSARY, AND UPON REQUEST, SIEMENS WILL PROVIDE GUIDANCE IN AN EFFORT TO FACILITATE RESOLUTION. PLEASE BE ADVISED THAT AFTER 30 DAYS NOTICE ANY REPAIR OR MAINTENANCE SERVICES NECESSITATED BY SEVERE DEFICIENCIES WILL FALL OUTSIDE YOUR WARRANTY COVERAGE.

MAGNET CO-SITING

MINIMUM DISTANCE MAGNET-MAGNET (SIEMENS)					
	0.2T	0.35T	1.0T	1.5T	3.0T
0.2T	32'-9"	32'-9"	16'-5"	19'-9"	32'-9"
0.35T	32'-9"	32'-9"	16'-5"	19'-9"	32'-9"
1.0T	16'-5"	16'-5"	14'-10"	16'-5"	19'-9"
1.5T	19'-9"	19'-9"	16'-5"	16'-5"	19'-9"
3.0T	32'-9"	32'-9"	19'-9"	19'-9"	19'-9"

DO NOT RAMP ONE MAGNET WHILE THE OTHER IS RUNNING APPLICATIONS. SHIM IS ONLY OPTIMIZED WHEN BOTH MAGNETS ARE RAMPED UP DURING THE SHIMMING PROCEDURE.

WHEN CO-SITING AN MR SYSTEM WITH A MAGNETIC NAVIGATION SYSTEM THE MINIMUM DISTANCE FOR CLINICAL IMAGING IS 96"-6". FOR SPECTROSCOPY THE MINIMUM SEPARATION IS 121"-5".

DC LIGHTING
THE MAGNETIC FIELD ADVERSELY AFFECTS THE OPERATING LIFE OF LIGHT BULBS LOCATED IN THE IMMEDIATE VICINITY OF THE MAGNET. THE FILAMENT IN THE BULB OSCILLATES WITH THE FREQUENCY OF THE POWER SUPPLY. DURING SCANNING, IT IS RECOMMENDED THAT LIGHT FIXTURES IN THE VICINITY OF THE MAGNET BE CONNECTED TO A DC VOLTAGE SUPPLY.

CONSTRUCTION REQUIREMENTS
THE CUSTOMER/CONTRACTOR IS RESPONSIBLE FOR SUPPLYING AND INSTALLING ALL CONSTRUCTION MATERIALS INCLUDING ELECTRICAL AND MECHANICAL DEVICES REQUIRED BY SIEMENS SPECIFICATIONS AND TO ENSURE THAT THE MATERIAL USED INSIDE THE REF-SHIELDING IS AS FREE OF FERROMAGNETIC PROPERTIES AS POSSIBLE.

ARCHITECTURAL NOTES

- ALL PRELIMINARY EQUIPMENT LAYOUTS SUBMITTED BY SIEMENS MEDICAL SOLUTIONS, INC. (SMS HEREAFTER) ARE BASED ON THE RECOMMENDED SPACE NECESSARY FOR THE OPERATION AND SERVICEABILITY OF THE EQUIPMENT BEING PROPOSED. SMS WILL NOT SUBMIT AN EQUIPMENT LAYOUT THAT IS NOT IN THE BEST INTEREST OF BOTH THE CUSTOMER AND SMS. ALL EQUIPMENT LAYOUTS ARE BASED EITHER ON AN ACTUAL SITE LOCATION SURVEY OR ARCHITECTURAL DRAWINGS SUPPLIED TO SMS. SMS WILL NOT BE RESPONSIBLE FOR ANY ALTERATIONS THAT ENCROACH WITHIN DESIGNATED SAFETY AND SERVICE CLEARANCE ZONES AS INDICATED ON DRAWINGS (IE. PIPE CHASES, VENTILATION DUCTS, CASEWORK, AND SOFFITS, ETC.) MADE BY THE CUSTOMER OR REQUIRED BY A CUSTOMER'S ARCHITECTURAL FIRM ONCE PRELIMINARY DRAWINGS HAVE BEEN SUBMITTED AND APPROVED. DO NOT ALTER ANY SPECIFICATIONS AND/OR DIMENSIONS WITHOUT CONTACTING AND RECEIVING WRITTEN CONFIRMATION FROM SMS PROJECT MANAGER.
- SMS IS NOT AN ARCHITECTURAL OR ENGINEERING FIRM. DRAWINGS SUPPLIED BY SMS ARE NOT CONSTRUCTION DRAWINGS. THEREFORE, THESE DRAWINGS ARE TO BE USED ONLY FOR INFORMATION TO COMPLEMENT ACTUAL CONSTRUCTION DRAWINGS AVAILABLE FROM A CUSTOMER APPOINTED ARCHITECTURAL REPRESENTATIVE OR A CUSTOMER'S ENGINEERING DESIGN GROUP. THE CUSTOMER'S ARCHITECT AND GENERAL CONTRACTOR SHALL BE ULTIMATELY RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE CODES AND PROFESSIONAL DESIGN REQUIREMENTS.
- THE CUSTOMER IS RESPONSIBLE FOR ALL ROOM AND AREA PREPARATION COSTS, PROFESSIONAL FEES, PERMITS, REPORTS, AND INSPECTION FEES.
- EQUIPMENT WARRANTIES, EXPRESSED OR IMPLIED ON THE PART OF SMS SHALL BE CONTINGENT UPON STRICT COMPLIANCE WITH THE ARCHITECTURAL, STRUCTURAL, ELECTRICAL, MECHANICAL AND RECOMMENDATIONS AND REQUIREMENTS CONTAINED IN THESE DRAWINGS, UNLESS SPECIFIED OTHERWISE.
- ALL DIMENSIONS SHOWN ARE TAKEN FROM FINISHED SURFACES UNLESS SPECIFIED OTHERWISE.
- THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST. ACTUAL PROTECTION REQUIREMENTS SHALL BE SPECIFIED BY A REGISTERED RADIATION PHYSICIST AT CUSTOMER'S ENGAGEMENT AND EXPENSE. RESPONSIBILITY FOR ALL INFORMATION AS TO THE ROOM LOCATION, USE, AND NUMBER OF ANTICIPATED EXAMINATIONS TO BE PERFORMED PER TIME PERIOD SHALL BE PROVIDED TO THE PHYSICIST BY THE CUSTOMER. THE CUSTOMER SHALL FURTHER TAKE ALL RESPONSIBILITY IN THE COMMUNICATION AND COORDINATION OF ACTIVITIES OF THE RADIATION PHYSICIST AND THE ARCHITECTURAL REPRESENTATIVE.
- SMS SHALL BE RESPONSIBLE FOR SMS EQUIPMENT INSTALLATION AND CALIBRATION, CONNECTION AND INSTALLATION OF SMS PROVIDED CABLES AND CONNECTION OF CONTRACTOR PROVIDED WIRES TO SMS EQUIPMENT. IN THE EVENT THAT SPECIFIC TRADE RULES OR LICENSE REQUIREMENTS PROHIBIT THIS, THE CUSTOMER SHALL INITIATE THE SERVICES OF APPROVED OTHER CONTRACTORS AND PAY FOR SELECTED APPROVED PARTIES TO PERFORM THIS WORK WITH JOB SUPERVISION TO BE PROVIDED BY SMS. CALIBRATION WHEN ACCOMPLISHED OUTSIDE OF NORMAL INSTALLATION SEQUENCES DUE TO CONTRACTOR OR TRADE RULE ACTIONS OR REQUIREMENTS SHALL BE SUPPORTED BY, AND ACCEPTED BY, THE CUSTOMER AS AN ADDITIONAL INSTALLATION EXPENSE.
- THE CUSTOMER SHALL VERIFY WITH SMS PROJECT MANAGER FINAL INSTALLATION DRAWINGS THE LOCATIONS AND TRAVEL OF ALL ANCHORAGE POINTS TO BE CEILING OR WALL MOUNTED (IE. O.R. LIGHTS, MEDICAL GAS COLUMNS, PHYSIOLOGICAL MONITORING INJECTORS, CRT PLATFORMS, SPRINKLER HEADS, SMOKE DETECTORS, ELECTRICAL OUTLETS, HVAC GRILLS, SPEAKERS, AND GENERAL ROOM LIGHTING, ETC.).
- THE GENERAL CONTRACTOR/CUSTOMER SHALL BE RESPONSIBLE FOR ALL FINAL PAINT, TOUCH-UP AND ANY COSMETIC OR TRIM WORK WHICH NEEDS TO BE OR IS REQUIRED TO BE COMPLETED AFTER THE INSTALLATION OF THE SMS EQUIPMENT AND ANY ASSOCIATED SUPPORT APPARATUS.

SITE READINESS GUIDELINES

THE FOLLOWING GENERAL CONDITIONS ARE NECESSARY TO HAVE THE STATUS OF "READY SITE":

- PROPER POWER AVAILABLE AT SIEMENS EQUIPMENT POWER CABINET LOCATION AND ALL POWER OUTLETS FUNCTIONING.
- AIR CONDITIONING/HUMIDIFICATION SYSTEMS COMPLETE, TESTED, AND FUNCTIONING PROPERLY ACCORDING TO SIEMENS SPECIFICATIONS.
- PROPER LIGHTING INSTALLED AND FUNCTIONING.
- PLUMBING COMPLETE EXCEPT FOR ANY FINAL CONNECTIONS TO SIEMENS EQUIPMENT.
- ALL CABLE TRAYS/DUCTS/CONDUITS CORRECTLY SIZED, LOCATED, AND INSTALLED ACCORDING TO THE SIEMENS DRAWINGS.
- ALL REINFORCEMENT PLATES/UNISTRUT INSTALLED AS REQUIRED.
- ROOM FOR EQUIPMENT INSTALLATION AND IMMEDIATE VICINITY IS DUST-FREE AND IS TO REMAIN SO FOR THE DURATION OF THE INSTALLATION.
- A SECURE AREA (APPROXIMATELY 10' x 10') IS AVAILABLE AT EQUIPMENT DELIVERY FOR PARTS AND INSTALLATION TOOLS.
- CUSTOMER SUPPLIED CAMERAS AND PROCESSORS INSTALLED.
- CUSTOMER APPROVAL FOR SIEMENS REMOTE SERVICES (SRS) CONNECTION, AND CUSTOMER'S I.T. CONTACT INFORMATION AND IP ADDRESSES ESTABLISHED.
- WALLS TO BE PRIMED AND PAINTED, FLOORS TO BE TILED EXCEPT IN AREAS OF THE EQUIPMENT BASE PLATES.

IF THESE CONDITIONS ARE NOT MET, THE SIEMENS PROJECT MANAGER AND THE DESIGNATED SIEMENS INSTALLATION SUPERVISOR SHALL RESCHEDULE THE INSTALLATION START DATE. NOTE: ADDITIONAL COST MAY BE INCURRED BY THE CUSTOMER/CONTRACTOR AND DELIVERY DATES MAY NEED TO BE RESCHEDULED, WHEN THE SIEMENS SITE READINESS GUIDELINES ARE NOT MET.

RESOURCE LIST (SMS USE ONLY)

DESIGNATION	PG NUMBER	DATE
PLANNING GUIDE	M7-030.891.01.04.02	01.12
MAGNETIC SHIELDING CALCULATIONS	400-9000001917-MR01	06.12

ATTENTION:

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
- THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.

- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
- THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

PROJECT MANAGER: JIM WILTHROW
TEL: (402) 960-7654
FAX: (402) 502-3001
EMAIL: JWILTHROW@CASSLING.COM

UNIVERSITY OF NEBRASKA - LINCOLN
MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583
MRI SUITE - MAGNETOM SKYRA W/FIXED TABLE

PROJECT #: **1201431** SHEET: **A-101**


THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW.
ALL RIGHTS ARE RESERVED.

SHEET 1 OF 10 DRAWN BY: D. BRISTOLE
DATE: 06/18/12 CHECKED:

SCALE: AS NOTED REF. # 50151667


-ISSUE BLOCK-

REFERENCE DOCUMENT - NOT FOR CONSTRUCTION




SAFETY/SERVICE CLEARANCE PLAN

SCALE: 1/4" = 1'-0"




SKYRA SIDE ELEVATION

SCALE: 1/4"=1'-0"



SKYRA MAGNET

SCALE: NONE



SKYRA FRONT ELEVATION

SCALE: 1/4"=1'-0"

ATTENTION:

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
- THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.



- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
- THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

		PROJECT MANAGER: JIM WILTHROW TEL: (402) 960-7684 FAX: (402) 502-3001 EMAIL: JWILTHROW@CASSLING.COM		SIEMENS UNIVERSITY OF NEBRASKA - LINCOLN MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583 MRI SUITE - MAGNETOM SKYRA W/FIXED TABLE	
06/29/12 MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC ROOM SHIELDING.		THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW.		PROJECT #: 1201431	
06/18/12 1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS		ALL RIGHTS ARE RESERVED.		SHEET: A-102 SHEET 2 OF 10 DRAWN BY: D. BRISTOLE CHECKED:	
-ISSUE BLOCK-		SCALE: AS NOTED REF. # 50151667		DATE: 06/18/12 CHECKED:	

SKYRA 02/24/12

SURFACE COIL SIZES				
COIL NAME	POUND WEIGHT	INCHES		
		LENGTH	WIDTH	HEIGHT
BODY COIL 18	4	15 1/8	23 1/4	3
HEAD/NECK COIL 20	11	17 3/8	13	14 5/8
SPINE COIL 32	24	47 1/4	19 1/4	3
FLEX COIL LARGE 4	1.2	20 3/8	8 7/8	-
FLEX COIL SMALL 4	1	14 3/8	6 7/8	-
PERIPHERAL ANGIO 36	18	33 7/8	26	11
HAND/WRIST COIL 16	6	13 1/8	8 1/2	4 1/2
HAND/WRIST COIL BASE	4	20 5/8	12 3/8	1 1/4
FOOT/ANKLE COIL 16	7	16 1/8	13	15 3/8
FOOT/ANKLE COIL BASE	15	16 3/4	13 1/8	15 1/8
SHOULDER COIL LARGE 16	15	15	17	19
SHOULDER COIL SMALL 16	15	12	17	19
CP EXTREMITY	15	16	10 5/8	11 3/8
TX/RX 15 CHANNEL KNEE	15	10 1/8	14 1/8	12 1/4
BI BREAST COIL 4 CH.	23	34 5/8	18 1/2	8 1/4
AI BREAST COIL 16 CH.	24	28	18 1/2	7 7/8
SENTINELLE VANGUARD IMMOBILIZER	45	43 1/4	22 7/8	11



ATTENTION:

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
- THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.



- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
- THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

		UNIVERSITY OF NEBRASKA - LINCOLN MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583 MRI SUITE - MAGNETOM SKYRA W/FIXED TABLE	
PROJECT MANAGER: JIM WILTHROW TEL: (402) 960-7654 FAX: (402) 502-3001 EMAIL: JWILTHROW@CASSELLING.COM		PROJECT #: 1201431	
MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC ROOM SHIELDING.		THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW.	
DATE: 06/29/12		SHEET: 3 OF 10	
DATE: 06/18/12		DRAWN BY: D. BRISTOLE	
-ISSUE BLOCK-		ALL RIGHTS ARE RESERVED.	
SCALE: AS NOTED		REF. # 50151667	
DATE: 06/18/12		CHECKED:	

A-501

SKYRA
02/24/12



RF DOOR OPENING

IN THE EVENT OF A CATASTROPHIC FAILURE OF THE QUENCH VENT DURING A QUENCH, PRESSURE BUILT UP MAY PREVENT OPENING A DOOR THAT OPENS INTO THE RF ROOM, PREVENTING EVACUATION FROM LIFE THREATENING CONDITIONS.

FOR THIS REASON THE RF DOOR SHOULD OPEN TO THE OUTSIDE OF THE RF ROOM. IF THE DOOR CANNOT OPEN OUT FROM THE RF ROOM, OTHER APPROPRIATE MEANS HAVE TO BE PROVIDED SO THAT THE RF ROOM DOOR IS NOT PREVENTED FROM OPENING DUE TO PRESSURE.

IF THE DOOR OPENS INTO THE RF ROOM, A 24"x24" OPENING FOR PRESSURE EQUALIZATION INTO THE RF ROOM MUST BE INSTALLED. THIS IS MANDATORY. THIS IS NOT AN ESCAPE HATCH. THE PURPOSE OF THE OPENING IS TO RELIEVE PRESSURE AND ALLOW THE MAIN DOOR TO BE OPENED SO THAT OCCUPANTS CAN BE EVACUATED.

THE OPENINGS WILL HAVE PANELS INSTALLED IN THE RF ROOM OR THE DOOR THAT CAN BE UNLOCKED AND OPENED TO THE OUTSIDE IN CASE OF EMERGENCY. THESE PANELS REQUIRE AN RF SEALED INSTALLATION. AFTER OPENING THE PANEL, THE OUTLET SHOULD MEASURE AT LEAST 24"x24", WHEN USING RECTANGULAR PANELS, THE SHORTER SIDE SHOULD MEASURE OF MINIMUM OF 24".


TO ENSURE UNOBSTRUCTED VENTING, THIS OPENING CANNOT BE SUBDIVIDED. THIS MEANS THAT, FOR EXAMPLE, RF SEALED HONEYCOMB GRIDS ARE NOT PERMITTED.

EASY REMOVAL OF THE PANEL BY A PERSON HAS TO BE ENSURED AND A MINIMUM DISTANCE OF 40" TO A FIXED OBJECT MUST BE MAINTAINED. THE PANEL SHOULD BE INSTALLED IN AN ACCESSIBLE LOCATION AND ALLOW ESCAPE OF THE LOW DENSITY HELIUM.

AS AN ALTERNATIVE TO AN OUTSWING DOOR, THE STATIONARY OBSERVATION WINDOW IS REPLACED BY A WINDOW OPENING INTO THE CONTROL AREA OR THE DOOR IS REPLACED WITH AN RF SEALED SLIDING DOOR. IT SHOULD BE ENSURED THAT THE DOOR CLOSING IN A WAY THAT ALLOWS IT TO MOVE AWAY FROM THE FRAME IN CASE OF OVERPRESSURE.

IF THE DOOR OPENS TO THE OUTSIDE, THE OPENING IN THE RF ROOM IS STILL RECOMMENDED.

THE RF ROOM MANUFACTURER CAN PROVIDE YOU WITH ADDITIONAL RF SEALED ROOM OPENINGS THAT LEAD DIRECTLY TO THE OUTSIDE. HOWEVER, THESE OPENINGS ARE ALSO CONDUITS FOR NOISE GENERATED OUTSIDE THE RF ROOM. UNOBSTRUCTED FLOW THROUGH THIS PIPE MUST BE GUARANTEED.



SAFETY ASPECTS FOR THE RF ROOM:
IT MUST BE POSSIBLE TO LOCK THE RF ROOM (EXAMINATION ROOM) DOOR FROM THE OUTSIDE. IT MUST ALSO BE POSSIBLE TO OPEN THE DOOR FROM THE INSIDE WITHOUT A KEY OR ADDITIONAL DEVICE.

THE RF DOOR IS AN IMPORTANT COMPONENT FOR GOOD IMAGE QUALITY AS WELL AS SAFETY. THE OWNER/OPERATOR OF THE MR SYSTEM MUST MAINTAIN THE RF ROOM AS INSTRUCTED BY THE RF ROOM MANUFACTURER IN ORDER TO GUARANTEE CORRECT FUNCTION OF THE RF DOOR.

NO FERROMAGNETIC ITEMS CAN BE BROUGHT INTO THE RF ROOM AFTER THE MAGNET HAS BEEN RAMPED UP TO FIELD. MAGNETIC ITEMS WILL BECOME ATTRACTED TO THE MAGNET WITH NO WARNING AND DUE TO THE HIGH MAGNETIC FIELD, WILL BECOME MISSILES.

NOTE: FOR DOORS MOVED BY AN AUXILIARY DRIVES (ELECTRICAL OR PNEUMATIC), MANUAL OPERATION HAS TO BE ENSURED. AN OUTSIDE WINDOW SHOULD BE IN THE VICINITY TO ALLOW VENTING EXHAUSTED GAS TO THE OUTSIDE. THE INTEGRITY OF THE RF SHIELD MUST BE TESTED AFTER REMODELLING.

1 SAFETY INFORMATION – PRESSURE EQUALIZATION SCALE: NONE

RF SHIELDING

THE EXAMINATION AREA MUST BE SHIELDED TO PROVIDE A REDUCTION OF RADIO FREQUENCY WAVES EMANATING FROM EXTERNAL TRANSMITTERS. THE REQUIRED ATTENUATION IS 90dB IN THE FREQUENCY RANGE OF 15-128 MHz. IF CO-SITING TWO SYSTEMS EACH ROOM SHOULD BE 100 dB. THE RF SHIELD MUST BE TESTED BEFORE AND AFTER MAGNET PLACEMENT IN THE RF ROOM AND AFTER THE SIEMENS RF FILTER PANEL IS INSTALLED.

THE RF-SHIELDING MUST BE INSULATED FROM ALL GROUNDS SUCH THAT THE ONLY GROUND IS THE SINGLE POINT GROUND ON THE OUTSIDE OF THE RF-ROOM WALL. RESISTANCE > 100 OHMS

ALL ELECTRICAL LINES INTO THE RF ROOM MUST BE ROUTED THROUGH RF FILTERS (PROVIDED BY RF SHIELDING SUPPLIER), ALL ELECTRICALLY NON-CONDUCTIVE SUPPLY LINES (E.G. FIBER OPTIC CABLES, OR HOSES) INTO THE RF ROOM MUST BE ROUTED THROUGH RF SEALED WAVEGUIDES (PROVIDED BY RF SHIELDING SUPPLIER).




FOR PRESSURE EQUALIZATION PURPOSES THE RF DOOR SHOULD OPEN TO THE OUTSIDE OF THE RF ROOM. AS AN ALTERNATIVE A 24"x24" OPENING IN THE RF ROOM FOR PRESSURE EQUALIZATION IS REQUIRED.

SHIELDING GENERAL NOTES

- SIEMENS REQUESTS THAT THE SHIELDING MANUFACTURER(S) SUBMIT FINAL SHOP DRAWINGS TO SIEMENS FOR REVIEW PRIOR TO THEIR INCLUSION IN CONSTRUCTION DOCUMENTS. SIEMENS SHALL BE COPIED ON ALL FIELD ORDER CHANGES CONCERNING CHANGES IN RF AND MAGNETIC SHIELDING CONDITIONS, CONFIGURATION AND SPECIFICATION. THE RF AND MAGNETIC SHIELDING CONTRACTOR(S) SHALL FURNISH "AS BUILT" SCALED AND DIMENSIONED PLANS REFLECTING ANY AND ALL FIELD ORDER CHANGES PRIOR TO THE COMPLETION OF THE CONSTRUCTION DOCUMENTS.
- ALL CHANGES TO SIEMENS RECOMMENDED OPENINGS AND PENETRATIONS SHALL BE APPROVED BY THE SIEMENS PROJECT MANAGER PRIOR TO THE COMPLETION OF THE CONSTRUCTION DOCUMENTS.
- THE SIZE, LOCATION, AND DIMENSIONS OF ANY MAGNETIC SHIELDING REQUIRED HAS BEEN DETERMINED BY SIEMENS. THIS INFORMATION HAS BEEN SUPPLIED TO THE MAGNETIC SHIELDING FABRICATOR TO DESIGN THE STRUCTURAL SUPPORT SYSTEM REQUIRED FOR THE MAGNETIC SHIELDING MATERIAL.

EXAM ROOM INTERIOR NOTES

- ONLY NON-MAGNETIC MATERIALS ARE TO BE USED AND INSTALLED IN THE RF ROOM.
- A SUSPENDED CEILING MUST BE STATICALLY SUSPENDED, NOT SUSPENDED WITH MOVABLE CLAMPS, SPRINGS, ETC.
- CORRUGATED RODS IN SUSPENDED CEILINGS MUST BE INSTALLED SECURELY. GALVANIC CONTACT BETWEEN THE CORRUGATED RODS MUST BE GUARANTEED, THEY MUST NOT JUST LIE ON TOP OF ONE ANOTHER. A WIRE JUMPER BETWEEN RODS MAY BE USEFUL.
- ELECTRICAL WIRING, FOR AMBIENT LIGHTS FOR EXAMPLE, MUST NOT SIMPLY REST ON THE SUSPENDED CEILING, THEY MUST BE FASTENED OR INSIDE A CONDUIT TO PREVENT MOTION.



FILTER PLATE GENERAL NOTES

- STRUCTURAL SUPPORT AND INTEGRATION OF THE SIEMENS SUPPLIED AND INSTALLED FILTER PLATE WITH MAGNETIC AND RF SHIELDING SHALL BE SPECIFIED, DETAILED AND NOTED BY THE RF AND MAGNETIC SHIELDING MANUFACTURER(S) WITH OVERALL COORDINATION WITH SIEMENS SITE SPECIFIC RECOMMENDATIONS TO BE THE RESPONSIBILITY OF THE ARCHITECT OF RECORD.
- THE FILTER PLATE FRAME, RF FILTER PLATE BLANK, RF GASKET AND MOUNTING HARDWARE FOR THE PURPOSES OF TESTING THE INTEGRITY OF THE RF ENCLOSURE PRIOR TO THE INSTALLATION OF THE SIEMENS SUPPLIED AND INSTALLED RF FILTER PLATE SHALL BE PROVIDED AND INSTALLED BY THE SHIELDING CONTRACTOR(S) UNLESS SPECIFIED OTHERWISE.

ATTENTION:

— THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
— THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.


— IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

— ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
— THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

PROJECT MANAGER: JIM WILTHROW TEL: (402) 960-7654 FAX: (402) 502-3001 EMAIL: JWILTHROW@CASSLING.COM		SIEMENS	
UNIVERSITY OF NEBRASKA - LINCOLN MEMORIAL STADIUM – EAST ADDITION, LINCOLN, NE 68583 MRI SUITE – MAGNETOM SKYRA W/FIXED TABLE		PROJECT #: 1201431	
THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW. ALL RIGHTS ARE RESERVED.		SHEET: A-502	
SYM	DATE	DESCRIPTION	SCALE: AS NOTED
△	06/29/12	MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC ROOM SHIELDING.	REF. # 30151667
△	06/29/12	ROOM SHIELDING.	DATE: 06/18/12
△	06/18/12	1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS	CHECKED:
—ISSUE BLOCK—		DRAWN BY: D. BRISTOLE	



SKYRA 02/24/12

REFERENCE DOCUMENT - NOT FOR CONSTRUCTION




STRUCTURAL FLOOR PLAN

SCALE: 1/4" = 1'-0"



SKYRA BASE DETAIL



BASEPLATE FOR FIXED PATIENT TABLE

- STRUCTURAL NOTES**
- 1) THE CUSTOMER/CONTRACTOR SHALL FURNISH AND INSTALL ALL STRUCTURAL SUPPORT MEMBERS AND NEEDED HARDWARE FOR THE INSTALLATION OF THE SIEMENS EQUIPMENT.
 - 2) THE OVERHEAD STRUCTURAL SUPPORT SYSTEM SHALL BE FIXED, RIGID AND BRACED FOR SWAY.
 - 3) ALL STRUCTURAL SUPPORT MEMBERS SHALL BE TRUE, SQUARE, LEVEL, PARALLEL AND COPLANAR WITH RESPECT TO EACH OTHER, WITH A HORIZONTAL STRUCTURAL SUPPORT MEMBER TO BE LOCATED AND SET WITH A TRANSIT.
 - 4) ALL STRUCTURAL SUPPORT DETAILS SHOWN ARE SAMPLE DETAILS BASED UPON TYPICAL AND STANDARD BUILDING PRACTICES AND ARE NOT INTENDED AS ACTUAL CONSTRUCTION DETAILS. ALL CONSTRUCTION DETAILS AND SUPPORT CALCULATIONS SHALL BE PREPARED BY A PROFESSIONAL STRUCTURAL ENGINEER AT THE CUSTOMER'S EXPENSE. IN THE EVENT AN EXISTING SUPPORT SYSTEM IS TO BE USED, IT WILL BE THE CUSTOMER'S RESPONSIBILITY TO VERIFY THE INTEGRITY OF THAT SYSTEM.
 - 5) WHERE SHOWN ON THE 1/4" STRUCTURAL FLOOR PLAN, THERE ARE ON OCCASION MOUNTING FRAMES FURNISHED BY SMS. THESE FRAMES ARE TO BE SET BY THE CONTRACTOR, UNDER THE SUPERVISION OF SMS PERSONNEL. THE CUSTOMER/CONTRACTOR IS RESPONSIBLE FOR ALL FRAMES INSTALLED BY HIM TO BE WATER LEVEL AND ANCHORED PROPERLY.
 - 6) ALL CEILING FIXTURES (I.E. AIR SUPPLY GRILLES, AIR RETURN GRILLES, EXHAUST GRILLES, SPRINKLER HEADS, INCANDESCENT AND FLUORESCENT LIGHT FIXTURES, INTERCOM SPEAKERS, MEDICAL GAS COLUMNS, ETC.) SHALL BE INSTALLED FLUSH MOUNTED WITH THE FINISHED CEILING TO PROVIDE FREE AND UNRESTRICTED TRAVEL OF THE SMS CEILING MOUNTED EQUIPMENT.
 - 7) THE BOTTOM SIDE OF THE UNISTRUT CEILING GRID AND ANY CEILING MOUNTED SUPPORT PLATES ARE TO BE INSTALLED FLUSH WITH THE FINISHED CEILING. THE CUSTOMER/CONTRACTOR SHALL ALSO PROVIDE COVERSTRIPS FOR THE UNISTRUT.
 - 8) THE STRUCTURAL PLANNING AS SHOWN ON THE 1/4" STRUCTURAL PLAN HAS BEEN COORDINATED WITH THE EQUIPMENT LOCATION AS SHOWN ON THE 1/4" EQUIPMENT LAYOUT PLAN. FOR THIS REASON, ANY DEVIATIONS FROM THE STRUCTURAL PLANNING AS SHOWN MUST BE APPROVED BY SMS PLANNING DEPARTMENT.
 - 9) THE STRUCTURAL ENGINEER OF RECORD SHALL BE RESPONSIBLE FOR THE DESIGN AND DETAIL OF FLOOR, WALL AND CEILING STRUCTURES IN ACCORDANCE WITH THE WEIGHTS, MOMENTS AND FORCES AS SHOWN ON OUR STRUCTURAL CALCULATIONS, OR INFORMATION, IN CONSIDERATION OF FORCES AS DETERMINED PER LOCAL GOVERNING BUILDING CODES.

FLOOR LOADING TABLE

	POUNDS
MAGNET AND PATIENT TABLE	16,381
MAGNET ONLY FLOOR LOADING	15,851
LOAD DISTRIBUTION PER SHIM PLATE	SEE DETAIL 1
PATIENT	550

CEILING HEIGHTS

MAGNET EXAMINATION ROOM: 7'-11" MINIMUM
EQUIPMENT ROOM: 7'-3" MINIMUM WITH RESTRICTION
ALL ANCILLARY AREAS: 6'-11" MINIMUM

PROJECT MANAGER: JIM WILTHROW
 TEL: (402) 960-7654
 FAX: (402) 228-5462 EXT: 1227
 EMAIL: JWILTHROW@CASSLING.COM

SIEMENS

UNIVERSITY OF NEBRASKA - LINCOLN
 MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583
 MRI SUITE - MAGNETOM SKYRA W/FIXED TABLE

PROJECT #:
1201431

SHEET:
S-101

THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW.

ALL RIGHTS ARE RESERVED.

SCALE: AS NOTED REF: 50151667

DATE: 06/18/12 CHECKED:

DATE: 06/18/12 DRAWN BY: D. BRISTOLE

DATE: 06/18/12


DATE: 06/18/12

ATTENTION:

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
- THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.
- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.
- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
- THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

SYM	DATE	DESCRIPTION
△	06/29/12	MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC ROOM SHIELDING.
△	06/29/12	ROOM SHIELDING.
△	06/18/12	1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS

-ISSUE BLOCK-



ELECTRICAL RACEWAY PLAN

SCALE: 1/4" = 1'-0"

SYMBOLS	
ALL MAY NOT APPLY	
	CAUTION OR WARNING
	CRITICAL NOTE(S)
	PANEL OR ENCLOSURE BY CUSTOMER/CONTRACTOR
	OPENING IN RACEWAY OR TRENCH/DUCT
	PULLBOX IN (FLOOR/WALL/CEILING)
	OPENING IN ACCESS FLOORING
	RF DOOR SWITCH - MCMASTER-CARR SUPPLY ROLLER LIMIT SWITCH 7078414 MOUNTED AT TOP OF DOOR. COORDINATE WITH SIEMENS PROJECT MANAGER.
	(EPO) EMERGENCY POWER OFF BUTTON
	CEILING DUCT
	SURFACE MOUNTED DUCT
	VERTICAL DUCT
	ETHERNET CONNECTION TO CUSTOMER'S INFORMATION SYSTEMS NETWORK (VERIFY WITH SMS PROGRAM MANAGER).
	110 VOLT, 20 AMP, HOSPITAL GRADE DUPLEX OUTLET LOCATED NEAR THE RDIAG PHONE LINE.

POWER REQUIREMENTS	
DEMAND AND CAPACITY REQUIREMENTS NOTES	
1)	IF EQUIPMENT UPGRADE IS ANTICIPATED, INSTALLING ELECTRICAL POWER TO MEET THE REQUIREMENTS OF THE HIGHER POWER GRADIENT PACKAGE AT THE TIME OF INITIAL INSTALLATION WILL REDUCE THE COST TO UPGRADE THE ELECTRICAL SYSTEM LATER.
2)	RECOMMENDED TRANSFORMER SIZE (SYSTEM WITHOUT UPS) IS BASED ON INDUSTRY STANDARD ISOLATION TRANSFORMER KVA RATINGS. SOURCE IMPEDANCE FEEDING THE MAGNETOM SYSTEM, INCLUDING ANY ISOLATION TRANSFORMERS, MUST MEET EQUIPMENT REQUIREMENTS AS LISTED HERE. SIEMENS RECOMMENDS A TRANSFORMER WITH COPPER WINDINGS, AN ELECTRO-STATIC SHIELD, AND A LOW IMPEDANCE (<3%) TO ENSURE THAT SOURCE IMPEDANCE REQUIREMENTS ARE MET.
3)	OVERCURRENT PROTECTION IS SPECIFIED FOR SYSTEMS WITHOUT AN UNINTERRUPTIBLE POWER SUPPLY (UPS). ADDITION OF A UPS REQUIRES A HIGHER CAPACITY MAINS CONNECTION (DEPENDENT UPON UPS MODEL AND SIZE). MAXIMUM FAULT CURRENT IS DEPENDENT UPON THE IMPEDANCE OF THE FACILITY ELECTRICAL SYSTEM. CUSTOMER'S ARCHITECT OR ELECTRICAL CONTRACTOR TO SPECIFY ARC RATING OF OVERCURRENT PROTECTION BASED ON FACILITY IMPEDANCE CHARACTERISTICS.
4)	MOMENTARY POWER IS BASED ON A MAXIMUM RMS VALUE FOR A PERIOD NOT TO EXCEED FIVE (5) SECONDS, AS DEFINED IN NEC 517.2. STAND-BY AND AVERAGE CURRENT ARE SUBSTANTIALLY LOWER.
5)	THE CONDUCTOR SIZE SHOULD BE SELECTED TO MEET THE VOLTAGE DROP REQUIREMENTS, TAKING INTO CONSIDERATION THE MAINS CAPACITY, RUN LENGTH, AND ANY ADDITIONAL TRANSFORMERS USED TO OBTAIN THE PROPER EQUIPMENT VOLTAGE LEVEL. NEMA STANDARD XR-9-1989 (R1994,R2000) PROVIDES GENERAL GUIDELINES FOR SIZING CONDUCTORS, TRANSFORMERS, AND ELECTRICAL SYSTEMS FOR MEDICAL IMAGING SYSTEMS.
6)	LONG-TIME POWER IS BASED ON THE HIGHEST AVERAGE RMS VALUES FOR A PERIOD EXCEEDING 5 MINUTES DURING CLINICAL SYSTEM OPERATION, AS DEFINED IN NEC 517.2.
7)	A CIRCUIT BREAKER WITH A HIGH INRUSH RATING (>8x RATED CURRENT) IS REQUIRED TO PERMIT SWITCH-ON OF THE UPS SYSTEM WITHOUT SPURIOUS TRIPPING. CIRCUIT BREAKERS WITH AN ADJUSTABLE MAGNETIC TRIP (SIEMENS F06 SERIES OR SIMILAR) ARE HIGHLY RECOMMENDED.

POWER REQUIREMENTS	
VOLTAGE RANGE:	480 VAC ±10% FOR ALL LINE AND LOAD CONDITIONS.
VOLTAGE BALANCE:	2% MAXIMUM DIFFERENCE BETWEEN PHASES
FREQUENCY:	60 Hz ± 1.0 Hz
LINE IMPEDANCE:	<95 mΩHMS
STAND BY POWER CONSUMPTION	8.0 kW
READY FOR MEASUREMENT	16.2 kW
CONNECTION VALUE (LESS THAN 5 MINUTES)	110 KVA
MOMENTARY POWER	101 KVA
RECOMMENDED TRANSFORMER	TBD
MR SYSTEM OVERCURRENT PROTECTION	175 A
RECOMMENDED UPS	160 KVA
UPS SYSTEM OVERCURRENT PROTECTION	225 A
MAX. ALLOWABLE VOLTAGE DROP AT MAX. POWER	6.0%

POWER QUALITY	
POOR POWER WILL ALTER EQUIPMENT PERFORMANCE	
IT IS IN THE CUSTOMER'S INTEREST THAT THE ELECTRICAL CONTRACTOR BE RESPONSIBLE FOR TESTING AND VERIFYING THAT THE EQUIPMENT POWER SUPPLY COMPLIES WITH THE SIEMENS SPECIFICATIONS.	

ELECTRICAL LEGEND			
SYM	SIZE	DESCRIPTION	REMARKS
SUPPLIED AND INSTALLED BY CUSTOMER/CONTRACTOR			
Ⓜ	3"ø	OPENING IN FACE OF VERTICAL DUCT 5'-0" ABOVE FINISHED FLOOR IN LOCATION TO BE COORDINATED WITH THE ARCHITECT.	ALARM BOX
Ⓢ	AS REQUIRED	LOCATION FOR CABLES TO DROP OUT OF BOTTOM OF RACEWAY.	MAGNET CABLE ACCESS
Ⓢ	AS REQUIRED	LOCATION FOR CABLES TO DROP OUT OF BOTTOM OF RACEWAY.	ELECTRONICS CABINETS
Ⓢ	AS REQUIRED	EMERGENCY POWER OFF BUTTONS TO PREVENT RESETTING OF BREAKER WHEN IN "OFF" POSITION, MOUNTED WITH CENTERLINE AT 5'-0" ABOVE FINISHED FLOOR. ALL PARTS ARE TO BE NON-FERROUS INSIDE THE RF ROOM. EXACT LOCATIONS ARE TO BE VERIFIED WITH THE ARCHITECT OF RECORD.	UNDER VOLTAGE TRIP SEE DETAIL E-501/1
Ⓢ	AS REQUIRED	SIEMENS RF FILTER PANEL TO BE MOUNTED ON RF SHIELDED WALL	FILTER PANEL
Ⓢ	3-PHASE	MAIN ENCLOSURE TO BE PROVIDED AND INSTALLED BY CUSTOMER/CONTRACTOR FLUSH OR SURFACE MOUNTED 5'-0" ABOVE FINISHED FLOOR, EXACT LOCATION TO BE DETERMINED BY CUSTOMER/CONTRACTOR.	SEE SHEET E-501
Ⓢ	4" x 4"	OPENING IN FACE OF RACEWAY IN SHOWN LOCATION.	MAIN CONSOLE
Ⓢ	AS REQUIRED	NON-FERROUS SINGLE GANG BOX MOUNTED FLUSH WITH FINISHED WALL MOUNTED 6'-0" ABOVE FINISHED FLOOR. PROVIDE NEATLY FINISHED AND REMOVABLE COVER WITH CABLE EXIT. EXACT LOCATION TO BE COORDINATED WITH THE ARCHITECT.	MAGNET STOP
Ⓢ	AS REQUIRED	PULL BOX MOUNTED FLUSH WITH FINISHED WALL AT FLOOR LINE IN SHOWN LOCATION PROVIDED WITH 2"ø OPENING IN FINISHED COVER.	POWERWARE 9130
Ⓢ	24"x4"	ALUMINUM LADDER TRAY, MOUNTED AT HEIGHT COORDINATED WITH SIEMENS PROJECT MANAGER, IN THE EXAM ROOM, MAINTAINING 12" CLEARANCE ABOVE THE TRAY FOR ACCESS. CABLE LADDER IS REQUIRED TO SUPPORT INTERCONNECTING CABLES BETWEEN THE FILTER PANEL AND THE MAGNET. A 15" MINIMUM CLEARANCE IS REQUIRED BETWEEN THE LADDER TRAY AND THE RF FILTER PANEL (F1). WHEN ROUTING ALL RACEWAYS REFER TO DETAIL E-501/2 TAKING CARE SO THAT MAXIMUM CABLE LENGTHS ARE NOT EXCEEDED. DO NOT LOCATE THIS CABLE TRAY ABOVE THE MAGNET.	CABLE TRAY SEE DETAIL E-501/3
Ⓢ	12"x4"	ALUMINUM LADDER TRAY, MOUNTED AT HEIGHT COORDINATED WITH SIEMENS PROJECT MANAGER IN EXAM ROOM. A 12" SEPARATION BETWEEN CD1 AND CD2 MUST BE MAINTAINED. DO NOT LOCATE THIS CABLE TRAY ABOVE THE MAGNET.	CABLE TRAY SEE DETAIL E-501/3
Ⓢ	24"x4"	LADDER TRAY, MOUNTED AT HEIGHT COORDINATED WITH SIEMENS PROJECT MANAGER IN EQUIPMENT ROOM MAINTAINING 12" CLEARANCE ABOVE THE TRAY FOR ACCESS. CABLE LADDER IS REQUIRED TO SUPPORT INTERCONNECTING CABLES BETWEEN THE EQUIPMENT ROOM AND THE RF FILTER PANEL (F1). AN 18" MINIMUM CLEARANCE IS REQUIRED BETWEEN THE LADDER TRAY AND THE FILTER PANEL.	CABLE TRAY SEE DETAIL E-501/3
Ⓢ	4" x 2"	WIRE MOLD SURFACE MOUNTED ON WALL IN CONTROL AREA AT FLOOR LINE AS SHOWN, FINISHED TO MATCH WALLS.	
Ⓢ	10" x 3-1/2"	ELECTRICAL DUCT MOUNTED FLUSH WITH FINISHED WALL IN CONTROL AREA FROM ABOVE FINISHED CEILING TO FLOOR LINE PROVIDED WITH REMOVABLE FINISHED COVERS.	
Ⓢ	AS PER NEC	CONDUIT FROM FACILITY POWER TO MAIN ENCLOSURE (ME)	SEE SHEET E-501
Ⓢ	AS PER NEC	CONDUIT FROM "ME" TO "EPO"	SEE DETAIL E-501/1
Ⓢ	AS PER NEC	CONDUIT FROM "EPO" TO "EPO" TO BE NON-FERROUS WHEN INSIDE THE RF ROOM. CUSTOMER/CONTRACTOR IS TO PROVIDE RF FILTERS FOR ALL NON-SIEMENS WIRING.	SEE DETAIL E-501/1
Ⓢ	(1) 3/4"ø	CONDUIT FROM "EPO" TO "UPS"	SEE DETAIL E-501/1
Ⓢ	(1) 3/4"ø	SURFACE MOUNTED FLEX CONDUIT FROM "UPS" TO SIEMENS PROVIDED UPS/EPO CONTROL BOX.	NOT TO EXCEED 4 FEET
Ⓢ	(1) 1"ø	CONDUIT FROM "UPS" TO "CD3" (EPC).	NOT TO EXCEED 29 FEET
Ⓢ	(1) 2"ø	CONDUIT FROM "ME" TO END AT "CD3" (EPC) VIA FLEX CONDUIT. THERE MUST BE A DIELECTRIC SEPARATION BETWEEN THE CONDUIT AND THE CONNECTION AT THE SIEMENS ACC CABINET.	
Ⓢ	(2) 2 1/2"ø	CONDUITS FROM "VD1" (MRC) TO "CD3" (EPC)	NOT TO EXCEED 60 FEET
Ⓢ	(1) 1 1/2"ø	CONDUIT FROM "VD1" (AB) TO "CD3" (EPC)	NOT TO EXCEED 60 FEET
Ⓢ	(1) 1/2"ø	CONDUIT FROM "DS" TO "CD3" (EPC)	NOT TO EXCEED 55 FEET
Ⓢ	(1) 3/4"ø	NON-FERROUS CONDUIT FROM "MS" TO "CD1" (B)	NOT TO EXCEED 20 FEET

CONTRACTOR SUPPLIED CABLES				
FROM	VIA	TO	DESCRIPTION	REMARKS
SOURCE	1	ME	(3) PHASE CONDUCTORS, (1) FULL SIZE EQUIPMENT GROUND WIRE AND (1) NEC SIZED SAFETY GROUND WIRE TO BE SIZED BY ELECTRICAL CONTRACTOR/ENGINEER.	
ME	2	EPO	DETERMINED BY ELECTRICAL CONTRACTOR.	
EPO	3	EPO	DETERMINED BY ELECTRICAL CONTRACTOR.	
EPO	4	UPS	DETERMINED BY ELECTRICAL CONTRACTOR.	6 FOOT TAILS
ME	7	EPC	(3) 2/0 AND (1) 2/0 EQUIPMENT GROUND. TO REDUCE EMI (INTERFERENCE) THE POWER CABLES MUST BE SHIELDED. THIS CAN BE ACHIEVED BY USING EMT CONDUIT, WHICH IS CONSIDERED A SHIELDING DEVICE. IF CABLES ARE RUN IN FREE AIR SHIELDED CONDUCTORS MUST BE USED.	

ELECTRICAL NOTES	
1)	COMPLIANCE: ELECTRICAL WORK SHALL BE IN COMPLIANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA-70), O.S.H.A. REGULATIONS, AS WELL AS APPLICABLE REGULATIONS OF CITY, COUNTY, STATE AND FEDERAL AGENCIES. PROVIDE MATERIALS AND EQUIPMENT THAT COMPLY TO ANSI, IEEE AND NEMA STANDARDS. WHERE APPLICABLE, PROVIDE ONLY MATERIALS AND PRODUCTS THAT ARE U.L. LISTED AND LABELED. CUSTOMER'S/CONTRACTOR'S WORK SHALL COMPLY WITH THE LATEST EDITION OF NECA STANDARD OF INSTALLATION.
2)	QUALITY ASSURANCE: THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS IN THE FIELD TO INSURE THAT THE NEW WORK WILL FIT TO THE EXISTING STRUCTURE AS SHOWN ON THE DRAWINGS. SHOULD ANY CONDITIONS EXIST OR BE DISCOVERED THAT PREVENT THE INSTALLATION OF WORK AS SHOWN, THE CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE PRIOR TO FABRICATION OF EQUIPMENT, OR THE PERFORMANCE OF ANY WORK THAT MAY BE AFFECTED. DO NOT ALTER DRAWINGS, DIMENSIONS, OR SPECIFICATIONS IN ANY WAY WITHOUT CONTACTING AND RECEIVING WRITTEN CONFIRMATION FROM SMS PROJECT MANAGER. ALL DIMENSIONS ARE FROM FINISHED SURFACES. CONDUIT AND PULL BOXES TO BE INSTALLED BY THE CUSTOMER/CONTRACTOR WITH LOCATIONS BEING FIELD VERIFIED BY SMS PROJECT MANAGER.
3)	WORK FURNISHED BY CUSTOMER/CONTRACTOR: WORK NOT PROVIDED BY SIEMENS MEDICAL SYSTEMS BUT SHOWN ON DRAWINGS TO BE FURNISHED AND INSTALLED BY CUSTOMER/CONTRACTOR INCLUDES THE FOLLOWING BUT IS NOT LIMITED TO UNLESS NOTED OTHERWISE: ELECTRICAL RACEWAYS AND DUCTS; WIRING DEVICES; PULL BOXES, CONDUITS, CIRCUIT BREAKERS, EMERGENCY OFF BUTTONS, DOOR SWITCHES, WARNING LIGHTS, WIRING, WIRING DEVICES, CONNECTORS, LIGHTING EQUIPMENT AND GROUNDING.
4)	RACEWAY AND CONDUIT NOTES: RACEWAY SHALL BE ELECTRIC METALLIC TUBING (EMT) FOR RIGID CONDUIT WORK, OR WHERE SHORT OFF-SET CONNECTIONS ARE REQUIRED LIQUIDTIGHT FLEXIBLE METAL CONDUIT SHALL BE USED. FIELD BENDS SHALL NOT BE LESS THAN AS SHOWN IN TABLE 346-10 OF THE NATIONAL ELECTRICAL CODE. PROVIDE A JETLINE "SUPER TRULIE TAPET" OR EQUIVALENT CONDUIT MEASURING TAPE FISH LINE IN ALL RACEWAYS AND CONDUITS. CONDUIT BODIES SHALL NOT BE USED. WHERE A CONDUIT ENTERS A BOX, FITTING, OR OTHER ENCLOSURE, AN INSULATED THROAT CONNECTOR SHALL BE PROVIDED TO PROTECT THE WIRE FROM ABRASION. CONNECTORS SHALL BE DOUBLE SET SCREW TYPE, STEEL CONCRETE TIGHT. KEEP RACEWAYS AT LEAST 6 INCHES AWAY FROM PARALLEL RUNS OF FLUES OR STEAM AND HOT WATER PIPES. INSTALL RACEWAY RUNS ABOVE WATER AND STEAM PIPES PROVIDED THAT CABLE RUN DISTANCES ARE MAINTAINED. USE TEMPORARY CLOSURES TO PREVENT FOREIGN MATTER FROM ENTERING RACEWAY. CONDUIT RUNS ARE SHOWN SCHEMATICALLY. INSTALL CONDUIT WITH A MINIMUM OF BENDS IN THE SHORTEST PRACTICAL DISTANCE CONSIDERING THE BUILDING CONSTRUCTION AND OBSTRUCTIONS, EXCEPT AS OTHERWISE INDICATED. THE CONTRACTOR SHALL MAKE CERTAIN THAT ANY CONDUIT/RACEWAY RUNS CONTAINING SIEMENS MEDICAL SYSTEMS CABLES DO NOT EXCEED THE SPECIFIED MAXIMUM DISTANCES AS SHOWN ON THE ELECTRICAL DETAILS. PROVIDE ENCLOSED METAL RACEWAY SYSTEM (WIRE DUCT) WHERE SHOWN ON DRAWINGS WITH DIVIDERS TO SEPARATE THE DUCT FOR POWER AND SIEMENS MEDICAL SYSTEMS CABLING. DIVIDERS AND CROSSOVER PIECES TO BE PROVIDED AS NECESSARY. FOR UL CERTIFIED SYSTEMS, THE CABLE TO CABLE AS WELL AS THE CIRCUIT TO CIRCUIT SEPARATION REQUIREMENT WAS EVALUATED DURING THE UL SYSTEM INVESTIGATION OF THIS EQUIPMENT. ADDITIONAL SEPARATION OF THE SYSTEM CABLE ASSEMBLIES INTO SEPARATE OR PARTITIONED RACEWAYS, UNLESS OTHERWISE NOTED, IS NOT NECESSARY TO INSURE SEPARATION OF CIRCUITS, AS THEY CAN BE IN THE SAME RACEWAY. PROVIDE WIRE DUCT/RACEWAY WITH ACCESSIBLE REMOVABLE COVERS. LOCATIONS OF OPENINGS TO BE CUT IN FIELD ARE TO BE COORDINATED WITH SIEMENS PROJECT MANAGER. ELECTRICAL PULL BOXES AND RACEWAY COVERS SHALL BE INSTALLED IN A MANNER TO ALLOW ACCESSIBILITY FOR INSTALLATION AND MAINTENANCE. IN-FLOOR TRENCH DUCT AND FLUSH FLOOR BOXES SHALL BE PROVIDED WITH FULLY GASKETED REMOVABLE COVERS.
5)	IN ADDITION TO THE CIRCUIT BREAKER LOAD CURRENT RATING, CONSIDERATION MUST ALSO BE GIVEN TO SELECTING CIRCUIT BREAKERS THAT HAVE A HIGH ENOUGH SHORT CIRCUIT CURRENT WITHSTAND RATING TO SAFELY COORDINATE WITH THE POWER SYSTEM AVAILABLE SHORT CIRCUIT CURRENT. GENERALLY, WHEN THE 480 VOLT, 3 PHASE, MR SYSTEM IS SERVED FROM A POWER SUPPLY SYSTEM THAT IS PROVIDED WITH A 500 KVA OR SMALLER TRANSFORMER, A STANDARD 14,000 RMS AMPERE WITHSTAND RATED CIRCUIT BREAKER WILL BE ADEQUATE. HOWEVER, IF THE POWER SUPPLY SYSTEM TRANSFORMER IS LARGER THAN 500 KVA, THEN THE CIRCUIT BREAKERS HAVING A SHORT CIRCUIT WITHSTAND RATING GREATER THAN 14,000 RMS AMPERES MAY BE REQUIRED.

CABLE LENGTH RESTRICTIONS	
1)	THE CABLE SET LENGTH IDENTIFIES THE "FREE CABLE LENGTH". THIS IS THE LENGTH FROM CONNECTION POINT TO CONNECTION POINT. THE CABLE LENGTH IS NOT THE DISTANCE BETWEEN COMPONENTS.
2)	THE GRADIENT CABLES INSIDE THE RF SHIELDED ROOM ARE 6'-0" SHORTER THAN THE OTHER SYSTEM CABLES. THIS MEANS THAT IF THE 22' CABLE SET IS SELECTED, THE GRADIENT CABLES WILL BE 16' IN LENGTH. THE GRADIENT CABLES NEED TO GO UP INTO THE CABLE TRAY IN THE CEILING AT THE FILTER PLATE AND DOWN AT THE MAGNET. THESE VERTICAL RUNS MUST BE DEDUCTED FROM THE TOTAL CABLE LENGTH OF 16'.

ATTENTION:

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
- THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.

- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
- THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

CEILING HEIGHTS	
MAGNET EXAMINATION ROOM:	7'-11" MINIMUM
EQUIPMENT ROOM:	7'-3" MINIMUM WITH RESTRICTION
ALL ANCILLARY AREAS:	6'-11" MINIMUM

SYM	DATE	DESCRIPTION
△	06/29/12	MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC ROOM SHIELDING.
△	06/29/12	ROOM SHIELDING.
△	06/18/12	1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS


PROJECT MANAGER: JIM WILTHROW
TEL: (402) 960-7654
FAX: (402) 502-3001
EMAIL: JWILTHROW@CASSLING.COM

SIEMENS UNIVERSITY OF NEBRASKA - LINCOLN
MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583
SUITE - MAGNETOM SKYRA W/FIXED TABLE

PROJECT #: **1201431**
SHEET: **E-101**
SHEET 6 OF 10
DRAWN BY: D. BRISTOLE
DATE: 06/18/12
CHECKED:

THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW.
ALL RIGHTS ARE RESERVED.
SCALE: AS NOTED
REF. # 50151667

SKYRA
02/24/12



ELECTRICAL DIMENSION PLAN

SCALE: 1/4" = 1'-0"

CEILING HEIGHTS	
MAGNET EXAMINATION ROOM:	7'-11" MINIMUM
EQUIPMENT ROOM:	7'-3" MINIMUM WITH RESTRICTION
ALL ANCILLARY AREAS:	6'-11" MINIMUM

		PROJECT MANAGER: JIM WILTHROW TEL: (402) 960-7654 FAX: (402) 502-3001 EMAIL: JWILTHROW@CASSLING.COM		SIEMENS UNIVERSITY OF NEBRASKA - LINCOLN <small>MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583 MRI SUITE - MAGNETOM SKYRA W/FIXED TABLE</small>	
		MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC ROOM SHIELDING.		THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW.	
		1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS		PROJECT #: 1201431	
		ALL RIGHTS ARE RESERVED.		SHEET: E-102	
-ISSUE BLOCK-		SCALE: AS NOTED		REF. # 50151667	
		DATE: 06/18/12		DRAWN BY: D. BRISTOE CHECKED:	

ATTENTION:

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
 - THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.

- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
 - THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

SKYRA
02/24/12

REFERENCE DOCUMENT - NOT FOR CONSTRUCTION

GENERAL NOTES

- 1) IN ORDER TO MAINTAIN THE INTEGRITY OF THE RF-SHIELDED EXAM ROOM, THE GROUND MUST ORIGINATE AT THE SIEMENS ELECTRONICS CABINET GROUND BUS, AND SHOULD BE CONNECTED AT BOTH ENDS UNDER SIEMENS SUPERVISION.
- 2) THE CUSTOMER/CONTRACTOR IS TO FURNISH A FLEXIBLE DEDICATED AND ISOLATED GROUND (GRD) CONDUCTOR FROM THE MAIN FACILITY DISTRIBUTION SOURCE TO THE SIEMENS ELECTRONICS CABINET (ACC). THE GROUND CONDUCTOR MUST BE SIZE AND TYPE TO MATCH THE PHASE CONDUCTORS.
- 3) THE INTERNAL LINE IMPEDANCE IS 100mOHMS MEASURED AT THE SIEMENS ELECTRONICS CABINET (EPC). ALL WIRING AND CONDUITS

- 4) THE EPO (EMERGENCY POWER OFF) MUST PROVIDE REMOTE "EMERGENCY OFF" CONTROL OF SYSTEM POWER. THE EPO'S MUST BE INSTALLED BY A QUALIFIED ELECTRICAL CONTRACTOR ACCORDING TO NATIONAL ELECTRICAL CODE, STATE AND LOCAL REGULATIONS. MEASURES SHOULD BE TAKEN TO DESIGN THE CIRCUIT IN SUCH A WAY THAT IT WILL ALWAYS WORK WHEN THE MEDICAL EQUIPMENT IS POWERED. IT IS RECOMMENDED THAT EPO CIRCUIT BE A NORMALLY CLOSED ENERGIZED CIRCUIT DESIGN AND THAT IT DERIVES ITS SOURCE FROM THE EQUIPMENT INCOMING FEEDER OR IS A DEDICATED BRANCH CIRCUIT, PREFERABLY FROM


AN EVERGENCY POWER SOURCE WITH CIRCUIT BREAKER LABELED AND 'LOCKED-ON'. THE EPO CONFIGURATION DEPICTED IN THIS DRAWING IS ONE EXAMPLE OF A POSSIBLE EPO CONFIGURATION THAT SATISFIES THESE REQUIREMENTS. HOWEVER, THE FACILITY/CONTRACTOR IS SOLELY RESPONSIBLE FOR THE IMPLEMENTATION OF THE EPO AND MUST MAKE THE FINAL DETERMINATION CONSIDERING ALL SITE CONDITIONS AND REGULATORY FACTORS.

THE SECOND SET OF NORMALLY CLOSED CONTACTS ARE TO BE DRY TYPE AND CONNECTED IN SERIES FOR THE UPS. (THEORY OF CIRCUIT) WHEN ANY EPO IS PUSHED, THE NORMALLY CLOSED UPS CONTACT WILL OPEN SENDING A SIGNAL TO THE UPS SHUTTING THE UPS DOWN.

LEGEND

A	E1SFD638175 - BREAKER AND ENCLOSURE
B	U01FD00 - 120VAC UNDERVOLTAGE TRIP
D	KT8050P - 480 VOLTS TO 120 VOLTS STEP DOWN TRANSFORMER FOR UNDERVOLTAGE TRIP
G	GROUND BAR

EMT CONDUIT
ALUMINUM CONDUIT
FLEXIBLE CONDUIT WITH DIELECTRIC AT ACC



BREAKER AND ENCLOSURE TO BE LOCATED IN EQUIPMENT ROOM

POWER AND GROUNDING REQUIREMENTS

SCALE: NONE

SIEMENS REMOTE SERVICES (SRS)

TO ENSURE THE UPTIME OF YOUR SYSTEM DURING THE WARRANTY PERIOD (AND BEYOND WITH A SERVICE AGREEMENT), SIEMENS REMOTE SERVICES (SRS) REQUIRES REMOTE LOCAL AREA NETWORK ACCESS TO SIEMENS SYSTEMS.

SRS REQUIRES ONE OF THE FOLLOWING CONNECTION METHODS:

(PREFERRED) VPN CONNECTION

THE PREFERRED CONNECTION METHOD IS (VPN) VIRTUAL PRIVATE NETWORK (WHERE THE CUSTOMER HAS AVAILABLE A VPN CAPABLE FIREWALL OR OTHER VPN APPLIANCE). THIS METHOD PROVIDES THE POSSIBILITY FOR REMOTE SYSTEM DIAGNOSTICS WITHOUT ADDITIONAL HARDWARE. PLEASE CONTACT SIEMENS REMOTE SERVICES (800-888-SIEM) TO DETERMINE IF THIS METHOD IS SUITABLE FOR YOUR SITE.


(OPTIONAL) SRS ROUTER CONNECTION

- THE SRS ROUTER IS SUPPLIED BY SIEMENS AND INSTALLED AT THE CUSTOMER'S SITE, WHILE STILL REMAINING THE PROPERTY OF SIEMENS. THE CUSTOMER'S NETWORK ADMINISTRATOR AND SIEMENS REMOTE SERVICES SHALL DETERMINE THE TYPE AND LOCATION OF THE SRS ROUTER REQUIRED.

- THE SRS ROUTER IS CONNECTED TO AN ANALOG MODEM THAT IS SUPPLIED BY SIEMENS, WHICH THEN IN TURN IS CONNECTED TO AN ANALOG PHONE LINE THAT IS SUPPLIED BY THE CUSTOMER. ONE SRS ROUTER ALLOWS REMOTE DIAGNOSTICS TO MULTIPLE MEDICAL SYSTEMS.

- THE SRS ROUTER SHOULD BE INSTALLED IN A SECURE LOCATION (CUSTOMER'S NETWORK COMPUTER ROOM) THAT HAS LIMITED ACCESS. IT CAN BE LOCATED ON A SHELF, TABLE, OR IN A CABINET. THE CONNECTION CABLES (WITH INDICATED LENGTHS BELOW) ARE INCLUDED WITH DELIVERY.

SRS ROUTER CONNECTION DIAGRAM



NOTE: ALL POWER OUTLETS ARE SUPPLIED/INSTALLED BY CUSTOMER.

- 1) ETHERNET SWITCH OR HUB, SUPPLIED BY CUSTOMER
- 2) SRS ROUTER, SUPPLIED BY SIEMENS (SIZE: 11.2"W x 8.7"D x 5.5"H, WEIGHT: 2 LBS.)
- 3) ANALOG MODEM, SUPPLIED BY SIEMENS
- 4) ANALOG PHONE LINE, SUPPLIED BY CUSTOMER

SIEMENS REMOTE SERVICE

SCALE: NONE

LIGHTING GUIDELINES

EXAM, CONTROL, AND EVALUATION ROOMS:

- 1) THE ROOM LIGHTING MUST REMAIN FUNCTIONAL WHEN THE MR SYSTEM IS SWITCHED OFF AND/OR WHEN EMERGENCY SHUTDOWN BUTTONS ARE ACTIVATED.
- 2) IT MUST BE POSSIBLE TO CONTROL THE INTENSITY OF ILLUMINATION OF APPROXIMATELY 46 FOOT-CANDELES THROUGH GROUP CONNECTION. ALL LIGHTS IN THE EXAMINATION ROOM ARE CONNECTED TO A COMMON SWITCH IN THE CONTROL ROOM. THERE SHOULD BE SEPARATE SWITCHES IN THE EXAMINATION ROOM FOR THE GROUPS OF LIGHTS ABOVE AND NEAR THE PATIENT TABLE, AS WELL AS FOR THE GROUP OF LIGHTS ABOVE THE MAGNET. THE LOCATION OF THESE SWITCHES IS AT THE OWNER'S DISCRETION.

EXAMINATION ROOM:

- 1) THE MAGNETIC FIELD ADVERSELY AFFECTS THE OPERATING LIFE OF LIGHT BULBS LOCATED IN THE IMMEDIATE VICINITY OF THE MAGNET. THE FILAMENT IN THE BULB OSCILLATES WITH THE FREQUENCY OF THE POWER SUPPLY. DURING SCANNING, IT IS RECOMMENDED THAT LIGHT FIXTURES IN THE VICINITY OF THE MAGNET (IN EXAMINATION ROOM) BE CONNECTED TO A DC VOLTAGE SUPPLY. THE RESIDUAL RIPPLE OF THE DIRECT VOLTAGE SHOULD BE ±5%. WHEN INSTALLING THE LIGHT SOCKET, ENSURE THAT THE POLARITY IS CORRECT.
- 2) FLUORESCENT LIGHTS, ENERGY-SAVING LIGHTS, AND DIMMERS ARE NOT PERMITTED.

CONTROL AND EVALUATION ROOM:

FOLLOW THE APPROPRIATE GUIDELINES FOR LIGHTING IN ROOMS WITH MONITOR WORKSTATIONS.

EQUIPMENT ROOM:

ILLUMINATION INTENSITY SHOULD BE APPROXIMATELY 46 FOOT-CANDELES.

ELECTRICAL INSTALLATION NOTES

- 1) INSTALL THE MR SYSTEM CIRCUIT BREAKER NEAR OR IN THE EQUIPMENT ROOM. THE PERMITTED FRINGE FIELD FOR THE PANEL IS UP TO 3mT. IF THE FRINGE FIELDS HAVE HIGHER VALUES, MAGNETIC SHIELDING MUST BE PROVIDED OR THE DISTANCE FROM THE MAGNET MUST BE INCREASED.
- 2) A UNDERVOLTAGE TRIP CIRCUIT BREAKER FOR SWITCHING MAIN POWER AND OFF SHOULD BE INSTALLED IN THE MAIN BREAKER PANEL. INSTALL EMERGENCY SHUTDOWN BUTTONS IN INDIVIDUAL ROOMS ACCORDING TO THE ELECTRICAL INSTALLATION PLAN. THE BUTTONS INTEGRATED IN THE ALARM BOX (AB) IN THE CONTROL ROOM SHOULD BE USED FOR SWITCHING THE SYSTEM ON AND OFF.
- 3) WALL RECEPTACLES MADE OF FERROMAGNETIC MATERIALS ARE NOT PERMITTED IN THE EXAM ROOM. PERIPHERAL UNITS (SUCH AS SERVO-VENTILATORS) NOT APPROVED FOR USE IN A HIGH MAGNETIC FIELD ENVIRONMENT CAN INFLUENCE THE MAGNETIC FIELD, COMPROMISING IMAGE QUALITY. THE CUSTOMER IS RESPONSIBLE FOR INSTALLATION AND USE OF RECEPTACLES IN THE EXAM ROOM. INSTALLATION OF RECEPTACLES AND THE FILTERS REQUIRED ARE TO BE COORDINATED WITH THE RF SHIELDING SUPPLIER.
- 4) THE EMERGENCY POWER OFF BUTTONS (EPO) ARE TO BE SIEMENS 52PA2W2A OR EQUIVALENT "EMERGENCY STOP" MUSHROOM BUTTONS WITH PUSH LOCK AND PULL TO RELEASE.
- 5) THE RF SHIELD MUST BE FITTED WITH A GROUND STUD OR BUS BAR, LOCATED WITHIN 24" OF THE AUXILIARY FILTERS FOR ROOM LIGHTS AND OUTLETS, SUPPLIED AND INSTALLED BY THE RF SHIELD SUPPLIER.
- 6) ALL CUSTOMER OR CUSTOMER/CONTRACTOR SUPPLIED AC POWER ENTERING THE EXAMINATION ROOM (I.E. OUTLETS, EPO, ETC.) SHOULD BE SUPPLIED VIA AN ISOLATION TRANSFORMER. THE ISOLATION TRANSFORMER SECONDARY WINDING GROUND CONDUCTOR SHOULD BE CONNECTED TO THE RF SHIELD GROUND STUD OR BUS BAR. SEE NOTES 5 ABOVE AND THE AUXILIARY AC POWER FOR EXAMINATION EXAMINATION ROOM DETAIL.

POWER QUALITY NOTES

- 1) IT IS THE CUSTOMER'S RESPONSIBILITY TO COMPLY WITH THE POWER QUALITY REQUIREMENTS FOR SIEMENS MEDICAL SYSTEMS EQUIPMENT.
- 2) THE ELECTRICAL FEEDER TO THE SIEMENS MEDICAL SYSTEM EQUIPMENT MUST FEED ONLY THE IMAGING SYSTEM AND BE KEPT SEPARATE FROM ELECTRICAL FEEDERS TO HVAC, MOTORS, PUMPS, COMPRESSORS, ELEVATORS, AND OTHER POTENTIAL SOURCES OF ELECTRICAL INTERFERENCE.
- 3) THE ELECTRICAL FEEDER TO THE IMAGING SYSTEM MUST BE RUN DIRECTLY TO A MAIN FACILITY DISTRIBUTION PANEL OR TO THE FACILITY SERVICE ENTRANCE, WITH NO OTHER LOADS POWERED FROM THIS FEEDER.
- 4) IN ORDER TO COMPLY WITH IMAGING SYSTEM POWER QUALITY REQUIREMENTS, ADDITIONAL POWER CONDITIONING DEVICES MAY BE REQUIRED. EXAMPLES INCLUDE VOLTAGE REGULATORS, TRANSFORMERS, SURGE PROTECTIVE DEVICES, FILTERS, AND/OR UNINTERRUPTIBLE POWER SUPPLIES (UPS). RECOMMENDATIONS FOR THE INSTALLATION OF ELECTRONIC EQUIPMENT CAN BE FOUND IN IEEE STANDARD 1100-1999 "POWERING AND GROUNDING ELECTRONIC EQUIPMENT."
- 5) POWER CONDITIONING DEVICES NOT APPROVED BY SIEMENS MEDICAL SYSTEMS MAY NOT BE COMPATIBLE WITH THE MAGNETOM SYSTEM. "FERRORESONANT" POWER CONDITIONING EQUIPMENT RE-APPLIED FROM PREVIOUS GENERATION SYSTEMS IS ALSO GENERALLY EXCLUDED DUE TO HIGHER POWER REQUIREMENTS OF THE NEWER SYSTEMS.

GROUNDING NOTES

EQUIPMENT GROUND CONDUCTOR TO COMPLY WITH THE FOLLOWING:

- 1) SIZED EQUIVALENT TO THE PHASE CONDUCTORS (FULL SIZED GROUND).
- 2) DERIVED FROM THE ELECTRICAL SERVICE, TRANSFORMER OR MAIN DISTRIBUTION PANEL FEEDING THE SIEMENS EQUIPMENT.
- 3) RUN IN THE SAME CONDUIT, TROUGH OR RACEWAY AS THE PHASE CONDUCTORS.
- 4) CONTINUOUS, WITH NO BREAKS OR USE OF CONDUIT, CHASSIS OR EARTH AS THE SOLE GROUNDING PATH.
- 5) BONDED TO CHASSIS AND/OR CONDUIT IN ACCORDANCE WITH THE NEC REQUIREMENTS.
- 6) MINIMIZE CONNECTIONS OR TERMINALS TO ENSURE CONTINUITY OVER THE LIFE OF THE INSTALLATION.
- 7) AS A NORM, THERE SHOULD NOT BE ANY CURRENT PRESENCE ON THE GROUND CONDUIT, BUT IT IS ACCEPTABLE TO HAVE $\leq 500\text{mA}$ DURING OPERATION OF THE IMAGING EQUIPMENT.
- 8) THERE MAY BE SOME APPLICATIONS WHICH REQUIRE AN ISOLATED GROUND AS PER NEC 250-96B.


CONDUITS AND RACEWAYS

- 1) ALL POWER CONDUCTORS SUPPLIED BY THE CUSTOMER/ CONTRACTOR SHALL BE INSTALLED IN METAL RACEWAY, 600 VOLT CLASS, STRANDED TYPE THIN-WALL, RATED FOR 75°C (165°F) OPERATION. RECOMMEND MINIMUM 5 FEET WIRE TAILS AT ALL OUTLET POINTS WITH WIRE IDENTIFICATION TAGGED AT BOTH ENDS FOR FINAL CONNECTION BY SIEMENS MEDICAL SYSTEMS.
- 2) THE CABLE GROUPS INCLUDED WITH THE MAGNETOM SYSTEM MAY BE ROUTED IN THE SAME CABLE TRAY IF PROVIDED WITH AN 8" SEPARATION BETWEEN SMALL SIGNAL LINES, GRADIENT CABLES, AND THE RF TRANSMIT CABLE. A 24" WIDE LADDER TYPE CABLE TRAY IS RECOMMENDED. CABLES SHOULD NOT BE BUNDLED TOGETHER.
- 3) NOTE THE CABLE CONNECTOR SIZES (LARGEST CONNECTOR SIZE IS 2 1/2" x 2 1/2") FOR CABLE FEED-THROUGHS AND CABLE DUCTS.
- 4) THE CABLE LENGTHS SPECIFIED ARE THE STANDARD RATED.
- 5) THE SIEMENS SYSTEM CABLES ARE NOT PLENUM RATED AND SHOULD NOT BE RUN UNPROTECTED IN AN AIR PLENUM UNLESS ENCLOSED IN A SEALED CABLE TRAY OR CONDUIT.

MR GROUNDING NOTES


THE INTERNAL GROUND WIRING OF THE MR SYSTEM MUST BE INSTALLED WITH MINIMUM GROUND LOOPS. THIS IS TO PREVENT NOISE CURRENTS AND GENERAL DISTURBANCES FROM FLOWING THROUGH THE GROUNDING PATH.

TO ACHIEVE SUCH GROUNDING, THREE MAJOR GROUND POINTS SHOULD BE USED.



CABLE SEPARATION

THE PROPER ROUTING OF CABLES IS ESSENTIAL TO ACHIEVE GOOD IMAGE QUALITY. RF CABLES MUST BE SEPARATED FROM FIBER OPTIC, BY AT LEAST 12" AND FROM THE GRADIENT CABLES BY AT LEAST 12". FIBER OPTIC CABLES MUST ALSO BE SEPARATED FROM THE GRADIENT CABLES BY AT LEAST 12". THIS SHOWS RACEWAY/CABLE ROUTING.




CABLE DESIGNATIONS ARE SHOWN AS AN EXAMPLE. ANY CATEGORY CABLE CAN BE LOCATED IN ANY OF THE COMPARTMENTS OF THE RACEWAY AS LONG AS CORRECT SEPARATIONS ARE MAINTAINED.

WHEN ROUTING RACEWAYS, DO NOT EXCEED THE MAXIMUM LENGTHS LISTED IN DETAIL E-501/2. EXCESS CABLE SHOULD BE ROUTED IN THE RACEWAY IN A MEANDERING METHOD, NEVER ROLLED IN LOOPS.

THE BENDING RADIUS FOR THE CABLES MUST BE MAINTAINED.
TRANSMITTER CABLE - 5" WHEN BENT ONCE.
TRANSMITTER CABLE - 1.4,25 WHEN BENT SEVERAL TIMES.
FIBER OPTIC CABLE - 6"
GRADIENT CABLE - 5.5" (ONLY WITH EXTENDED CABLE SET)
FIBER OPTIC CABLE FOR PATIENT OBSERVATION - 2"


CABLE SEPARATION

SCALE: NONE



SIEMENS SYSTEM CABLING - FREE CABLE LENGTHS

SCALE: NONE



AUXILIARY AC POWER FOR EXAMINATION ROOM

SCALE: NONE

ATTENTION:

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.

- THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.


- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.

- THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

<p>PROJECT MANAGER: JIM WILTHROW TEL: (402) 960-7654 FAX: (402) 502-3001 EMAIL: JWILTHROW@CASSLING.COM</p>		<p>SKYRA 02/24/12</p>	
<p>SIEMENS</p>			
<p>UNIVERSITY OF NEBRASKA - LINCOLN</p> <p>MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583 MRI SUITE - MAGNETOM SKYRA W/FIXED TABLE</p>			
<p>PROJECT #: 1201431</p>		<p>SHEET: E-501</p>	
<p>ROOM SHIELDING: 1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS</p>		<p>THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW.</p>	
<p>ALL RIGHTS ARE RESERVED.</p>		<p>DATE: 06/18/12</p>	
<p>SCALE: AS NOTED</p>		<p>REF. # 50151667</p>	
<p>DATE: 06/29/12</p>		<p>DESCRIPTION: MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC</p>	
<p>DATE: 06/29/12</p>		<p>DESCRIPTION: ROOM SHIELDING.</p>	
<p>DATE: 06/18/12</p>		<p>DESCRIPTION: 1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS</p>	
<p>-ISSUE BLOCK-</p>			
<p>SYMBOL</p>		<p>DATE</p>	
<p>DESCRIPTION</p>		<p>DRAWN BY: D. BRISTOLE</p>	
<p>CHECKED:</p>		<p>DATE: 06/18/12</p>	

REFERENCE DOCUMENT - NOT FOR CONSTRUCTION



MECHANICAL PLAN


SCALE: 1/4" = 1'-0"

ENVIRONMENTAL REQUIREMENTS

- AIR CONDITIONING IS TO PROVIDE A TEMPERATURE OF 70°F ±5°F IN THE CONTROL & EQUIPMENT ROOMS 65°F-71°F IN EXAM ROOM. RELATIVE HUMIDITY OF 40-60% (NON-CONDENSING) IS REQUIRED EXAMINATION ROOM AND 40-80% (NON-CONDENSING) IN ALL OTHER AREAS WHERE SIEMENS EQUIPMENT IS INSTALLED. THESE CONDITIONS ARE TO BE MET AT ALL TIMES; 24 HOURS A DAY, 7 DAYS A WEEK.
- A DEDICATED AIR CONDITIONING AND HUMIDIFICATION SYSTEM IS RECOMMENDED FOR THE EXAM ROOM. A MINIMUM AIR EXCHANGE RATE OF 6 TIMES PER HOUR FOR THE EXAM ROOM IS REQUIRED. IT IS RECOMMENDED TO INSTALL A FRESH AIR SYSTEM WITH 30%-50% FRESH AIR INTAKE.
AIR SUPPLY AND RETURN ABOVE THE FINISHED CEILING IN THE EXAM ROOM IS RECOMMENDED. EACH ROOM SHOULD HAVE A DEDICATED CONTROL AND SENSOR TO MONITOR AND ADJUST THE AIR.
- THE HEAT INTO THE EXAM ROOM IS LESS THAN 10,236 BTU/HR. THE HEAT INTO THE EQUIPMENT ROOM IS LESS THAN 3,412 BTU/HR. THIS HEAT DISSIPATION IS FROM THE SIEMENS EQUIPMENT ONLY. AUXILIARY SUPPORT EQUIPMENT (i.e. UPS) AND LIGHTING MUST BE CONSIDERED FOR TOTAL HEAT LOADS.
- IT IS IMPORTANT FOR FRESH AIR INTAKE SYSTEMS TO EXHAUST AIR DIRECTLY OUT OF THE BUILDING. THE EXHAUST AIR MUST NOT BE DEFLECTED INTO ANOTHER ROOM. THE MAGNET ROOM EXHAUST AIR SHOULD BE INSTALLED AT LEAST 6'-6" ABOVE FINISHED FLOOR.
- THE AIR INTAKE OF THE AIR CONDITIONING SYSTEM MUST NOT BE LOCATED IN THE VICINITY OF THE QUENCH VENT EXHAUST.
- IF THE INPUT DRAWS UPON AIR FROM OUTSIDE THE BUILDING, IT IS RECOMMENDED TO INSTALL AN ON-SITE FILTER TO REMOVE DUST PARTICLES GREATER THAN 10 MICRONS.

CHILLED WATER SUPPLY


A CHILLED WATER SUPPLY IS REQUIRED TO THE MRI SYSTEM 24 HOURS A DAY, YEAR ROUND FOR THE COOL HEAD AND GRADIENT SYSTEMS. THIS CAN BE PROVIDED BY A CENTRAL CHILLED WATER SUPPLY OR A SEPARATE STAND ALONE CHILLER THAT MEETS THE STATED REQUIREMENTS. THE CHILLED WATER CAN ALSO BE SUPPLIED BY A DEDICATED KRAUS ECO CHILLER AND INTERFACE PANEL. WITHOUT THE USE OF A DEDICATED KRAUS CHILLER, A SEP (SYSTEM SEPARATOR CABINET), MUST BE INCLUDED WITH THE SIEMENS ORDER. THE PIPE SIZE BETWEEN THE KRAUS CHILLER AND INTERFACE PANEL OR BETWEEN THE WATER SUPPLY AND SEP MUST BE 2 INCH UP TO 82 FEET, 2-1/2 INCH UP TO 148 FEET, CONSULT FOR LONGER PIPE. PERMISSIBLE MATERIALS THAT CAN BE USED FOR THE PIPING ARE: STAINLESS STEEL (V2A, V4A), NON-FERROUS METAL (COPPER, BRASS), SYNTHETIC MATERIAL, PLASTICS, BRAZING SOLDER, HARD SOLDER, OR FITTING SOLDER TYPE 3 AND 4. THERE ARE MATERIALS THAT MAY CAUSE DAMAGE TO THE COOLING SYSTEM AND CANNOT BE USED. THESE MATERIALS ARE ALUMINUM, IRON, CARBON STEEL, ZINC, ZINC PLATED STEEL, OR STANDARD STEEL PIPES. THESE REQUIREMENTS ARE REQUIRED FOR NEW INSTALLATIONS, IF EXISTING WATER PIPES COMPLY WITH SIEMENS WATER SPECIFICATIONS, THEY DO NOT NEED TO BE REPLACED. NORMAL TAP WATER MUST BE AVAILABLE FOR FILLING THE SECONDARY WATER CIRCUIT. THERE SHALL BE A HOSE BIB LOCATED WITHIN 65' OF THE SEP, I/P, ACC OR THE KRAUS CHILLER. THE SUPPLY AND RETURN CHILLED WATER PIPES MUST BE LABELED. THE LOCATION OF THE LABELS MUST BE AT ALL CONNECTION AND REFILLING POINTS AND MUST CONTAIN FLOW DIRECTION AND CONTENTS.



CEILING HEIGHTS

MAGNET EXAMINATION ROOM: 7-11" MINIMUM
EQUIPMENT ROOM: 7'-3" MINIMUM WITH RESTRICTION
ALL ANCILLARY AREAS: 6'-11" MINIMUM

ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.



CHILLED WATER REQUIREMENTS

WATER REQUIREMENTS TO BE MEASURED AT THE SEP CABINET.

FLOW RATE:	26.42 GPM ±2.64 GPM
WATER TEMPERATURE:	43°F - 53°F
BTU DISCHARGE TO THE WATER	204,729 BTU/HR
WATER PRESSURE	MAXIMUM 87 PSI
LOSS OF PRESSURE FOR SEP CABINET	14.5 PSI MAXIMUM
CHILLED WATER ACIDITY RANGE	6 pH TO 8 pH
CHILLED WATER HARDNESS	<250 ppm CALCIUM CARBONATE
CHLORINE GAS CONCENTRATION	<200 ppm
FILTRATION	700 μm

FOR INSTALLATION OF A KRAUS ECO CHILLER, IT IS THE RESPONSIBILITY OF THE CUSTOMER/MECHANICAL CONTRACTOR TO PROVIDE A MIXTURE OF WATER WITH 35%-38% ETHYLENE GLYCOL PRIOR TO CHILLER START UP. DO NOT USE PROPYLENE GLYCOL OR AUTOMOTIVE ANTI-FREEZE.

THE AMOUNT OF THE MIXTURE MUST FILL THE CHILLER, MR SYSTEM AND PIPING (SUPPLY AND RETURN), SEE EXAMPLES BELOW.

(1) GALLON OF UNDILUTED GLYCOL OR (2) GALLONS OF WATER/GLYCOL MIXTURE MUST REMAIN ON SITE FOR USE AFTER START UP.

PIPE DIAMETER	TOTAL LENGTH	MIXTURE VOLUME	GLYCOL NEEDED
2"	100'	31.3 GALLONS	11.9 GALLONS
2"	200'	47.6 GALLONS	18.1 GALLONS
2.5"	100'	40.5 GALLONS	15.4 GALLONS
2.5"	200'	66.0 GALLONS	25.1 GALLONS

MIXTURE VOLUME = 3.14 x (PIPE RADIUS)² x PIPE LENGTH + 15 GALLONS.
GLYCOL AMOUNT = 35-38% OF MIXTURE VOLUME.

MECHANICAL NOTES

- THE AIR H.V.A.C. SYSTEM MUST OPERATE FOR A MINIMUM OF 48 CONSECUTIVE HOURS PRIOR TO THE DELIVERY OF THE EQUIPMENT.
- THE FILTERS MUST BE CHANGED IMMEDIATELY PRIOR TO THE DELIVERY OF THE EQUIPMENT.
- SMS REQUIRES THE USE OF A DEDICATED H.V.A.C. SYSTEM FOR THE EQUIPMENT ROOM TO BE LOCATED, SIZED AND SPECIFIED BY THE MECHANICAL ENGINEER OF RECORD AND TO BE SUPPLIED AND INSTALLED BY THE MECHANICAL CONTRACTOR.
- SMS RECOMMENDS THAT THE CUSTOMER PROVIDE AND INSTALL AN OXYGEN MONITORING SYSTEM WITH VISUAL AND AUDIBLE ALARMS TO INDICATE WHEN THE OXYGEN CONTAINED IN AMBIENT AIR FALLS BELOW PRE-PROGRAMMED SAFETY LEVELS WITH THE SENSOR TO BE LOCATED IN THE SCAN ROOM IN THE AREA DESIGNATED FOR OXYGEN FILLING.
- THE SIEMENS ACTIVE SHIELDED MAGNET RECIRCULATES LIQUID HELIUM, ELIMINATING THE NEED FOR A DEDICATED CRYOGEN STORAGE AREA. THE RECIRCULATING SYSTEM SIGNIFICANTLY REDUCES THE HELIUM "BOIL OFF". THE MAGNET WILL REQUIRE OCCASIONAL FILLING. A DELIVERY ROUTE FOR CRYOGEN DEWAR'S MUST BE ESTABLISHED. A MINIMUM 36" CLEARANCE IS REQUIRED.

FIRE CONTROL NOTES

- SIEMENS HAS NO SPECIFIC REQUIREMENT FOR FIRE PROTECTION. FIRE PROTECTION REQUIREMENTS SHALL BE IN ACCORDANCE WITH LOCAL CODES AND CUSTOMER'S INSURANCE REQUIREMENTS. ALL FIRE PROTECTION SYSTEMS SHALL BE DEFINED BY THE ARCHITECT OF RECORD WITH DESIGN, SPECIFICATION AND DETAILING OF THE FIRE PROTECTION SYSTEM BY THE MECHANICAL ENGINEER OF RECORD IN ACCORDANCE WITH SIEMENS GUIDELINES AS STATED HEREIN.
THE ELECTRONIC EQUIPMENT OF THE MR SYSTEMS WILL BE DAMAGED BY WATER. REDUCTION OR ELIMINATION OF WATER USED FOR FIRE SUPPRESSION WILL REDUCE POTENTIAL WATER DAMAGE. PRE-ACTION INERT GAS, OR HALOCARBONS OR OTHER METHODS CAN REDUCE OR ELIMINATE WATER. REFER TO YOUR FIRE PROTECTION PROFESSIONAL.
- THE USE OF SMOKE DETECTORS INSIDE OF THE MR EXAMINATION ROOM IS NOT RECOMMENDED. SMOKE DETECTORS, BY DESIGN, CAN GENERATE NOISE THAT MAY INTERFERE WITH THE MRI EXAMINATION AND CAUSE IMAGE ARTIFACTS. IF THE USE OF A SMOKE DETECTOR IN THE EXAMINATION ROOM IS MANDATED BY LOCAL REQUIREMENTS, SPECIAL NOISE TESTS MUST BE PERFORMED BY SIEMENS SERVICE AFTER THE MRI IS OPERATIONAL. MRI EQUIPMENT PERFORMANCE PROBLEMS DUE TO SMOKE DETECTORS ARE THE RESPONSIBILITY OF THE CUSTOMER AND ARE NOT COVERED UNDER WARRANTY OR SERVICE AGREEMENT.
- ALL MATERIAL USED INSIDE THE MAGNET ROOM SHALL BE NON-MAGNETIC.
- ALL PENETRATIONS IN THE RF CABIN/SHIELD SHALL BE THROUGH A WAVEGUIDE TO BE EQUIPPED WITH A SIEMENS APPROVED DIELECTRIC COUPLER ON BOTH ENDS OF THE WAVEGUIDE. ALL WAVEGUIDES SHALL BE DESIGNED, DETAILED AND SPECIFIED BY THE RF CABIN/SHIELD CONTRACTOR WITH ALL LOCATIONS TO BE DETERMINED BY THE ARCHITECT AND MECHANICAL ENGINEER OF RECORD TO BE ESTABLISHED IN A PRE-PLANNING MEETING PRIOR TO THE DESIGN, SPECIFICATION, AND FABRICATION OF THE RF CABIN/SHIELD.
- EACH ELECTRICAL PENETRATION OF THE RF CABIN/SHIELD FOR ELECTRICAL SERVICING OF THE FIRE PROTECTION SYSTEM SHALL BE THROUGH AN RFI FILTER TO BE SUPPLIED BY THE RF SHIELD CONTRACTOR WITH FILTER LOCATIONS TO BE DETERMINED BY THE ARCHITECT AND THE ELECTRICAL ENGINEER OF RECORD TO BE ESTABLISHED IN A PRE-PLANNING MEETING PRIOR TO THE DESIGN, SPECIFICATION AND FABRICATION OF THE RF CABIN/SHIELD.
- IT IS PERMISSIBLE TO RUN "BLACK PIPE" UP TO THE DIELECTRIC COUPLER ON THE OUTSIDE OF THE RF SHIELD.
- THERE MUST BE NO GROUND CONNECTIONS MADE DURING THE INSTALLATION OF EITHER THE PIPING OR ELECTRICAL FOR THE FIRE PROTECTION SYSTEM.
- THE USE OF HALON IS NOT ACCEPTABLE.
- THE LOCATION OF FIRE CONTROL SYSTEM COMPONENTS SHALL BE COORDINATED THROUGH THE ARCHITECT OF RECORD WITH ALL LOCATIONS TO BE COORDINATED WITH SIEMENS EQUIPMENT LOCATIONS AS SHOWN ON THE 1/4" SCALE EQUIPMENT LOCATION PLAN.
- THE FIRE CONTROL CONTRACTOR SHALL VERIFY EQUIPMENT MOUNTING PROCEDURES AND LOCATIONS ON ANY WALLS CONTAINING RF SHIELDING WITH THE SIEMENS PROJECT MANAGER PRIOR TO THE COMMENCEMENT OF WORK.

ATTENTION:

THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.
IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

PROJECT MANAGER: JIM WILTHROW
 TEL: (402) 960-7654
 FAX: (402) 502-3001
 EMAIL: JWILTHROW@CASSELLING.COM

SIEMENS
 UNIVERSITY OF NEBRASKA - LINCOLN
 MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583
 MRI SUITE - MAGNETOM SKYRA W/FIXED TABLE

PROJECT #: **1201431**
 SHEET: **M-101**




DATE: 06/18/12
 DRAWN BY: D. BRISTOLE
 CHECKED:

ALL RIGHTS ARE RESERVED.
 SCALE: AS NOTED
 REF. # 30151667

06/29/12 MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC ROOM SHIELDING.
 06/18/12 1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS

SYMBOL DATE DESCRIPTION

-ISSUE BLOCK-



CRYOGEN NOTES

- "CRYOGENS" IS A TERM USED TO IDENTIFY THE REFRIGERANT USED TO MAKE THE MAGNET "SUPER-CONDUCTING". IN THIS APPLICATION, LIQUID AND GASEOUS HELIUM, IN THEIR LIQUID STATE THE CRYOGENS CAN REACH 4.2K (-452°F). SPECIAL CARE MUST BE TAKEN DURING THE TRANSFILLING OF THE MAGNET WITH CRYOGENS AND NORMAL EXHAUST OF CRYOGENS FROM THE SYSTEM. ASIDE FROM THE OBVIOUS DANGER OF FREEZING, HELIUM GAS WILL ALSO DISPLACE THE OXYGEN IN THE ROOM. THE INSTALLATION OF AN APPROVED TOXGARD OXYGEN MONITORING SYSTEM IS RECOMMENDED.
- A TRANSPORT ROUTE FOR DELIVERY OF CRYOGENS TO THE EXAM ROOM. SPECIAL VESSELS CALLED DEWARs ARE USED TO TRANSPORT HELIUM. A 250 LITER DEWAR WEIGHS 335 POUNDS AND HAS A 32" DIAMETER, A 500 LITER IS 540 POUNDS, AND 42" IN DIAMETER.
- OUTSIDE VENTING OF THE HELIUM IS TO BE PROVIDED BY MEANS OF A VENT PIPE OF NON-MAGNETIC MATERIAL CALLED A QUENCH VENT.





QUENCH VENT NOTES

- IN THE EVENT OF A QUENCH, THE THERMAL ENERGY DISSIPATED CAUSES AN EXTREMELY RAPID BOIL OFF OF THE LIQUID HELIUM. THE SYSTEM MUST BE CAPABLE OF VENTING THE LARGE VOLUME OF GAS GENERATED AT THE APPROXIMATE EXPANSION RATIO OF 1:700 FROM LIQUID AT 4.2K TO ROOM TEMPERATURE GAS. THE EXHAUST SYSTEM IS CRITICAL FOR THE SAFE OPERATION OF THE MAGNET. THE DATA IN THIS DOCUMENT MUST BE FOLLOWED, SINCE HELIUM VENTED IN A QUENCH IS AN ASPHYXIANT & AN EXTREMELY COLD GAS, THE QUENCH TUBE MUST ALWAYS END AT A POINT WHERE ACCESS BY PEOPLE IS NOT POSSIBLE. QUENCH TUBE PLANNING MUST ONLY BE DONE BY QUALIFIED PERSONNEL. IT IS THE OWNER'S RESPONSIBILITY TO ENSURE THAT THE QUENCH TUBE IS MAINTAINED IN AN OPERABLE STATE.
- IF THE QUENCH VENT IS NOT CONFIGURED CORRECTLY THERE IS A RISK OF DANGER THAT MAY LEAD TO DEATH OR SERIOUS INJURY AND CAN RESULT IN STRUCTURAL DAMAGE. THE EXHAUST MUST NOT BE VENTED IN AN ENCLOSED SPACE. THE OPERATOR OF THE SYSTEM MUST PREPARE AN EMERGENCY PLAN IN THE EVENT OF A QUENCH.
- THE QUENCH TUBE CONSISTS OF STRAIGHT, HYDRAULICALLY SMOOTH SECTIONS, BENDS UP TO 90° AND A DIFFUSER, IF REQUIRED. THE END OF THE TUBE MUST BE PROTECTED FROM RAIN, SNOW, AND FOREIGN OBJECTS. ROUND SECTIONS ONLY, NO SQUARE SECTIONS.
- THE SIEMENS MAGNET HAS A QUENCH VALVE ASSEMBLY FOR CONNECTION TO THE TUBE LOCATED AT THE TOP LEFT SIDE OF THE MAGNET (SEE MAGNET ELEVATION). THE MECHANICAL CONTRACTOR WILL SUPPLY AND INSTALL A QUENCH VENT TUBE WITH CAP TO BE NON-MAGNETIC STAINLESS STEEL (>22 GAUGE, RECOMMENDED). GRADES AISI304, 309, 316, OR 321 ONLY. THERMAL CONDITIONS MAY CAUSE THE TUBE TO CONTRACT UP TO 3mm/METER 50 A STAINLESS STEEL BELLOWS OR FLEXIBLE SECTION MUST BE INSTALLED A MINIMUM OF EVERY 32'-9" NOT TO EXCEED 2% OF THE OVERALL LENGTH. THE QUENCH TUBE MAY ALSO BE MADE OF ALUMINUM, EXTRUDED TUBE ALUMINUM GRADES 6063 AND 6062 ONLY MUST BE USED. ROLLED AND WELDED TUBE FROM SHEET ALUMINUM GRADE 5083 ONLY MUST BE USED. THE WALL SECTIONS OF ALUMINUM TUBE MUST BE A MINIMUM 14 GAUGE. THERMAL CONTRACTION OF 4.5 MM/METER MUST BE CONSIDERED FOR ALUMINUM QUENCH TUBES. THE MOVEMENT OF THE BELLOWS MUST BE RESTRICTED TO PREVENT EXCESSIVE EXPANSION DUE TO PRESSURE. THE WEIGHT OF THE TUBE MUST BE SUPPORTED BY THE BUILDING AND BE FLEXIBLE ENOUGH TO ALLOW MOVEMENT FROM THERMAL CONTRACTION. THE WALL EXIT SHOULD ALSO BE FLEXIBLE.
- THE MAXIMUM INTERNAL PRESSURE IS CALCULATED AT 1.45 PSI. THE MAXIMUM PRESSURE SHOULD BE ENGINEERED FOR 6.5 PSI.
- USE THE QUENCH VENT CALCULATOR PROVIDED BY SIEMENS TO DESIGN A QUENCH VENT THAT MEETS DESIGN REQUIREMENTS FOR DIAMETER, LENGTH, NUMBER OF ELBOWS AND PRESSURE DROP. ALL BENDS MUST BE SMOOTH WALLED AND HAVE A CENTERLINE TO INTERNAL PIPE DIAMETER RATIO OF 1.5 TO 5.0. EXPANSIONS TO PIPE DIAMETER CAN BE DONE WITH A DIFFUSER. ONLY ROUND TUBE SECTIONS MAY BE USED. RECTANGULAR SECTIONS ARE NOT ALLOWED.
- THERE MUST BE A 12-19 INCH FLEXIBLE SECTION OF PIPE FOR CONNECTION TO THE QUENCH VALVE AT THE MAGNET WITH AN INSIDE DIAMETER GREATER THAN 4" (1.5T) OR 6" (3.0T) AND ABLE TO WITHSTAND 6.5 PSI.
- SECTIONS OF THE PIPE CAN ONLY BE JOINED BY WELDING OR BOLTED FLANGES WITH FIBER GASKETS. ROTARY FLANGES ARE PERMITTED, VEE CLAMPED FLANGES MAY NOT BE USED.
- THE PROTECTION AT THE END OF THE TUBE SHALL BE 3/8" WIRE MESH COVERING AN AREA AT LEAST 2.5 TIMES THE CROSS SECTION AREA OF THE QUENCH PIPE.
- WHERE THE QUENCH TUBE EXISTS THROUGH A FLAT ROOF, THE TUBE MUST BE ABOVE A LEVEL WHERE WATER COULD ENTER IN THE EVENT THAT THE ROOF DRAINS BECOME BLOCKED. IN THE CASE OF A HORIZONTAL EXIT THROUGH A WALL, THE OUTLET SHOULD BE ANGLED DOWNWARD NOT LESS THAN 1 PIPE DIAMETER TO PREVENT RAIN INGRESS. THE EXIT SHOULD BE LOCATED ABOVE THE LEVEL OF DRIFTING SNOW.
- WHERE THE QUENCH TUBE EXISTS VERTICALLY, A RAIN COVER MUST ALSO BE FITTED WITH THE DIAMETER TO BE TWO TIMES THE DIAMETER OF THE QUENCH TUBE. THE CLEARANCE BETWEEN THE RAIN GUARD AND THE MESH SHOULD 2 TIMES THE DIAMETER OF THE TUBE. A DEFLECTOR PLATE SHOULD BE WELDED TO THE TUBE WHERE IT EXISTS THE ROOF TO PREVENT HELIUM FROM RE-ENTERING THE BUILDING. THE DEFLECTOR SHOULD BE AT LEAST THE DIAMETER OF THE RAIN GUARD AND LOCATED TWO PIPE DIAMETERS ABOVE THE ROOF AND TWO PIPE DIAMETERS BELOW THE RAIN GUARD.
- TO AVOID INJURY FROM COLD BURNS AND ASPHYXIATION ACCESS TO THE QUENCH VENT MUST BE RESTRICTED BY 9'-11" ON EACH SIDE AND BELOW, AND 19'-9" ABOVE WITH WARNING SIGNS. THE EXIT MUST NOT BE LOCATED WHERE HELIUM GAS COULD BE DRAWN INTO AN AIR INLET OR OPEN WINDOW.
- THE QUENCH TUBE MUST HAVE MINIMUM 1" INSULATION FOR THE FULL LENGTH. WITHIN THE RF ROOM THERE SHOULD BE A 1" LAYER OF MINERAL FIBER INSULATION WITH A VAPOR BARRIER AND 1" CLASS O OR CLASS AP ARMAFLEX. OUTDOOR PIPES MUST BE WEATHERPROOF. THE TUBE MUST HAVE A WARNING POSTED ALONG ITS ENTIRE LENGTH FOR EXTREMELY COLD HELIUM GAS. AUTHORIZED PERSONNEL ONLY. THE INSULATION MUST NOT TOUCH THE MAGNET COVERS.
- GALVANIC SEPARATION MUST BE PROVIDED BETWEEN THE MR SYSTEM, THE RF ROOM, AND THE BUILDING, TWO SEPARATIONS ARE REQUIRED USING STAINLESS STEEL BOLTS, INSULATING BUSHES AND LOCKING NUTS. NO OTHER DESIGNS ARE PERMITTED FOR SAFETY.
- THE DESIGN AND CONSTRUCTION OF THE QUENCH PIPE MUST BE DOCUMENTED WITH DRAWINGS AND CALCULATIONS THAT ARE KEPT WITH INSTALLATION DOCUMENTS. IT MUST COMPLY WITH THE REQUIREMENTS IN THIS DOCUMENT BEFORE BEING CONNECTED TO THE MAGNET.

HELIUM CONTENT

LITERS AT 100%	1,190	FOR TYPICAL CLINICAL USE, DEPENDING ON SEQUENCES AND OPERATING TIME.
TYPICAL BOIL OFF RATE	0.0 L/HR	
TYPICAL REFILL INTERVAL	10 YEARS	

WITHOUT THE COLDHEAD RUNNING THE LIQUID HELIUM WILL BOIL OFF FROM 98% TO 0% IN APPROX 29 DAYS. THE LOSS DURING SHIPPING IS APPROX. 3.3% PER DAY.



ATTENTION:

- THIS DRAWING IS DESIGNED TO CONFORM TO FEATURES AND EQUIPMENT REQUIREMENTS PRESENTED AT THE TIME OF THEIR PREPARATION. SINCE BOTH THESE FACTORS ARE SUBJECT TO DESIGN MODIFICATION, THEY ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES.
- THIS SET OF PLANS REPRESENTS A COMPLETE SET OF DETAILS AND SHOULD NOT BE SEPARATED.

- IT IS RECOMMENDED THAT THE SIEMENS DRAWINGS BE INCORPORATED WITH THE CONSTRUCTION DOCUMENTS FOR REFERENCE.

- ALL DIMENSIONS SHOWN ON THIS DRAWING ARE FROM FINISHED SURFACES.
- THIS DRAWING DOES NOT PROVIDE RADIATION SHIELDING REQUIREMENTS FOR X-RAY AND ASSOCIATED EQUIPMENT. THE CUSTOMER IS RESPONSIBLE FOR CONSULTING WITH A REGISTERED RADIATION PHYSICIST TO SPECIFY RADIATION PROTECTION.

PROJECT MANAGER: JIM WILTHROW TEL: (402) 960-7654 FAX: (402) 502-3001 EMAIL: JWILTHROW@CASSLING.COM		SIEMENS	
UNIVERSITY OF NEBRASKA - LINCOLN MEMORIAL STADIUM - EAST ADDITION, LINCOLN, NE 68583 MRI SUITE - MAGNETOM SKYRA W/FIXED TABLE		PROJECT #: 1201431	
THE USE OR REPRODUCTION OF THIS TITLE BLOCK WITHOUT SIEMENS' AUTHORIZATION WILL RESULT IN PROSECUTION UNDER FULL EXTENT OF THE LAW.		SHEET: M-501	
ALL RIGHTS ARE RESERVED.		DATE: 06/18/12	
SCALE: AS NOTED		CHECKED: D. BRISTOLE	
REF. # 50151667		DRAWN BY: D. BRISTOLE	

SYM	DATE	DESCRIPTION
△	06/29/12	MODIFIED MAGNET GAUSS FIELDS TO REFLECT THE USE OF MAGNETIC ROOM SHIELDING.
△	06/29/12	1201431RA DATED 04/24/12 APPROVED BY CUSTOMER FOR FINALS

SKYRA
02/24/12