



ADDENDUM NO. 1

Project: Fremont YMCA
Maintenance Projects

BVH Project No.: L12034
Date: July 24, 2012

This Addendum is issued by the Architect all plan holders of record prior to receipt of proposals. Bidders shall acknowledge receipt of this addendum by so indicating on the Proposal Form. Failure to do so may subject Bidder to disqualification. All information and instructions given herein shall become a part of the Contract Documents.

PRE-BID MEETING

1. The following contractors attended the pre-bid meeting:
 - a. Fauss Construction, phone: 402-654-339
 - b. Boschult Construction, phone: 402-721-1017
 - c. B-D Construction, phone: 402-564-1225
 - d. Lacey Construction, phone: 402-450-1112

PROJECT MANUAL

2. Section 096466 – 2.02D: Add AcerFlex Floor System by Acer.
3. Section 096566 – 2.01B: Add DynaCourt by LG Chem and Taraflex Sport M Performance.
4. Section 098400 – 2.01B: Add CMA Baffle, 2", 3 pound density PVC wrapped baffle by Creative Materials for Acoustics (CMA, Inc).
5. Section 098400 – 2.02E: Add the attached Installation Instructions from Kinetics Noise Control. Total panel count shall provide panel area equal 150% of the ceiling deck area, with panels spaced 24" – 28" apart. Supplier/Manufacturer shall submit a layout drawing for approval of the proposed installation. Include all structural, lighting, HVAC and other ceiling elements in place and lighting changes planned for work to occur under separate contract this fall. Owner/Electrical Contractor shall provide information of other work to occur this fall for coordination.

DRAWINGS

6. Sheet A1.1, Drawing 2, Large Gym & Fitness Studio, add note 1C to the four cross court basketball hoop locations. Omit note 1E and new 6'-0" wall padding at area between the two existing doors at the south west corner.
7. Sheet A1.1, Drawing 3, New Sidner Gym and Old Sidner Gym, painting in these rooms will not include the ceiling areas or wall areas where the finish surface is insulation systems or metal panel siding.
8. Note 4C – Add to note, "Include wall area at northwest corner of New Sidner Gym where insulation system transitions down wall to stair hallway opening.
9. The drawings including the photos on sheet A1.2 are available on A&D's website at the web address below for review online.
http://www.adtechplans.com/View/ViewJob.aspx?job_id=8995&view=ph

END OF ADDENDUM

BAHR VERMEER HAECKER ARCHITECTS

440 NORTH 8TH STREET STE 100
1425 JONES STREET

LINCOLN NE 68508
OMAHA NE 68102

402 475 4551
402 345 3060

bvh.com