

ADDENDUM NO. 1

PROJECT NAME: North 17th Rec Area
UNL PROJECT NUMBER: C906P072

CONSULTANT: Olsson Associates
ADDRESS: 1111 Lincoln Mall #1111, Lincoln, NE

DATE OF ISSUANCE: July 31, 2012
DATE OF BID OPENING: August 3, 2012

The bid documents dated May 18, 2012 for the above referenced project are amended by this addendum.

NOTICE: This Addendum is issued to all interested prospective bidders as an amendment to the project manual or other parts of the bidding (contract) documents for the above named project. Reference to this Addendum must be included in the Bid proposal. The information contained herein shall be fully incorporated into the contract documents as though originally included therein.

MODIFICATIONS TO PROJECT MANUAL:

1. Refer to Section 32 13 14 – Textured Acrylic Color Surfacing for Basketball – On Concrete
 - A. **DELETE:** Part 2: Products: Paragraphs 2.2 and 2.3 in their entirety.
 - B. The materials and installation of the synthetic court surface shall be in accordance with the attached document “Plexicourt System, Multisport Surfacing (Fine). All other provisions of Section 32 12 14 shall remain.
2. Refer to Section 03 38 16 – Unbonded Post-Tensioned Concrete
 - A. **ADD:** Paragraph 1.3: Section C: Concrete Mix Design. Contractor to supply concrete mix design to engineer for approval prior to installation.
3. Refer to Section 32 31 13 – Chain Link Fences and Gates, Paragraph 2.2 Fence Framing
 - A. Light Industrial Strength: Material Group IC, SS-30 Round Steel Tube, ASTM 1043, is accepted as an approved alternate for fence framing framework.
4. Refer to Section 00 11 16 – Invitation to Bid, Page 2 of 2, Add new Paragraph 8.0 as follows:
 - A. **LIQUIDATED DAMAGES:** The completion date required by the Owner is November 16, 2012. Liquidated damages of one hundred eighty eight dollars (\$188.00) per calendar day have been established and shall be taken into consideration by the Bidder. This amount shall be subtracted from the Contract for Construction before final payment for each calendar day Work is not substantially complete as judged by the Owner and Engineer of Record.

MODIFICATIONS TO DRAWINGS:

1. Refer to Drawing S1.1 – COURT TENDON LAYOUT DETAILS.
 - A. The concrete mix design shall develop an ultimate 28-day compressive strength of 4,000 psi.
 - B. Not less than 564 pounds of cement shall be used per cubic yard of concrete.

ADDENDUM NO. 1

Project Name: North 17th Rec Area

Project Number: C906P072

2 of 2

- C. Maximum water/cement ratio shall be 0.45
- D. Air entrainment, 3%, +/- 1%
- E. Maximum slump of 4 inches.
- F. Concrete curing compounds or concrete sealers shall not be used on the concrete slab.
- G. The post-tensioned concrete slab shall receive a medium broom finish.

2. Refer to Drawing C1.1 – SITE PLAN.

- A. **DELETE:** General Note #17.
- B. Bench locations shown on site plan are for reference only. Bench installation is not included with this project.
- C. **ADD:** General Note "Temporary chain link fencing with red fabric screening shall be provided for the entirety of the construction project."

3. Refer to Drawing C5.1 – DETAILS.

- A. Reference Water Service Connection Detail: Contractor shall provide all fittings as necessary for an air compressor connection on the water service pipe after the ½" tee and ball valve.

END OF ADDENDUM NO. 1