



5845 Huntington Ave
Omaha, NE 68507

This addendum is issued by the Owner to all known bidders prior to receipt of Proposal. Bidders shall acknowledge receipt of this Addendum by so indicating on the Proposal Form. All information and instruction given herein shall become a part of the Contract Documents.

This amendment contains the following information:

This Addendum #1

2 pages

Total **(2)** pages

If this amendment appears incomplete, notify the architect immediately.

SPECIFICATIONS

SECTION 081416 FLUSH WOOD DOORS

1. At 1.5 Quality Assurance. Delete "A. Manufacturer Qualifications: A qualified manufacturer that is certified for chain of custody by an FSC-accredited certification body."

SECTION 221005 PLUMBING PIPING

1. At 2.1 change to "Sanitary Sewer Piping, Above and Below Grade."

DRAWINGS

ARCHITECTURAL DRAWINGS

1. Sheet A1.1, A1.2 & A1.3
 - A. Add the following general notes to the drawings:

"General Demo Notes:

1. The intent of these demolition drawings is to define a general scope of demolition work. These drawings may not identify every item to be removed. The contractor shall be responsible for determining all items which must be removed to facilitate new construction. Coordinate with mechanical and electrical.
2. Dashed items in bold shall be removed by contractor. Refer to keyed notes for specific items.
3. Protect all items not slated for demolition. Contractor responsible for repair/replacement of all items damaged during demolition.
4. The contractor shall shore as required any areas affected or compromised by demolition activities.
5. Remove all material not specifically noted at interior of restrooms to studs/slab. Remove existing cavity insulation if found.

WhiteHall ADA Restroom Renovation
APMA Project No. 12023
20 August 2012

General Notes:

1. Install new drywall and sound batts at interior of restrooms at locations not specifically noted."

END OF ADDENDUM #1