ADDENDUM NO. 1

Project: General Services Building Roof Replacement
University of Nebraska Kearney

Issued: October 2, 2012

Bid Date: Thursday, October 4, 2012 – 2:00pm

This Addendum is issued to all known plan holders before receipt of proposals.

The following shall be included with, and considered a part of, the original contract documents to the same extent as if they were included therein, for the construction of the above mentioned project. The Project Manual and Drawings shall be modified or revised as herein described. Where at variance with the original work, this Addendum shall have precedence.

This Addendum modifies the original Bidding Documents. The Bidder must acknowledge receipt of this Addendum in the space provided on the Proposal Form. Failure to do so may subject bidder to disqualification.

ARCHITECTURAL ADDENDA ITEMS:

AD1.1. Clarification: The question was asked at the preconstruction meeting if the contractor could move only the junction box on the north side of the building, instead of the entire length of conduit. We believe the entire conduit will need to be moved to allow for installation of the new fascia metal. Proceed as shown on the drawings.

AD1.2. Correction: Drawing Sheet AD100: Details 1-3 – In all three details, delete and disregard the line "Insulation to remain under alternate #1". The insulation will not remain under any alternate, and Alternate #1 remains as noted in the specifications, regarding the change to a 90-mil. EDPM and 30 year warranty.

General Contractor shall acknowledge receipt of this Addendum on the Proposal Form in the space provided.

END OF ADDENDUM NO. 1

209 South 9th Street **402.475.1787 Tel.**
Lincoln, Nebraska 68508 **402.475.1800 Fax**