ADDENDUM NO. 5

Project: Beta Theta Pi Remodel – Phase 2

Issued: October 26nd, 2012

Bid Date: 2:00 pm Tuesday October 30th 2012.

This Addendum is issued to all known plan holders before receipt of proposals.

The following shall be included with, and considered a part of, the original contract documents to the same extent as if they were included therein, for the construction of the above mentioned project. The Project Manual and Drawings shall be modified or revised as herein described. Where at variance with the original work, this Addendum shall have precedence.

This Addendum modifies the original Bidding Documents. The Bidder must acknowledge receipt of this Addendum in the space provided on the Proposal Form. Failure to do so may subject bidder to disqualification.

GENERAL ELECTRICAL ADDENDA ITEMS:

AD5.1. ALL FLOORS:

1. Ceiling fan fixture #19 and fan speed controls associated with these fans, located in studies and day room shall not be provided under this contract. Provide conduit, junction boxes and circuits to all ceiling fan and speed control locations. Provide blank cover plates for junction boxes.
2. For clarification, existing data racks shall be mounted to south wall of Mech. 020. Provide 4' x 8' x ¾" plywood board with two coats of gray enamel paint. See sheet E3.01.

General Contractor shall acknowledge receipt of this Addendum on the Proposal Form in the space provided.

END OF ADDENDUM NO. 5

209 South 9th Street **402.475.1787 Tel.**
Lincoln, Nebraska 68508 **402.475.1800 Fax**