ROOM FINISH SCHEDULE

No.	Name	Floor Finish	Base	North Wall Material	North Wall Finish	East Wall Material	East Wall Finish	South Wall Material	South Wall Finish	West Wall Material	West Wall Finish	Ceiling Material	Ceiling Finish	NOTES	No.
Basement															
001	T. KITCHEN	RUB-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-3	-	-	001
001A	KITCHEN ST.	RUB-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-3	-	-	001A
002	STORAGE	S CONC	VWB *(3)	CONC	-	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	EXPOSED	-	3	002
003	TRAINING ROOM C	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-	-	003
004	MEDIA	S CONC	VWB *(3)	-	-	-	-	GWB	PNT-1	CONC	-	EXPOSED	-	1, 3	004
005	MEDIA ARCHIVES	S CONC	VWB *(3)	GWB	PNT-1	-	-	-	-	CONC	-	EXPOSED	-	1, 3	005
006	CUSTODIAL	S CONC	VWB *(3)	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	CONC	-	EXPOSED	-	3	006
007	MUSIC STORAGE	S CONC	VWB *(3)	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	CONC	-	EXPOSED	-	3	007
008	TRAINING ROOM A	CPT-1	VWB	-	-	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(5)	5	008
008A	TRAINING ROOM B	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	-	-	GWB	PNT-1	APC-1 / GWB	PNT-2 *(5)	5	008A
008B	TRAINING	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	EXPOSED	-	-	008B
009	STORAGE	S CONC	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	EXPOSED	-	-	009
010	ESU STORAGE	S CONC	VWB *(3)	PCST / GWB	PNT-1 *(21)	CONC	-	CONC	-	PCST / GWB	PNT-1 *(21)	EXPOSED	-	3, 21	010
011	CURRICULUM	S CONC	VWB *(3)	GWB	PNT-1	CONC	-	GWB	PNT-1	GWB	PNT-1	EXPOSED	-	3	011
012	ATHLETIC STORAGE	S CONC	VWB *(3)	PCST	-	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	EXPOSED	-	3	012
081	LOBBY	RUB-1 / CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-	-	081
081A	CORR.	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	-	-	APC-1	-	-	081A
081B	MENS	CT-4	CT-5, CT-6 *(17)	GWB	PNT-1	GWB	CT-1	GWB	PNT-1	GWB	CT-2	GWB	PNT-2	6	081B
081C	CUST	S CONC	VWB	GWB	PNT-1 / FRP *(2)	GWB	PNT-1 / FRP *(2)	GWB	PNT-1	GWB	PNT-1	GWB	PNT-2	2	081C
081D	SHWR	CT-2, CT-4 *(25)	CT-5, CT-6 *(17)	GWB	CT-1, PNT-1 *(26)	GWB	CT-1	GWB	CT-1, PNT-1 *(26)	GWB	CT-1, CT-2, PNT-1 *(26)	GWB	PNT-2	6, 17, 25, 26	081D
081E	ELEV. EQUIP.	S CONC	VWB	GWB	PNT-1	GWB	PNT-1	PCST	-	GWB	PNT-1	GWB	PNT-2	-	081E
081F	SHWR	CT-2, CT-4 *(25)	CT-5, CT-6 *(17)	GWB	CT-1, PNT-1 *(26)	GWB	CT-1	GWB	CT-1, PNT-1 *(26)	GWB	CT-1, CT-2, PNT-1 *(26)	GWB	PNT-2	6, 17, 25, 26	081F
081G	WOMENS	CT-4	CT-5, CT-6 *(17)	GWB	PNT-1	GWB	CT-1	GWB	PNT-1	GWB	CT-2	GWB	PNT-2	6	081G
081M	MECH / ELEC	S CONC	VWB *(3)	CONC	-	CONC	-	GWB	PNT-1	GWB	PNT-1	EXPOSED	-	3	081M
082	CORRIDOR	CPT-1	VWB	GWB	PNT-10	-	-	GWB	PNT-8	-	-	APC-1	-	-	082
083	CORRIDOR	RUB-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-	-	083
083A	CORRIDOR	S CONC	VWB *(3)	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	-	-	EXPOSED	-	1, 3	083A
083E	ELECTRICAL	S CONC	VWB *(3)	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	CONC	-	EXPOSED	-	3	083E
083M	MECHANICAL	S CONC	VWB *(3)	CONC	-	GWB	PNT-1	GWB	PNT-1	CONC	-	EXPOSED	-	3	083M
083N	MECHANICAL	S CONC	VWB *(3)	GWB	PNT-1	GWB	PNT-1	CONC	-	CONC	-	EXPOSED	-	3	083N
084	CORR.	RUB-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	-	-	APC-1	-	-	084
084M	STORAGE	CONC	VWB *(3)	GWB	PNT-1	PCST	-	-	-	GWB	PNT-1	EXPOSED	-	1	084M
084N	DATA CENTER	CONC	VWB *(3)	-	-	GWB	PNT-1	CONC	-	GWB	PNT-1	EXPOSED	-	1	084N

ROOM FINISH SCHEDULE

No.	Name	Floor Finish	Base	North Wall Material	North Wall Finish	East Wall Material	East Wall Finish	South Wall Material	South Wall Finish	West Wall Material	West Wall Finish	Ceiling Material	Ceiling Finish	NOTES	No.
GROUND LEVEL															
100	BOARD ROOM	CPT-1	WWB	-	-	GWB	PNT-1, PNT-5 *(7)	GWB	PNT-1, PNT-5 *(7)	GWB	PNT-1, PNT-5 *(7)	APC-1 / GWB	PNT-2 *(11)	7, 11	100
100A	EXEC. BOARD ROOM	CPT-1	WWB	GWB	PNT-1 / WP-1 *(13)	GWB	PNT-1, PNT-5 *(7, 8)	-	-	GWB	PNT-1, PNT-5 *(7, 8)	GWB / WP-2	PNT-2 / STN *(11)	7, 8, 11, 13	100A
100C	STORAGE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		100C
100D	AV STOR	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		100D
100E	RECEPT.	ET-1	ET-1	GWB	PNT-4	GWB	PNT-1	GWB	PNT-1	GWB	PNT-4	APC-1 / WP-1 *(13)	-	13	100E
101	EXEC. CONF.	CPT-1	VWB, WWB	GWB	PNT-1	GWB	PNT-1, PNT-10 *(10)	GWB	PNT-1,WP-1 *(13)	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-2	10, 13	101
101B	KITCHENETTE	CPT-1	VWB	GWB	PNT-10	GWB	PNT-10	GWB	PNT-10	GWB	PNT-10	APC-1 / GWB	PNT-2 *(11)	11	101B
102	CONTROL	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		102
103	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-6	GWB	PNT-5	GWB	PNT-5	APC-1	-		103
104	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-7	GWB	PNT-5	GWB	PNT-5	APC-1	-		104
105	BREAK ROOM	RUB-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-5	GWB	PNT-1, PNT-13 *(10)	APC-1 / GWB	PNT-2 *(11)	10, 11	105
106	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	106
107	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	107
108	GRAPHICS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	108
109	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-5	GWB	PNT-1	GWB	PNT-1, PNT-12 *(9, 10)	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	109
110	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	110
111	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		111
112	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		112
113	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-8	GWB	PNT-5	GWB	PNT-5	APC-1	-		113
114	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-6	GWB	PNT-5	GWB	PNT-5	APC-1	-		114
115	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-11	GWB	PNT-5	GWB	PNT-5	APC-1	-		115
116	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-10	GWB	PNT-5	GWB	PNT-5	APC-1	-		116
117	RECEIVING	S CONC	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	PCST	PNT-1	EXPOSED	-		117
117A	BREAK ROOM	RUB-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	117A
117B	RR	CT-4	CT-5	GWB	CT-2	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-2		117B
117C	CUST. OFF.	S CONC	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	117C
117D	CLO.	S CONC	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-2		117D
117E	CUST. EQUIP. STORAGE	S CONC	FRP	GWB	FRP *(4)	GWB	FRP *(4)	GWB	FRP *(4)	GWB	FRP *(4)	APC-1	-	4	117E
117F	MAIL	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		117F
118	CONFERENCE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-9	GWB	PNT-5	GWB	PNT-5	APC-1	-		118
119	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-7	GWB	PNT-5	GWB	PNT-5	APC-1	-		119
120	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-8	GWB	PNT-5	GWB	PNT-5	APC-1	-		120
121	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		121
122	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		122
123	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	123
124	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-5 *(10)	GWB	PNT-1, PNT-12 *(9, 10)	GWB	PNT-1, PNT-12 *(9, 10)	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	124
125	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-6	GWB	PNT-5	GWB	PNT-5	APC-1	-		125
126	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	126
127	BREAK	RUB-1	VWB	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1, PNT-12 *(10)	APC-1 / GWB	PNT-2 *(11)	10, 11	127
128	CONF.	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-9	APC-1	-		128
129	CONF.	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-10	APC-1	-		129
130	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-11	APC-1 / GWB	PNT-2 *(11)	11	130
131	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1, PNT-12 *(9, 10)	GWB	PNT-1, PNT-12 *(9, 10)	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	131
132	CONF.	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-7	APC-1	-		132
133	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-8	APC-1	-		133
134	CREDIT UNION	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		134
180A	VESTIBULE	CPT-2	-	STOREFRONT	-	STOREFRONT	-	STOREFRONT	-	GWB, BRK	PNT-1 *(21)	GWB	PNT-2	21	180A
180B	MENS	CT-2, CT-3, CT-4 *(14)	CT-5, CT-6 *(17)	GWB	PNT-5	GWB	CT-2, PNT-5 *(16)	GWB	PNT-5	GWB	CT-2,CT-3, CT-4,PNT-5 *(15)	GWB	PNT-2	14, 15, 16, 17	180B
180C	CUST.	CT-4	CT-5	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-2		180C
180D	SOUTH PUBLIC LOBBY	ET-1	ET-1, CT-1 *(13)	GWB	PNT-1, WP-1 *(13)	GWB	PNT-1	GWB	PNT-1, CT-1 *(12)	GWB	PNT-1, WP-1 *(13)	APC-1, WP-1, GWB	PNT-2 *(11)	11, 12, 13	180D
180E	MEDIA	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		180E
180F	CUST.	CT-4	CT-5	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-2		180F
180G	WOMENS	CT-2, CT-3, CT-4 *(14)	CT-5, CT-6 *(17)	GWB	PNT-5	GWB	CT-2, CT-3, CT-4, PNT-5 *(15)	GWB	PNT-5	GWB	CT-2, PNT-5 *(16)	GWB	PNT-2	14, 15, 16, 17	180G
181	LOBBY	ET-1	ET-1, CT-1 *(12)	GWB	CT-1, PNT-1, WP-1 *(13)	GWB	PNT-1	GWB	PNT-1, PNT-2, WP-1 *(13, 28)	GWB	PNT-1	GWB, APC-1	PNT-2 *(11)	11, 12, 13, 28	181
181A	CUST.	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	EXPOSED	-		181A
181B	CUST.	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	EXPOSED	-		181B
182	CORRIDOR	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		182
182A	VESTIBULE	CPT-2	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	182A
182B	CORR.	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	-	-	APC-1	-		182B
182C	PRODUCTION	CPT-1	VWB	GWB	PNT-5, PNT-9 *(18)	GWB	PNT-5	GWB	PNT-5, PNT-9 *(18)	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	11, 18	182C
182G	WOMEN	CT-2, CT-3, CT-4 *(14)	CT-5, CT-6 *(17)	GWB	CT-2, PNT-5 *(16)	GWB	PNT-5	GWB	CT-2, CT-3, CT-4, PNT-5 *(15)	GWB	PNT-5	GWB	PNT-2	14, 15, 16, 17	182G
182M	MECH / ELEC	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	EXPOSED	-		182M
183	RECEPTION	CPT-1	VWB	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1,PNT-14 *(10)	APC-1 / GWB	PNT-2 *(11)	10, 11	183
183A	CORRIDOR	CPT-1	VWB	-	-	GWB	PNT-5	-	-	GWB	PNT-1	APC-1	-		183A
183B	CORRIDOR	CPT-1	VWB	-	-	GWB	PNT-5	-	-	GWB	PNT-1	APC-1	-		183B
184	CORRIDOR	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		184
184A	VESTIBULE	CPT-2	VWB	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	10, 11	184A
184B	MEN	CT-2, CT-3, CT-4 *(14)	CT-5, CT-6 *(17)	GWB	CT-2, CT-3, CT-4, PNT-5 *(15)	GWB	PNT-5	GWB	CT-2, PNT-5 *(16)	GWB	PNT-5	GWB	PNT-2	14, 15, 16, 17	184B
184C	PRODUCTION	CPT-1	VWB	GWB	PNT-5, PNT-10 *(18)	GWB	PNT-5	GWB	PNT-5, PNT-10 *(18)	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	11, 18	184C
184D	CORRIDOR	CPT-1	VWB	GWB	PNT-5	GWB	PNT-1	GWB	PNT-1	-	-	APC-1	-		184D
184E	FAMILY RM	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		184E
184M	MECH / ELEC	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	EXPOSED	-		184M
184N	CUST.	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5 / FRP *(2)	GWB	PNT-5 / FRP *(2)	EXPOSED	-	2	184N
185	RECEPTION	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	10, 11	185
185A	FILES	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		185A
190	EQUIP	S CONC	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	PCST	PNT-1	EXPOSED	-		190
C1	CHASE	-	-	-	-	-	-	-	-	-	-	-	-	22	C1

ROOM FINISH SCHEDULE

No.	Name	Floor Finish	Base	North Wall Material	North Wall Finish	East Wall Material	East Wall Finish	South Wall Material	South Wall Finish	West Wall Material	West Wall Finish	Ceiling Material	Ceiling Finish	NOTES	No.
C2	CHASE	-	-	-	-	-	-	-	-	-	-	-	-	22	C2
EV1	ELEV	CONC	-	PCST	-	PCST	-	PCST	-	PCST	-	PCST	-		EV1
EV2	ELEV	CONC	-	PCST	-	PCST	-	PCST	-	PCST	-	PCST	-		EV2
ST01	STAIR	RUB-1	VWB	GWB	PNT-1, PNT-5 *(23)	GWB	PNT-1, PNT-5 *(24)	GWB	PNT-1	GWB	PNT-1, PNT-5 *(23)	GWB	PNT-2	23, 24	ST01
ST02	STAIR	PCST	-	PCST	PNT-5	PCST	PNT-5	PCST	PNT-5	PCST	PNT-5	PCST	PNT-2		ST02
ST03	STAIR	PCST	-	PCST	PNT-5	PCST	PNT-5	PCST	PNT-5	PCST	PNT-5	PCST	PNT-2		ST03
ST04	STAIR	S CONC	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-2		ST04
SECOND FLOOR															

ROOM FINISH SCHEDULE

No.	Name	Floor Finish	Base	North Wall Material	North Wall Finish	East Wall Material	East Wall Finish	South Wall Material	South Wall Finish	West Wall Material	West Wall Finish	Ceiling Material	Ceiling Finish	NOTES	No.
200	MEDIA LIBRARY	CPT-1	VWB	GWB	PNT-1, PNT-5, PNT-10 *(10)	GWB	PNT-1, PNT-6, PNT-8, PNT-9, PNT-11, PNT-12 *(10)	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1, PNT-5, PNT-14 *(10)	APC-2	-	10	200
201	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	201
202	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB, BRK	PNT-1 *(11)	GWB	PNT-8	APC-1 / GWB / WP-1	PNT-2 *(11)	11	202
203	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-11	APC-1 / GWB / WP-1	PNT-2 *(11)	11	203
204	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-6	APC-1 / GWB / WP-1	PNT-2 *(11)	11	204
205	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-12	APC-1 / GWB / WP-1	PNT-2 *(11)	11	205
206	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-9	APC-1 / GWB / WP-1	PNT-2 *(11)	11	206
207	CAFE	RUB-1 / CPT-1	VWB, WWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1, PNT-5, PNT-14, WP-1	GWB	PNT-1, PNT-5 *(10)	APC-1 / GWB	PNT-2 *(11)	10, 11	207
208	PROCESSING	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-2	-		208
209	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-7	APC-1	-		209
210	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-8	APC-1	-		210
211	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-6	APC-1	-		211
212	STORAGE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	EXPOSED	-		212
213	BREAK	RUB-1 / CPT-1	VWB	GWB	PNT-1, PNT-12 *(10)	GWB	PNT-1,PNT-12 *(10)	GWB	PNT-1, PNT-5, PNT-12 *(10)	GWB	PNT-1, PNT-12 *(10)	APC-1 / GWB	PNT-2, PNT-12 *(11, 27)	10, 11, 27	213
214	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	214
215	CONFERENCE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-11	GWB	PNT-5	GWB	PNT-5	APC-1	-		215
216	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-10	GWB	PNT-5	GWB	PNT-5	APC-1	-		216
217	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-9	GWB	PNT-5	GWB	PNT-5	APC-1	-		217
218	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-7	GWB	PNT-5	GWB	PNT-5	APC-1	-		218
219	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-8	GWB	PNT-5	GWB	PNT-5	APC-1	-		219
220	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1, PNT-13 *(9, 10)	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1	GWB	PNT-1, PNT-13 *(9, 10)	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	220
221	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	221
222	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		222
223	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-12	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	223
224	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		224
225	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	225
226	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1, PNT-13 *(9, 10)	GWB	PNT-1, PNT-13 *(9, 10)	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	226
227	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-6	GWB	PNT-5	GWB	PNT-5	APC-1	-		227
228	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-11	GWB	PNT-5	GWB	PNT-5	APC-1	-		228
229	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-10	GWB	PNT-5	GWB	PNT-5	APC-1	-		229
230	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-9	GWB	PNT-5	GWB	PNT-5	APC-1	-		230
231	CONFERENCE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-7	GWB	PNT-5	GWB	PNT-5	APC-1	-		231
232	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	232
233	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	233
234	BREAK	RUB-1 / CPT-1	VWB	GWB	PNT-1, PNT-5, PNT-13 *(10)	GWB	PNT-1, PNT-13 *(10)	GWB	PNT-1, PNT-13 *(10)	GWB	PNT-1, PNT-13 *(10)	APC-1 / GWB	PNT-2, PNT-13 *(11, 27)	11, 27	234
235	STORAGE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		235
236	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	236
237	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	237
238	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-8	APC-1	-		238
239	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1, PNT-13 *(9, 10)	GWB	PNT-1, PNT-13 *(9, 10)	GWB	PNT-1, PNT-5 *(9, 10)	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	239
240	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-6	APC-1	-		240
241	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-11	APC-1	-		241
242	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-10	APC-1	-		242
243	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-9	APC-1	-		243
280	RECEPTION	CPT-1	VWB, WWB *(19)	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1, PNT-14 *(10)	GWB	PNT-1, PNT-5	GWB	PNT-5	APC-1	-	9, 10, 19	280
281	LOBBY	ET-1, CPT-1	ET-1, CT-1 *(12)	GWB	PNT-5, WP-1, CT-1 *(13)	GWB	PNT-5	GWB	PNT-2, PNT-5, WP-1 *(13, 28)	GWB	PNT-5	APC-1, GWB, WP-1	PNT-2 *(11)	11, 12, 13, 28	281
281B	MEN	CT-2, CT-3, CT-4 *(14)	CT-5, CT-6 *(17)	GWB	CT-2, CT-3, CT-4, PNT-5 *(15)	GWB	PNT-5	GWB	CT-2, PNT-5 *(16)	GWB	PNT-5	GWB	PNT-2	14, 15, 16, 17	281B
281C	EQUIP.	CT-4	CT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-2		281C
281D	EQUIP.	CT-4	CT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-2		281D
281G	WOMEN	CT-2, CT-3, CT-4 *(14)	CT-5, CT-6 *(17)	GWB	CT-2, PNT-5 *(16)	GWB	PNT-5	GWB	CT-2, CT-3, CT-4, PNT-5 *(15)	GWB	PNT-5	GWB	PNT-2	14, 15, 16, 17	281G
282	PRODUCTION	CPT-1	VWB	GWB	PNT-5, PNT-7 *(18)	GWB	PNT-5	GWB	PNT-5, PNT-7 *(18)	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	11, 18	282
282M	MECH / ELEC.	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		282M
283	RECEPTION	CPT-1	VWB, WWB *(19)	GWB	PNT-5	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-12	APC-1	-	10, 19	283
284	PRODUCTION	CPT-1	VWB	GWB	PNT-5, PNT-6 *(18)	GWB	PNT-5	GWB	PNT-5, PNT-6 *(18)	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	11, 18	284
284C	CUST.	S CONC	VWB	GWB	PNT-5 / FRP *(2)	GWB	PNT-5 / FRP *(2)	GWB	PNT-5	GWB	PNT-5	EXPOSED	-	2	284C
284M	MECH / ELEC.	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	EXPOSED	-		284M
THIRD FLOOR															

ROOM FINISH SCHEDULE

No.	Name	Floor Finish	Base	North Wall Material	North Wall Finish	East Wall Material	East Wall Finish	South Wall Material	South Wall Finish	West Wall Material	West Wall Finish	Ceiling Material	Ceiling Finish	NOTES	No.
300	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1, PTN-5 *(10)	APC-1	-	10	300
301	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	301
302	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-12	APC-1 / GWB	PNT-2 *(11)	11	302
303	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	303
304	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	304
305	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	305
306	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	306
307	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	307
308	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	308
309	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	309
310	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	310
311	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-11	APC-1	-		311
312	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-6	APC-1	-		312
313	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-8	APC-1	-		313
314	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-7	APC-1	-		314
315	BREAK ROOM	RUB-1	VWB	GWB	PNT-1, PNT-13 *(10)	GWB	PNT-1, PNT-13 *(10)	GWB	PNT-1,PNT-5, PNT-13 *(10)	GWB	PNT-1, PNT-5, PNT-13 *(10)	APC-1 / GWB	PNT-2, PNT-13 *(11, 27)	10, 11, 27	315
316	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	316
317	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	317
318	CONFERENCE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-10	GWB	PNT-5	GWB	PNT-5	APC-1	-		318
319	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-9	GWB	PNT-5	GWB	PNT-5	APC-1	-		319
320	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-7	GWB	PNT-5	GWB	PNT-5	APC-1	-		320
321	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-8	GWB	PNT-5	GWB	PNT-5	APC-1	-		321
322	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-6	GWB	PNT-5	GWB	PNT-5	APC-1	-		322
323	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1, PNT-14 *(9, 10)	GWB	PNT-5	GWB	PNT-1	GWB	PNT-1, PNT-14 *(9, 10)	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	323
324	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	324
325	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		325
326	CONFERENCE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-13	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	326
327	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-11	GWB	PNT-5	GWB	PNT-5	APC-1	-		327
328	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-10	GWB	PNT-5	GWB	PNT-5	APC-1	-		328
329	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-9	GWB	PNT-5	GWB	PNT-5	APC-1	-		329
330	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-7	GWB	PNT-5	GWB	PNT-5	APC-1	-		330
331	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1	-		331
332	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	332
333	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1, PNT-5 *(10)	GWB	PNT-1, PNT-14 *(9, 10)	GWB	PNT 1, PNT-14 *(9, 10)	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	333
334	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	334
335	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	335
336	CONFERENCE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-8	GWB	PNT-5	GWB	PNT-5	APC-1	-		336
337	BREAK ROOM	RUB-1	VWB	GWB	PNT-1, PNT-5, PNT-14 *(10)	GWB	PNT-1, PNT-14 *(10)	GWB	PNT-1, PNT-14 *(10)	GWB	PNT-1, PNT-14 *(10)	APC-1 / GWB	PNT-2, PNT-14 *(11, 27)	10, 11, 27	337
338	STORAGE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1	-		338
339	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	339
340	CONFERENCE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-6	APC-1	-		340
341	OFFICE	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	GWB	PNT-1	APC-1 / GWB	PNT-2 *(11)	11	341
342	WORKSTATIONS	CPT-1	VWB	GWB	PNT-1	GWB	PNT-1, PNT-14 *(9, 10)	GWB	PNT-1	GWB	PNT-1, PNT-5 *(10)	APC-1 / GWB	PNT-2 *(11)	9, 10, 11	342
343	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-11	APC-1	-		343
344	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-10	APC-1	-		344
345	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-9	APC-1	-		345
346	OFFICE	CPT-1	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-6	APC-1	-		346
380	RECEPTION	CPT-1	VWB, WWB *(19)	GWB	PNT-5	GWB	PNT-12	GWB	PNT-5	GWB	PNT-5	APC-1	-	19	380
380A	FILES	CPT-1	VWB	GWB	PNT-1	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	11	380A
381	LOBBY	ET-1, CPT-1	ET-1, CT-1 *(12)	GWB	CT-1, PNT-5, WP-1 *(13)	GWB	PNT-5	GWB	PNT-2, PNT-5, WP-1 *(13, 28)	GWB	PNT-5	GWB / WP-1	PNT-2 *(11)	11, 12, 13, 28	381
381A	EQUIP.	CT-4	CT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-2		381A
381B	MEN	CT-2, CT-3, CT-4 *(14)	CT-5, CT-6 *(17)	GWB	CT-2, CT-3, CT-4, PNT-5 *(15)	GWB	PNT-5	GWB	CT-2, PNT-5 *(16)	GWB	PNT-5	GWB	PNT-2	14, 15, 16, 17	381B
381C	EQUIP.	CT-4	CT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5, CT-4	GWB	PNT-5	GWB	PNT-2		381C
381G	WOMEN	CT-2, CT-3, CT-4 *(14)	CT-5, CT-6 *(17)	GWB	CT-2, PNT-5 *(16)	GWB	PNT-5	GWB	CT-2, CT-3, PNT-5 *(15)	GWB	PNT-5	GWB	PNT-2	14, 15, 16, 17	381G
382	PRODUCTION	CPT-1	VWB	GWB	PNT-5, PNT-6 *(18)	GWB	PNT-5	GWB	PNT-5, PNT-6 *(18)	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	11, 18	382
382M	MECH / ELEC	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	EXPOSED	-		382M
383	RECEPTION	CPT-1	VWB, WWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-13	APC-1	-	19	383
384	PRODUCTION	CPT-1	VWB	GWB	PNT-5, PNT-10 *(18)	GWB	PNT-5	GWB	PNT-5, PNT-10 *(18)	GWB	PNT-5	APC-1 / GWB	PNT-2 *(11)	11, 18	384
384C	CUST.	S CONC	VWB	GWB	PNT-5 / FRP *(2)	GWB	PNT-5 / FRP *(2)	GWB	PNT-5	GWB	PNT-5	EXPOSED	-	2	384C
384M	MECH / ELEC	S CONC	VWB	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	GWB	PNT-5	EXPOSED	-		384M
ROOF															

ROOM FINISH SCHEDULE

No.	Name	Floor Finish	Base	North Wall Material	North Wall Finish	East Wall Material	East Wall Finish	South Wall Material	South Wall Finish	West Wall Material	West Wall Finish	Ceiling Material	Ceiling Finish	NOTES	No.
482	VESTIBULE	S CONC	-	PCST	-	PCST	-	PCST	-	PCST	-	EXPOSED	-		482
482M	MECHANICAL	S CONC	VWB *(20)	PCST, CMU, GWB	PNT-5	PCST, CMU, GWB	PNT-5	PCST, CMU, GWB	PNT-5	PCST, CMU, GWB	PNT-5	EXPOSED	-	20	482M
484	VESTIBULE	S CONC	-	PCST	-	PCST	-	PCST	-	PCST	-	EXPOSED	-		484
484M	MECHANICAL	S CONC	VWB *(20)	PCST, CMU, GWB	PNT-5	PCST, CMU, GWB	PNT-5	PCST, CMU, GWB	PNT-5	PCST, CMU, GWB	PNT-5	EXPOSED	-	20	484M

ROOM FINISH GENERAL NOTES

1. ALL EXPOSED GWB SURFACES ARE INTENDED TO BE PAINTED.
2. ALL HM FRAMES ARE TO BE PAINTED PNT-3. REFER TO SPECIFICATIONS 099123 FOR COLOR SCHEDULE.
3. ALL INTERIOR RAILINGS, STRINGERS, GUARDRAILS AND MISCELLANEOUS STEEL SHALL BE PAINTED.
4. AT LOCATIONS SCHEDULED TO RECEIVE A WOOD WALL BASE (WWB), BASE IS TO BE 1/2" THICK X 4" TALL, RIFT CUT SOLID OAK STAINED TO MATCH THE PRE-FINISHED DOORS.

ROOM FINISH SCHEDULE NOTES

1. NOT ALL WALLS IN THIS ROOM WILL BE INSTALLED. DASHED LINES INDICATE FUTURE WALLS AND ARE SHOWN FOR INFORMATIONAL PURPOSES ONLY.
2. FRP WALL PANELS TO STOP AT 4'-0" +/- AFF. PROVIDE CAP TRIM AT TOP OF FRP PANEL. PANELS TO BE APPLIED TO LENGTH OF ENTIRE WALL THAT ADJOINS WALL OF MOP SINK.
3. VWB ONLY INSTALLED ON GWB WALLS. CONCRETE WALLS WILL NOT HAVE ANY WALL BASE.
4. FRP PANELS TO INSTALL FULL HEIGHT OF WALL.
5. EXPOSED GWB HEADERS AND SOFFIT SURFACES TO BE PAINTED
6. WALL TILE TO GO FULL HEIGHT OF WALL.
7. PNT-1 TO 8'-2" AFF, THEN PNT-5 TO THE CEILING. PROVIDE A CONTROL JOINT AT 8'-2" TO SEPARATE FINISHES
8. HORIZONTAL CONTROL JOINT AND 2-COLOR PAINT SCHEME TERMINATES AT INSIDE CORNER WHERE 119 DEGREE WALL INTERSECTS NORTH/SOUTH WALL.
9. ACCENT PAINT ON BOTH SIDES PARTIAL HEIGHT WALL
10. REFER TO A800 SERIES FOR LOCATION OF PAINT COLOR TRANSITIONS.
11. ONLY GWB SURFACES TO RECEIVE PNT FINISH.
12. CT-1 ONLY AT DRINKING FOUNTAIN NICHE.
13. WP-1 APPLIED OVER GWB TO ELEVATION INDICATED ON SHEET A505. PANELING TO TERMINATE AT INSIDE CORNERS AS INDICATED IN DETAILS.
14. REFER TO ENLARGED FLOOR PLANS FOR PATTERN OF TILE AND TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.
15. REFER TO LAVATORY ELEVATIONS FOR PATTERN OF TILE. TILE IS ONLY LOCATED AT LAVATORY WALL FROM INSIDE CORNER TO INSIDE CORNER.
16. TILE IS ONLY LOCATED ON TOILET WALL FROM INSIDE CORNER TO INSIDE CORNER.
17. TILE BASE AT ALL WALLS.
18. REFER TO A800 SERIES FOR LOCATION OF PAINT TRANSITIONS. ACCENT COLOR TO TYPICALLY OCCUR BETWEEN GRIDS B & C, INSIDE CORNER TO INSIDE CORNER.
19. WOOD WALL BASE AT ALL SIDES OF BUILT-IN RECEPTION DESK.
20. PROVIDE VWB AT WALLS OF MECHANICAL CHASE.
21. ONLY PAINT GWB SURFACE.
22. 2-HOUR MECHANICAL SHAFT. SHAFT LINER
23. PNT-5 ONLY FROM LANDING ELEVATION 107'-5 1/2" AND UP.
24. PNT-5 ONLY FROM LANDING ELEVATION 100'-0" AND UP.
25. CT-2 AT ACTUAL SHOWER AND DRESSING AREA OUTSIDE OF SHOWER.
26. CT-1 AT ACTUAL SHOWER WALLS AND DRESSING AREA OUTSIDE OF SHOWER.
27. PNT-2 OCCURS AT ALL GWB SURFACES OTHER THAN THE GWB SOFFIT AT THE ISLAND. SOFFIT AT ISLAND TO BE PAINTED THE SAME COLOR AS THE WALLS OF THE ISLAND.
28. PNT-2 TO OCCUR FROM INSIDE CORNER TO INSIDE CORNER AT GWB SURFACE BEHIND ART GLASS PANELS.

C:\REVIT LOCAL PROJECTS\11065-04_QUADE WORKING_9-14-12_2012.rvt

REVISIONS:
Addendum 01: 9.18.2012

DESIGN ARCHITECT: Michael Penn
PROJECT ARCHITECT: David Quade
DRAWN BY: Author
ISSUED: September 7, 2012

ARCHITECT DAVID E. QUADE A-3466 9.7.12 STATE OF NEBRASKA

PROJECT CONSULTANTS

MECHANICAL ENGINEER
ELECTRICAL ENGINEER
Engineering Technologies Inc.
825 M Street, Suite 200
Lincoln, NE 68508
T: 402.476.1273

CIVIL ENGINEER
Olsson Associates
1111 Lincoln Mall
Lincoln, NE 68508
T: 402.474.6311

STRUCTURAL ENGINEER
R.O Youker Inc.
1201 'O' Street, Suite 310
Lincoln, NE 68508
T: 402.477.7640

LPS District Office

SINCLAIR hille architects
700 Q St. Lincoln, NE 68508 T: 402 476 7331 F: 402 476 8341

Room Finish Schedules

SHA PROJECT NO. 11065

A107

© Copyright SINCLAIR HILLE ARCHITECTS