

AD1.7. Pre-Bid Meeting Question: Corridor 182K: please clarify key note 1 on the west wall.
Disregard this key note, as well as the key note 1 pointing at the east wall of Receptionists 183.

AD1.8. Pre-Bid Meeting Question: Room 149C: please clarify key note 6 on the west wall.
Disregard this key note.

AD1.9. Pre-Bid Meeting Question: What finish material (paint, base, etc) is required for the exterior portion of door infill in the existing room 182F? The finish of the exterior portion of door infill in existing Room 182F is GWB, Pntd, with vinyl wall base to match existing.

MECHANICAL / ELECTRICAL ADDENDA ITEMS:

AD1.10. Sheet E200, Power Plans: Provide 40' each of 2 – 4" conduits in the tunnel/crawl space to the main data closet. Provide 40' each of 2 – 4" conduits vertically from the tunnel/crawl space within the main data closet. Provide pull strings throughout the length of the conduit with 12" additional length at each end. This work will require core drilling through 2 concrete walls, 1 drywall wall and a concrete floor. Coordinate exact location of core drills and the main data closet with UNK Information Technology Services.

AD1.11. Pre-Bid Meeting Question: Are flexible conduit whips able to be used for the light fixtures? Each fixture must be connected by a 6' whip to a junction box to allow the light fixtures to be relocated.

AD1.12. Pre-Bid Meeting Question: Does an accessible tunnel or crawlspace exist underneath room 182A and 182B where new plumbing is to be located? - No, the existing plumbing tunnel is 4'-0" wide and is at the building perimeter.

AD1.13. Pre-Bid Meeting Question: Is anything to be done with the existing ceiling fans throughout the space? The existing ceiling fans are to be removed and turned over to the owner.

END OF ADDENDUM NO. 1



Pre-Bid Meeting
UNK Healthcare/Counseling Remodel
Project No. K008P006
February 14, 2013, 3:00 p.m.
Attendees List

Name	Organization	Phone	E-Mail
Steve Lentell	Central Contracting	308-234-2421	slentell@centralcontracting.net
Ron Hansen	Winn Construction	402-932-5298	ronewinnvet.com
Mike Fields	Middleton Electric	308-382-2550	
Tim Hewitt	Bamford	308-237-2157	Hewitttim2@hmail.com
Ray Rice	Bamford	308-237-2157	bamford@citlink.net
Mark Means	Essink Bros.	308-383-9923	mark@essink.biz
Dennis McLaughlin	Kelly Electric	308-234-2822	mmclaughlin@kellyelec.com
Jeremy Sklenar	Kelly Electric	308-234-2822	jsklen@kellyelec.com
Curtis Baetz	RMV Construction	308-233-7576	Curtis-baetz@yahoo.com
Bob Rasmussen	Lacy	308-380-5904	bob.rasmussen.lacy.gc.com
Brad Myers	Sampson	308-865-1375	bradmyers@sampson-construction.com
Brian Cox	UNK-ITS	308-865-8176	Coxb12@unk.edu
John Langrehr	NE Fire Sprinkler	308-381-2033	
Ryan Dexter	NE Fire Sprinkler	308-381-2033	ryan@nebraskafire.com