



ADDENDUM NO. 2

**TITLE: BOONE CENTRAL POST TENSION TRACK AND FOOTBALL FIELD PROJECT
BOONE CENTRAL PUBLIC SCHOOLS**

PROJECT: REGA NO. 121271

LOCATION: Albion, Nebraska

ADDRESS: S. 1st and Park Street

DATE OF ADVERTISEMENT: March 3, 2013

DATE OF ISSUE: March 26, 2013

DATE OF BID OPENING: March 29, 2013

NOTE TO ALL PLAN HOLDERS: Please insert this Addendum into your copy of the contract documents for the above named project.

The following changes to the contract documents are issued by the Architect/Engineer, shall be attached and made a part of the plans and specifications and shall have the same force and effect as though a part of the original issue. All other stipulations and requirements of the plans and specifications remain in effect.

CHANGES TO THE SPECIFICATIONS:

Delete: Section 32-18-23.33, Running Track Surfacing, Summary, Subsection A, Second Paragraph in its entirety; Provide 8-Lane Track with black colored structural spray.

Add: Section 32-18-23.33, Running Track Surfacing, Summary, Subsection A, Second Paragraph in its entirety; Provide 8-Lane Track with black colored base mat as base bid.

Add: Section 32-84-00, Field Irrigation, 1.02 Description, Paragraph K in its entirety; K. The current water service for the field irrigation is a 2” service at 60 psi.

CHANGES TO THE PLAN SHEETS:

SHEET C1.4AR

Delete: Dimension 133’-2”± from north edge of rock base to north edge of 6’ wide sidewalk on Detail 2 for rock base under I-beam bleachers.

Add: Dimension 131’-2”± for Detail 2 from north edge of 6’ wide sidewalk to new north edge of rock base under I-beam bleachers.

Delete: Dimension 49’-2”± from south edge of rock base to south edge of 6’ wide sidewalk on Detail 2 for rock base under I-beam bleachers.

Add: Dimension 47'-2"± for Detail 2 from south edge of 6' wide sidewalk to new south edge of rock base under I-beam bleachers.

Delete: Dimension 40'-2"± from east edge of rock base to west edge of rock base on Detail 2 for rock base under I-beam bleachers.

Add: Dimension 38'-2"± for Detail 2 from east edge of rock base to new west edge of rock base under I-beam bleachers. Start east edge of rock base 12' from outside edge of track.

Delete: Dimension 188'-3 1/4"± from north edge of rock base to south edge of rock base on Detail 3 for rock base under Angle Frame bleachers.

Add: Dimension 184'-3 1/4"± for Detail 3 from new north edge of rock base to new south edge of rock base under Angle Frame bleachers. Center dimension on 50 yard line.

Delete: Dimension 40'-2"± from east edge of rock base to west edge of rock base on Detail 3 for rock base under Angle Frame bleachers.

Add: Dimension 38'-2"± for Detail 3 from east edge of rock base to new west edge of rock base under Angle bleachers. Start east edge of rock base 12' from outside edge of track.

Add: Dimensions for rock base Alternate Bid Item Number 10. Rock base under I-Beam bleachers (Alternate Bid Item Number 10) shall be 160'-0"± (long) by 38'-2"± (wide). Dimension from north edge of rock base to north edge of 6' sidewalk shall 118'-10"±. Dimensions from south edge of rock base to south edge of 6' sidewalk shall be 35'-2"±. Center bleacher dimensions on 50 yard line, 12 feet from outside edge of track.

Add: Dimensions for rock base Alternate Bid Item Number 11. Rock base under Angle Frame bleachers (Alternate Bid Item Number 10) shall be 160'-0"± (long) by 38'-2"± (wide). Center bleacher dimensions on 50 yard line, 12 feet from outside edge of track.

Respectfully Submitted,
REGA ENGINEERING GROUP, INC



Nathaniel Burnett, EIT