

addendum

addendum no. 1

date: March 27, 2013

bid date: April 2, 2013

project name: UNL Nebraska Hall Room 230 Electrical Remodel

project no: UNL Project No C024P516
MEI Project No 11136

This addendum is hereby made a part of the contract documents to the same extent as if it were originally included therein. Contract documents shall be considered modified or revised as hereinafter described.

Drawings

1. Sheet a1, Enlarged Partial 2nd Floor Plan - Architectural Demolition. Flag note #3, revise to read: "Abatement contractor shall remove existing ceiling, including black iron grid support, metal lath and plaster. Remove existing surface mounted electrical equipment..."
2. Sheet e2, Partial 2nd Floor Plan - Electrical. Relocate 'RDC3' from location indicated one floor tile west such that there is 6' clear distance between 'RDC3' and cabinet 'B32'.