

645-020-13

### ADDENDUM NO. 3

The Architect/ Engineer issues this addendum, applicable to the above named project, to all known Contractors before receipt of proposal.

This addendum includes Item Number 3-1 thru 3-4. This addendum item shall be fully incorporated into the Bidding/Contract Documents and have the same force and effect as though originally included.

The Bidder shall acknowledge receipt of this Addendum No. 3 on the Bid Proposal Form in the place provided.

#### Specifications

**Item 3-1: Section 01 23 00 Alternates**

Refer to 3.1 Schedule of Alternates;  
Bid Alternate L-1 Clarification: This bid alternate shall include the removal of the existing 6' high chain link and installation on a new 7' high chain link fence as indicated on the drawings.

#### Drawings

**Item 3-2: L2.03 Site Fencing Plan**

Refer to note on drawing referencing bid alternate L-2 to install a 7' tall chain link fence. This note should be changed to bid alternate L-1.

**Item 3-3: L6.01 Site Details**

Refer to Detail 7.  
Question: Can we use a 2x4 in lieu of the 2x8 called out in the plans?  
Answer: A 2x4 will be acceptable as long as you do not damage the track drain.

**Item 3-4: L6.02 Site Fencing Details**

Refer to Detail 7. Make the following changes;

1. Replace bottom rail with galvanized tension wire and 6 gauge galvanize hog rings at 18" O.C.
2. Change 6 gauge mesh to 9 gauge finish.

Refer to Detail 8. Make the following changes;

1. Replace bottom rail with galvanized tension wire and 6 gauge galvanize hog rings at 18" O.C
2. Change 6 gauge mesh to 9 gauge core, 8 gauge finish
3. Change Terminal posts to 2-1/2" O.D
4. Change Line posts to 2" O.D.

END OF ADDENDUM NO. 3