

**ADDENDUM #001**  
**Date: 4/5/13**

**JACKSON-JACKSON & ASSOCIATES, INC.**  
**1905 N. 81<sup>ST</sup> Street**  
**Omaha, NE 68114**

**PROJECT:**  
**Omaha Public Schools**  
**Door and Hardware Replacement Projects Pkg. 2**  
**Masters Elementary and Florence Elementary**  
**Omaha, Nebraska**

**JJA Project: 3431CD**  
**DRAWINGS & SPECIFICATIONS**  
**Dated 3/26/13**

**The Drawings and Specifications for the above referenced project are hereby amended and the following changes shall be made part of the Contract Documents.**

**ARCHITECTURAL**

**ITEM #1**      **Refer to the Project Manual, Section 08 71 00, Door Hardware**

- A. Refer to Paragraph 3.6B, Hardware Set No. 2. Delete the smoke seal at all doors scheduled as door type B on sheet A2.1.
- B. Delete the installation of new door silencers at the hollow metal door frames where smoke seals are to be installed.

**ITEM #2**      **Refer to the Project Manual, Appendix "B", Sheet A2.1, Floor Plan.**

- A. As a matter of clarification, OPS will deactivate and remove the alarm security contacts from doors #6A and #165B prior to the contractor removing the doors. OPS will reinstall the alarm contacts and reactivate after the doors have been installed by the contractor.