

OWNER

St Francis Borgia Catholic Church

Beautification and Capital Improvements Project

2005 Davis Drive, Blair, Nebraska

DRAWINGS & SPECIFICATIONS

Dated 5/1/13

The Drawings and Specifications for the above referenced project are hereby amended and the following changes shall be made part of the Contract Documents.

ARCHITECTURAL

ITEM #1 Refer to the Project Manual, Division 09 - Finishes, Section 09 68 16, Sheet Carpeting.

- A. As a matter of clarification: the Sheet Carpeting shall be used on Stairs #107 and Stairs #108 including the landing.

ITEM #2 Refer to the Project Manual, Division 06 – Wood, Plastics and Composites, Section 06 22 00, Finish Carpentry and Millwork.

- A. Refer to Paragraph 2.4.A. Metal Laminate Trim. Trim shall be installed over 1 inch by 1 inch wood that frames the crucifix. There is 9 inches clear space between 1 inch metal trim. The metal trim separates the painted field that the crucifix is mounted on and the painted wall that is stenciled. No exposed anchors shall be mounted by through the metal trim.
- B. Refer to Paragraph 2.4.B. Change Midwest Tile Marble and Granite's phone number from 402/331-3900 to **402/331-3800**.

ITEM #3 Refer to the Project Manual, Division 09 - Finishes, Section 09 30 00, Tiling.

- B. Refer to paragraph 2.1.A.1. Change tile size from 12" by 12" to **12" by 18"**.

ITEM #4 Refer to the Project Manual, Appendix "A", Drawing Sheets D1.1.

- A. Refer to Altar #119, North wall. Remove marble column and cap on the north wall that remains from the former communion rail. Patch plaster wall to match existing.

ITEM #5 Refer to the Project Manual, Appendix "A", Drawing Sheets A1.1.

- B. Refer to Keynote #8. At statue alcove install tile apron on front edge. A tile base is not required.
- C. Refer to Corridor #117. Change the floor from CPT-1 to **CPT-2**.

OWNER

St Francis Borgia Catholic Church

Beautification and Capital Improvements Project

2005 Davis Drive, Blair, Nebraska

DRAWINGS & SPECIFICATIONS

Dated 5/1/13

ITEM #6 Refer to the Project Manual, Appendix "A", Drawing Sheets A1.3.

- A. Refer to Choir Loft Floor Plan 1/A1.3. Refer to acoustical wall panels. Fabric on wall panels shall be **“Gilford of Maine FR701, Style 2100.”**

ITEM #7 Refer to the Project Manual, Appendix "A", Drawing Sheets A2.1, Room finish Schedule.

- A. Refer to Commons Area #102 and Drawing Sheet A1.2. Inside door #102 at the bottom of stairs #107 install Carpet CPT-2 to the edge of the stair wall.
- B. Refer to Corridor #117. Change the floor from CPT-1 to **CPT-2**.
- C. Refer to Altar #119, East Wall. Change wall finish “B” to **“A.”** The back of the archway opening can be painted.
- D. Refer to Altar #119 and Photo Sheets P1.2 through P1.7. Install new porcelain tile floor over the existing mosaic tile shown to remain. Prep floor as required. At contractor’s option the existing mosaic tile can be removed down to concrete floor prior to performing floor prep for new tile.
- E. Refer to Choir Loft #202. Install carpet tiles at risers. Install Johnsonite vinyl stair nosing VCD-XX at all risers nosing’s as required to accommodate carpet tiles.

ITEM #8 Refer to the Project Manual, Appendix "A", Drawing Sheets A2.1, Door Schedule, Section 08 71 00, Door Hardware, and Alternate #4.

- A. Refer to pair of doors #E114 and Hardware Set #5. Delete all work at Pair of doors #E114.
- B. Door Security Contractor shall be responsible for coordinating and providing any **electrical power** needs for a complete system.

ELECTRICAL

ITEM #9 Refer to the Project Manual, Appendix "A", Drawing Sheets A1.3 and E1.1.

- A. Refer to Choir Loft Floor Plan 1/A1.3. Note the relocation of the two existing electrical floor boxes to be extended to the elevation of the new platform height.
- B. Provide and install a 1inch conduit sleeve in the new platform extension with 90 degree extensions to the new platform height on both ends to accommodate existing speaker wiring. Terminate the conduits at the new floor elevation with grommet hole covers.

OWNER

**St Francis Borgia Catholic Church
Beautification and Capital Improvements Project
2005 Davis Drive, Blair, Nebraska**

**DRAWINGS & SPECIFICATIONS
Dated 5/1/13**

ITEM #10 Refer to the Project Manual, Appendix "A", Drawing Sheets E1.1.

- A. Refer to the 12 light fixtures in Nave #113. Change the note to read as follows:
“12 existing pendant fixtures in Nave: at each fixture clean, replace existing down flood light sockets typical. Replace all lamps with Owner provided 18watt and 20watt LED light bulbs.”
- B. Refer to the two light fixtures in the Choir loft. As a matter of clarification, there are three light bulbs in each fixture. Light bulbs for these fixtures are not provided by the Owner.
- C. Refer to the two existing flood lights on the west end of the Nave that are schedule to be changed to track lights. As a matter of clarification, these fixtures will not be dimmable. They are currently controlled from the panel breakers that will be moved to wall switches as part of this project.

ITEM #11 Refer to the Project Manual, Appendix "A", Drawing Sheets E2.1.

- A. Refer to the Symbol Legend:
 - a. At the data/telecommunication symbol – add the following note **“provide 2 CAT 6 cables to each location, typical”**
 - b. At the data/telecommunication symbol – change the location of the cable run from Sacristy #118 to **Sound Equip. Closet #135.**
 - c. At the data/telecommunication symbol – Add: HDMI to CAT 6 converter at each location shall be provided by owner. Terminate CAT 6 cables in wall jack, typical.
 - d. At the wireless hub symbol – note: **At hub provide 1-CAT 6 cable with RJ45 termination. Wireless hub device provided by owner and installed by contractor.**
 - e. At the Video symbol – change the location of the cable run from Sacristy #118 to **Sound Equip. Closet #135.**
- B. Refer to the relocated microphone wall jack on the back of the south arch of Altar #119. Provide a 1” raceway from the relocated microphone wall jack to the lectern through the accessible ceiling space below the altar area.

ITEM #12 Refer to the Project Manual, Appendix "A", Drawing Sheets E2.2.

- A. Refer to Sound Equip. Closet #135. Contractor to supply wall mounted data rack and patch panel. Terminate CAT 6 cable in 24 port patch panel.
- B. Refer to the power and video cables at the north soffit of Parish Center #125. Verify location of devices with Owner to accommodate Owner provided equipment.

ADDENDUM #001

Date: May 17, 2013

JACKSON-JACKSON & ASSOCIATES

1905 N. 81ST Street

Omaha, NE 68114

OWNER

St Francis Borgia Catholic Church

Beautification and Capital Improvements Project

2005 Davis Drive, Blair, Nebraska

DRAWINGS & SPECIFICATIONS

Dated 5/1/13

ITEM #13 Refer to the Project Manual, Appendix "A", Drawing Sheets E2.3.

- A. Refer to the Symbol Legend on sheet E2.1 and Item #11 of this addendum for full device requirements. Termination point of cabling in education building shall remain at the new wall mounted data rack in Mechanical #102 as indicated.
- B. In order to accommodate the Owner use of the Educational Building. The scope of work shown on Sheet E2.3 shall be completed by September 1, 2013.

End of Addendum #001