

ADDENDUM NO. 1

**NORFOLK REGIONAL CENTER
IP CAMERA UPGRADE PROJECT**

**1700 North Victory Road
Norfolk, Nebraska 68701**

DATE OF ADDENDUM ISSUE: May 29, 2013
DATE OF BID OPENING: June 4, 2013
PA PROJECT NO. : 131903

NOTE TO ALL PLAN HOLDERS: Please insert this Addendum into your copy of the contract documents for the above named project.

The following changes to the contract documents are issued by the Architect/Engineer, shall be attached and made a part of the plans and specifications, shall be acknowledged with the bidder's proposal and shall have the same force and effect as though a part of the original issue. All other stipulations and requirements of the plans and specifications remain in effect.

CHANGES TO THE SPECIFICATIONS

SECTION 13760, DIGITAL VIDEO SURVEILLANCE SYSTEM:

- a. Page 13760-1, paragraph 2.1(T), Change to
 - a. Milestone Expert
 - b. Avigilon Enterprise
- b. Page 13760-1, Delete paragraph 2.1(E)

CHANGES TO THE DRAWINGS

SHEET E1.1, GROUND & FIRST FLOOR ELECTRICAL PLAN:

- a. Refer to keynote #2, the chases indicated by this keynote are not true shaft chases and do not have a 2 hour rating. The chases have floors and the 2 hour separation is at the floor. Any penetrations to the floor will need to be sealed to maintain the 2 hour rating.
- b. In the following rooms an exception to the use of surface metal raceway will be allowed such that exposed cables may be run horizontally tight against the structural ceiling but raceway would be required whenever cables drop vertically from the ceiling. The rooms include BW-N5, BW-N6, BW-N7, BW-S3, BW-S4, BW-S5, BW-6, BE-N3, BE-N4, BE-N5, BE-E1, BE-S2, BE-S4, & BE-S9.
- c. For wireless cameras in the elevators, that work will need to be coordinated with the elevator contractor. Contact Josh at Kone' elevator at 402-592-7381 ext 203 to schedule a meeting well in advance so that it can be coordinated with a regular maintenance trip.

Please acknowledge receipt of this Addendum No.1 on your bid form.

Respectfully Submitted,

PROCHASKA & ASSOCIATES

BY: 

Brian Kerl, LEED AP BD+C

Attachments:
None