

ADDENDUM



Date: September 5, 2013

Project: LPS Print Center Hydronic System
Renovation

To: Planholders

AES Project No.: 13071-124

Addendum No.: 2

CC:

CHANGES TO PROJECT MANUAL

GENERAL:

- New piping is permitted to be installed below the roof joists up as high as possible and shall be kept as close to the east wall as possible.
- Grooved coupling piping is allowed, joints shall be supported within 12" on each side of joints.
- In attendance at the pre-bid meeting
 - Kyle Wilkinson – AES
 - Tim Loseke – LPS
 - Jay Lawson – LPS
 - Steve DeGarmo – LPS
 - John Burbach – LPS
 - Mike Cook – Vision Mechanical
 - Jeff Cooper – Midlands Mechanical

By:

Kyle Wilkinson/AES

Date:

9/5/2013