

Sampson Construction Co., Inc.
3730 South 14th Street
Lincoln, NE 68502
Phone: (402) 434-5450
FAX: (402) 434-5466

Bid Bulletin #04

PROJECT: Baldwin Filters Distribution Facility (Bid Package #04)
Kearney, NE

DATE: November 19, 2013

This Bid Bulletin includes items 1-1 through 1-4. Each item shall be fully incorporated into the Bidding/Contract Documents and have the same force and effect as though originally included. Bidders shall acknowledge receipt of this Bid Bulletin on the bid form.

- Item 1-1 **Specification section 00 01 40- Summary of work #04B- Footings/CIP Walls**
- A. Prior to placing concrete for continuous and pad footings, the top of the exposed Geopier elements under the footings shall be compacted by the footing contractor with a standard hand operated impact compactor (i.e whacker packer). The anticipated number of Geopiers below all footings is 1,000 each.
 - B. The footings and poured walls for the stairs at gridline A & 9.4 shall be included with this summary of work. The architectural section call out for these stairs is incorrect. The stairs are shown on 3/A-507.
 - C. This summary of work shall include installation of steel embeds in the footings and walls for the precast panels. Bidders shall assume installation of 626 embeds (313 panels with 2 embeds per panel).
- Item 1-2 **Specification section 00 01 40- Summary of work #04C- Slabs**
- A. Geopiers will be placed below the slab in the area identified as the settlement sensitive slab on S-102a and S-102b. Prior to placing concrete for the settlement sensitive slab, the top of the exposed Geopier elements under the slab shall be compacted by the slab contractor with a standard hand operated impact compactor (i.e whacker packer). The anticipated number of Geopiers below the settlement sensitive slab is 2,000 each (approximately 8'-0" on center, each way).
 - B. The cast in place steps for the stairs at gridline A & 9.4 shall be included with this summary of work. The architectural section call out for these stairs is incorrect. The stairs are shown on 3/A-507.
- Item 1-3 **Specification section 012300- Alternates**
- A. Delete Alternate #6 as referenced in bid bulletin #3. There is no Alternate #6.
- Item 1-4 Bid date remains 11/21/13 at 2:00 PM.

END OF BID BULLETIN #04