

## **ADDENDUM NO. 1**

STEVENS CREEK STREAM STABILITY  
WATERSHED MASTERPLAN: CIP PROJECT 14  
LANCASTER COUNTY, NEBRASKA

January 9, 2014

The following shall be added to the Contract Documents:

1. Replace Section 01200 MEASUREMENT AND PAYMENT, PART 1 – GENERAL, 1.02 BID ITEMS, Bid Item 8: Excavation Disposal.
2. Replace Section 02220 EARTHWORK, PART 1 – GENERAL, 3.09 MATERIAL DISPOSAL.

## 1.02 BID ITEMS

### **Bid Item 8: Excavation Disposal**

Work under this item shall consist of excavating earth material and disposing of the unsatisfactory and excess excavated material at the spoil location shown on sheet 14 of the drawings. Work under this item includes all handling of the material including excavating, loading, hauling excavated materials, and disposing of the material at the spoil site.

The pay unit for this item is one in-place (prior to excavation) cubic yard. Final measurement of the specified quantity of excavation shall not be made. The quantity shown on the Drawings shall be an established quantity and shall be the basis of payment at the Contract Unit Price per cubic yard bid.

Payment for this Unit Price item will be made at the Contract Unit Price given in the Bid Form, as the work proceeds. This payment shall be full compensation for all stripping of vegetation, conservation of topsoil, excavation, over-excavation, equipment, fuel, labor, materials, and performing all operations necessary for excavating, hauling, disposing of the excavated soil at the spoil site, and all related requirements as indicated on the Drawings and as specified.

## 3.09 MATERIAL DISPOSAL

- A. Excess earth material excavated as part of the construction and unsatisfactory earth material not suitable for use in the project shall be disposed of at the spoil location shown on sheet 14 of the drawings. Temporary stockpiles may be used as necessary to stockpile material prior to final disposal. Coordinate with Engineer on locations of spoil. Contractor shall deposit material at least 40 feet from drainage swales and in a manner that promotes positive drainage. If material is placed on terraced areas, the terraces shall be reformed and compacted at the conclusion of construction.
- B. Contractor shall dispose of all other non-earth material including debris, rubble, rocks, trash at an appropriate offsite disposal facility, unless otherwise specified or directed by the Engineer.
- C. Compaction of Spoil Pile
  - 1. Spoil pile shall be compacted equivalent to NDR Class I Embankments.
    - a. Material shall be not be rolled.
    - b. Material shall be placed in successive horizontal layers not to exceed 12 inches in depth (uncompacted). The layers shall be of uniform thickness and full width and shall be compacted as evenly and densely as possible by varying the haul route over the entire area.
- D. Finished slopes on the spoil locations shall not exceed a 5:1 slope.