



25 February 2014

MILITARY DEPARTMENT  
STATE of NEBRASKA  
LINCOLN, NEBRASKA

**NEBRASKA ARMY NATIONAL GUARD  
CATS BLDG 53 ENVELOPE SUSTAINMENT PROJECT**

at

**Camp Ashland Training Site  
220 County Road A  
Ashland, NE 68003**

**PROJECT NO. 31090345**

**ADDENDUM NO. 1**

The original specifications and drawings on the STATE OF NEBRASKA REQUEST for PROPOSAL FORM for the project noted above are amended as noted in this Addendum No. 1.

Receipt of this Addendum shall be acknowledged by inserting its number and date in the space provided on the Bid Form.

**ADDENDUM NO. 1**

NOTE TO ALL PLANHOLDERS: Please insert this Addendum into your copy of the Contract Documents for the above named project.

The following changes to the Contract Documents are issued by the CFMO-CMB and shall have the same force and affect as though a part of the original issue.

**THE RECEIPT DATE, TIME and LOCATION of the BID PROPOSAL submission HAVE NOT CHANGED.**

**ITEM NO.**

- ADD 1-1     Pre-Bid Meeting Sign-In Sheet.  
Refer to the sign-in sheet, attached at the end of this addendum.
- ADD 1-2     Pre-Bid Meeting Owner Comments  
A. Contractors must be on site to receive their own deliveries. The owner will not accept deliveries on behalf of the contractor.  
B. Space will be provided around the building for staging of materials and contractor parking.  
C. All work must be completed around the building user schedule. A schedule will be provided by the owner.
- ADD 1-3     Sheet A0.01 Demolition Plan  
Refer to General Demolition Note 17, temporary fence shall be 4' plastic construction fence or approved equal.

ADD 1-4

Sheet A1.01 Proposed Drawings

- A. Refer to Floor Plan, West wall paint shall extend to the Southeast outside corner of the Pantry.
- B. Refer to General Notes. Add note 8, interior dust protection / separation and protection of existing equipment shall be provided to allow use of the facility during the construction period.
- C. Refer to Floor Plan and Proposed Key Note 1, note that there are existing receptacles located along the west wall, some below windows and some below windows that require adjustment as noted. Electrical shall be adjusted as required at all window locations.
- D. Refer to 1 – South Elevation, note that step flashing shall be provided at the shingle to siding transition where the roof pitch varies.
- E. Refer to Detail 5 – Toenail Siding Detail Section, stainless steel nails utilized to secure siding shall be minimum of 10 penny.
- F. Refer to Section 7 – Typical Wall Section, soffit material shall be ½" thickness.

ADD 1-5

Specification Section 06 20 13 – Exterior Finish Carpentry

Refer to section 2.4, B – Plywood Soffits, Thickness shall be ½".

ADD 1-6

Specification Section 07 31 13 – Asphalt Shingles


Refer to section 2.5, D – Eave Ventilation Troughs. Units shall be provided at each truss space, spacing is assumed to be 24"oc.

ADD 1-7

Specification Section 07 62 00 – Sheet Metal Flashing and Trim

Refer to section 2.2, note that all flashing, trim, gutters, downspouts, etc. shall be pre-finished WHITE to match the site standard.

THIS ADDENDUM SHALL BE ATTACHED TO AND MADE A PART OF THE DRAWINGS AND SPECIFICATIONS AND SHALL BE ACKNOWLEDGED WITH THE BIDDER'S PROPOSAL.

  
DARYL L. BOHAC  
MAJOR GENERAL The Adjutant General

End of Addendum No. 1



Attachments: One (1)

Pre-Bid Meeting Sign-In Sheet