FARRIS ENGINEERING

ADDENDUM 1

Date:	05/19/14	**Date of Issuance:**	05/19/14
Project Name:	NCECBVI Kitchen Exhaust and Electrical System Upgrade	**Date of Opening:**	05/22/14
FE Project No.:	144008		

NOTICE: This addendum is applicable to the referenced project and is issued to all known planholders prior to receipt of proposals. The information contained herein shall be fully incorporated into the Bid Contract Documents as though originally incorporated. Failure to acknowledge all amendments may be cause for rejection of the bid.

TO: Bidders and Others Concerned

Changes to the Project Manual

1. SECTION 00 11 13 - ADVERTISEMENT FOR BIDS:

   A. Page 1, delete all references to bid date or bids received on "May 22, 2014" and replace with "May 29, 2014."

   B. Page 1, delete all references to the Pre-Bid Walk-Through on "May 19, 2014 at 10:00 am" and replace with "May 22, 2014 at 9:00 am"

2. SECTION 00 41 19 - PROPOSAL:

   A. Page 1, delete all references to "DAS/State Building Division" and replace with "Nebraska Department of Education."

Changes to the Drawings

1. SHEET M-101 – MECHANICAL FLOOR PLANS:

   A. CHANGE ALL NATURAL GAS PIPE SIZE SERVING MAU-1 FROM 2" TO 1 ½".

2. SHEET M-501 – MECHANICAL DETAILS AND SCHEDULES:

   A. CHANGE DISCONNECT FURNISHED/INSTALL BY "E/E" TO "M/I" ON THE MECHANICAL / ELECTRICAL COORDINATION SCHEDULE.

   B. CHANGE THE TSP FROM "2.00" TO "1.25" ON THE GAS FIRED MAKE-UP AIR UNIT SCHEDULE, AND ADD THE FOLLOWING REMARK: "7. PROVIDE FIRE SUPPRESSION SYSTEM WITH WALL MOUNTED STANDARD ENCLOSURE. MOUNT FIRE SUPPRESSION SYSTEM AT SAME LOCATION AS EXISTING, COORDINATE FINAL LOCATION WITH OWNER."

Clarifications

1. THE EQUIPMENT MANUFACTURER IS TO PROVIDE MOTOR STARTERS AND DISCONNECTS FOR MAU-1 AND EF-1.

--END--