

### **Addendum No. 3**

**Project:** St. Patrick Catholic Church  
Bid Set #3  
6111 Morrill Avenue  
Lincoln NE, 68507

**Date Issued:** June 2, 2014

**Issued By:** Brian Semerad, Project Manager  
Kingery Construction Co.

**Bid Date:** June 4, 2014, 2:00 PM

**Item 1:** Section 012300 – Alternates

A. Alternate No. 02: Interior scaffolding

1. Base Bid: All interior work will be performed off of lifts provided by the trade performing the work.
2. Alternate: All interior work will be performed off of scaffolding provided by Kingery Construction Co.

**Item 2:** All materials and systems shall be bid as specified. Voluntary alternates may be bid as well and will be reviewed after bids are received.

**Item 3:** Sheet A701 – First Floor Reflected Ceiling Plan

- A. Revise the exterior soffit at the west Loggia to be a Portland Cement Plaster Finish System as per sheet A201 – West Elevation and Loggia Section.
- B. The Portland Cement Plaster Finish System shall be bid as metal lath that is fastened (wired) to the hat channels which are supported by 1 ½" carrying channels. The plaster is applied to the metal lath. Direct applied EIFS can be bid as a voluntary alternate.

**Item 4:** Sheet M500 – Fire Protection Plan

- A. A dry sprinkler system is to be provided as shown.
- B. The sprinkler system in the existing restrooms in the school can be installed as exposed piping.
- C. Each window on the existing school next to the new entry shall have a ceiling mounted wall wash sprinkler head as per Note 1 on sheet G200 – Code Summary.

**End of Addendum**