



XII STONES INC.

6821 NW 3rd Street
Lincoln, Nebraska 68521

ADDENDUM 3

Date: June 17, 2014

Project: Wayne Maintenance Facility Roof Replacement
District 3
NDOR Building Number: 33702
Project: AFE I-302

This Addendum, consisting of one page, is issued to the Nebraska Department of Roads and all potential bidders.

The following shall be included with, and considered a part of, the original contract documents to the same extent as if they were included therein, for the construction of the above mentioned project, the Project Manual and Drawings shall be modified or revised as herein described, where at variance with the original work, this Addendum shall have precedence.

GENERAL CLARIFICATIONS

1. All Roof Areas
Core samples of the existing roofs to determine insulation thickness is not allowed. Profiles of existing roof construction, including but not limited to the thickness of insulation, are detailed on the drawing sheets enumerated EC-1 and EC-2. Questions pertaining to these existing details shall be brought to the attention of the Architect

DRAWINGS

Architectural

1. Sheet D-2, Note # 13
 - A. Add the following sentences to Note 13, "Reconditioning shall include the removal of rust and paint scale with a wire brush, priming the entire surface with rust inhibiting primer and painting the surface with two coats of paint compatible with the primer. Carefully rake and remove existing sealant or caulk at perimeter of hood and reseal with sealant between metal hood and brick and metal hood and new term bar".

ADDENDUM 2

Architectural

1. Sheet D-3, Note # 12
 - A. Delete the new sentences from Addendum 2 and replace them with the following sentence, "Upon notice or discovery of possible asbestos containing material by the Contractor, the Owner shall initiate steps to identify, remove and mitigate asbestos containing materials that are within the Contractor's area of affected work activities".

End of Addendum 3