

Olsson Associates  
1111 Lincoln Mall  
Lincoln, Nebraska 68608  
June 23, 2014

ADDENDUM NO. 3

NDOR – Oshkosh Oil/Water Separator & Shop Floor Reconstruction  
NDOR Bldg. No. 51601  
AFE I-532  
OA Project No. 012-2295

TO ALL WHO HAVE RECEIVED PLANS AND SPECIFICATIONS FOR THE REFERENCED PROJECT.

**SPECIFICATION DOCUMENTS:**

1. Refer to the 033000 CAST-IN-PLACE CONCRETE.

PART 2 PRODUCTS

2.5 CURING MATERIALS

Delete paragraphs C. and D. in their entirety that were added by Addendum No. 2.

PART 3 EXECUTION

3.9 CONCRETE PROTECTING & CURING

Delete paragraphs D.3 and D.4 in their entirety that were added by Addendum No. 2.

Add the following paragraph:

- E. The Owner will apply an epoxy coating to the floor when the floor is completed. This epoxy coating will not be part of this project. Concrete curing procedure shall accommodate the epoxy coating to be used by the Owner.

Each Bidder must acknowledge receipt of all addenda in the space provided on the Proposal Form.

F:\PROJECTS\012-2295\DOCUMENTS\SPECS\OSHKOSH\_ADDENDUM 3.DOC

