

**ADDENDUM NO. 1**

**PROJECT NAME:** Othmer Hall Machine Shop Renovation  
**UNL PROJECT NUMBER:** 10151  
**BID INVITATION NUMBER:** 2410-14-7200

**CONSULTANT:** Alley Poyner Macchietto Architecture  
**ADDRESS:** 1516 Cuming Street, Omaha, NE 68102

**DATE OF ISSUANCE:** 7-2-2014  
**DATE OF BID OPENING:** 7-17-2014

The bid documents dated, **June 24, 2014**, for the above referenced project are amended by this addendum.

NOTICE: This Addendum is issued to all interested prospective bidders as an amendment to the project manual or other parts of the bidding (contract) documents for the above named project. Reference to this Addendum must be included in the Bid proposal. The information contained herein shall be fully incorporated into the contract documents as though originally included therein.

---

**MODIFICATIONS TO THE DRAWINGS:**

**MODIFICATIONS:**

1. Add the following:

**DRAWING NO. D1.0 – DETAIL: Demolition Plan**

**END OF ADDENDUM NO. 1**

# OTHMER HALL MACHINE SHOP RENOVATION

17th and Vine Streets  
Lincoln NE



## DEMOLITION GENERAL NOTES

1. THE INTENT OF THESE DEMOLITION DRAWINGS IS TO DEFINE A GENERAL SCOPE OF DEMOLITION WORK. THESE DRAWINGS MAY NOT IDENTIFY EVERY ITEM TO BE REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING ALL ITEMS WHICH MUST BE REMOVED TO FACILITATE NEW CONSTRUCTION.
2. ITEMS DRAWN SOLID AND DASHED ARE TO BE REMOVED. REFER TO KEYED NOTES FOR SPECIFIC ITEMS.
3. REMOVE ALL ABANDONED PIPING, ELECTRICAL CONDUIT, MISCELLANEOUS HANGERS, MISCELLANEOUS DUCTWORK, AND ALL OTHER ABANDONED ITEMS UNLESS OTHERWISE NOTED. COORDINATE WITH MEP SCOPE OF WORK.  
  
AT ALL ABANDONED PIPING STUBS IN FLOOR, CAP PIPES 6" BELOW THE FLOOR AND PATCH FLOOR TO MATCH THE EXISTING.  
  
AT ALL ABANDONED FLOOR DRAINS, INSTALL FLOATABLE FILL TO CREATE LEVEL SURFACE.
4. DISPOSE OF ALL ITEMS IN ACCORDANCE WITH ALL APPLICABLE REQUIREMENTS.

## DEMOLITION KEYED NOTES

- (d1) REMOVE EXISTING DOOR, FRAME AND HARDWARE
- (d2) REMOVE WALL AS REQUIRED FOR NEW CONSTRUCTION.
- (d3) REMOVE LOWER 4" OF DRYWALL
- (d4) REMOVE ALL EXPOSED REBAR SURROUNDING ACCESS DOORS.
- (d5) REMOVE CONCRETE FOR INSTALLATION OF SUMP PUMP
- (d6) EXISTING DOOR(S) TO REMAIN

**ALLEY•POYNER  
MACCHIETTO  
ARCHITECTURE**  
1516 Cuming Street  
Omaha, NE 68102  
Ph: 402.341.1544  
Fx: 402.341.4735  
alleypoyner.com

CONSULTANTS  
CIVIL ENGINEER

STRUCTURAL ENGINEER  
Thompson, Dreesen & Dornier, Inc.  
10836 Old Mill Rd.  
Omaha, NE 68154  
(402) 330-8860 / FAX: (402) 330-5866

MECHANICAL ENGINEER  
Engineering Technologies Inc  
1111 North 13th St, Suite 216  
Omaha, NE 68102  
(402) 330-2772 / FAX: (402) 330-2630

ELECTRICAL ENGINEER  
Engineering Technologies Inc  
1111 North 13th Street, Suite 216  
Omaha, NE 68102  
(402) 330-2772 / FAX: (402) 330-2630




REVISION \_\_\_\_\_ DATE \_\_\_\_\_

PROJECT NUMBER: 13088  
DATE: 06/24/2014

COPYRIGHT © 2014  
ALLEY•POYNER MACCHIETTO ARCHITECTURE, P.C.

# D1.0

**J4** DEMOLITION FLOOR PLAN  
AD1.0 SCALE: 1/8" = 1'-0"



**M8** TYPICAL PIPES TO BE CAPPED AND FLOOR DRAIN TO BE LEVELLED  
AD1.0 SCALE: 1/8" = 1'-0"