



**ADDENDUM NO. 2**

Project: State of Nebraska – Department of Roads  
District 6 Oconto Maintenance Facility Project (AFE K-600)

Issued: July 14, 2014

Bid Date: **July 17, 2014**

This Addendum is issued to all known plan holders before receipt of proposals.

The following shall be included with, and considered a part of, the original contract documents to the same extent as if they were included therein, for the construction of the above mentioned project. The Project Manual and Drawings shall be modified or revised as herein described. Where at variance with the original work, this Addendum shall have precedence.

This Addendum modifies the original Bidding Documents. The Bidder must acknowledge receipt of this Addendum in the space provided on the Proposal Form. Failure to do so may subject bidder to disqualification.

**ARCHITECTURAL ADDENDA ITEMS:**

- AD2.1.** Specification Section 01 10 00, Part 1.05A. Clarification: The fuel tank will be a 2,000 Gallon tank as shown on the cut sheet in Addendum 1, with a single fuel pump. Regardless of a single or double pump installation there is only a single connection point (under one of the pumps) for electrical connection. The fuel tank and pump platform will be delivered on site and will need to be unloaded and set in place by the Contractor. The tank and pump is estimated at approximately 4,200 lbs.
- AD2.2.** Specification Section 01 10 00, Part 1.05A. The Owner will provide for installation by the Contractor all interior ADA signage, INCLUDING the Men's and Women's restroom signage.
- AD2.3.** Specification Section 08 45 00: In lieu of the specified aerogel, the panels shall have standard insulation with a "U" factor of 0.23 and a light transmission value of 20%.
- AD2.4.** Specification Section 08 71 00, Hardware Schedule . The Owner will provide the Men's and Women's restroom signage for installation by the contractor.
- AD2.5.** Drawing Sheet A700: Finish Schedule, Note 7 shall be deleted. The fabric wrapped acoustic panels have been removed from the drawings and from the project.

**CIVIL ADDENDA ITEMS:**

- AD2.6.** Drawing Sheet C104, Correction on Existing Well: (Refer also to Addendum Item AD2.7) It is believed that the existing 4" well shown on the drawings, even with a new well pump, cannot provide the required 100GPM. Therefore, the contractor shall provide a new well with a submersible water pump to deliver a minimum of



