



5 January 2015

MILITARY DEPARTMENT
STATE of NEBRASKA
LINCOLN, NEBRASKA

**NEBRASKA ARMY NATIONAL GUARD
1776 ARMORY DOOR HARDWARE PROJECT**

at the

**1776 Armory
1776 North 10th Street
Lincoln, Nebraska 68508**

for the

MILITARY DEPARTMENT
STATE of NEBRASKA
Lincoln, Nebraska

ADDENDUM NO. 1

The original specifications and drawings on the STATE OF NEBRASKA REQUEST for PROPOSAL FORM for the project noted above are amended as noted in this Addendum No. 1.

Receipt of this Addendum shall be acknowledged by inserting its number and date in the space provided on the Bid Form.

ADDENDUM NO. 1

NOTE TO ALL PLANHOLDERS: Please insert this Addendum into your copy of the Contract Documents for the above named project.

The following changes to the Contract Documents are issued by the CFMO-CMB and shall have the same force and affect as though a part of the original issue.

THE RECIEPT DATE, TIME and LOCATION of the BID PROPOSAL submission HAS NOT CHANGED.

ITEM NO.:

ADD 1-1: Refer to Sheets D1.1 and D1.2. Remove existing room signage - typical at each door. Patch, repair and repaint existing wall as required.





- ADD 1-2: Refer to Sheet A1.1. At the existing exterior aluminum doors on the North, West and South, replace the existing cylinder. Hardware supplier to verify type as required.
- ADD 1-3 Refer to Sheet A1.1. At doors 147, 158, 161, 162, 165B, 168A, 168B, 168C, 171A and 171B there are existing security system sensors on the doors. The sensors shall be removed and reinstalled by the Contractor as required to accomplish the work, including but not limited to, the prep and painting of the existing frame and the installation of the new door.
- ADD 1-4 Refer to Sheet A1.1. Sign Contractor to provide and install 12 – 18” x 18” way finding signs. Signs will be similar design to the previously specified signage with silk screen characters and shall indicate a grouping of room number locations and directional arrow. Signs shall generally be mounted on interior walls with high bond type and be located at the exterior entry points. Verify exact sign text and mounting location with Architect and Owner prior to fabrication and installation.
- ADD 1-5 Refer to Sheet E1.1. At door 147, add the following note:
“light switch to be removed and relocated into supply room”
- ADD 1-6 Attached is the pre-bid meeting sign-in sheet.

THIS ADDENDUM SHALL BE ATTACHED TO AND MADE A PART OF THE DRAWINGS AND SPECIFICATIONS AND SHALL BE ACKNOWLEDGED WITH THE BIDDER'S PROPOSAL.


DARYL L. BOHAC
Major General The Adjutant General

End of Addendum No. 1



