



PROJECT:	Axtell Outdoor Athletic Complex Upgrades	PROJECT NO.	L14098
FROM:	BVH Architects	DATE:	2.3.2015
TO:	Perspective Bidders	ADDENDUM NO.	No. 2

This Addendum is issued by the Architect to all bidders of record prior to receipt of proposals. Bidders shall acknowledge receipt of this addendum by so indicating on the Proposal Form. Failure to do so may subject Bidder to disqualification.

All information and instructions given herein shall become a part of the Contract Documents.

PROJECT MANUAL

1. Reference Section 012300 – Alternates; subsection 1.04 Schedule of Alternates.
 - a. The following clarifications are being made to Alternates 13 and 14 which were added via Addendum No. 1 issued on 1.30.2015.
 1. Alternate 13 shall include: grinding and sealing all cracks prior to overlay, 2" SPR PG 58-34 asphalt paving overlay on the existing track, and striping of track. No milling will be performed under Alternate 13.
 2. Alternate 14 shall include: grinding and sealing all cracks prior to overlay, 2" Type B, 64-22 asphalt paving overlay on the existing track, and striping of track. No milling will be performed under Alternate 14.

DRAWINGS-N/A

END OF ADDENDUM