ERICKSON ■ ARCHITECTS ■ SULLIVAN

ADDENDUM NO. 2

Project: State of Nebraska
Lincoln Regional Center (LRC) Building #5 Re-Roof Project

Issued: December 5, 2016

Revised Bid Date: December 15, 2016

This Addendum is issued to all known plan holders before receipt of proposals.

The following shall be included with, and considered a part of, the original contract documents to the same extent as if they were included therein, for the construction of the above mentioned project. The Project Manual and Drawings shall be modified or revised as herein described. Where at variance with the original work, this Addendum shall have precedence.

This Addendum modifies the original Bidding Documents. The Bidder must acknowledge receipt of this Addendum in the space provided on the Proposal Form. Failure to do so may subject bidder to disqualification.

AD2.1. The revised Bid Date for this project is now 2:00 pm, Thursday, December 15th, Room 2B.

AD2.2. Correction: Specifications Section 07 53 00, Fully Adhered Elastomeric membrane Roofing, Page 6, Section 2.2 B1, should read as follows: "Total R Value: R=20 continuous minimum total insulation value at all roof areas, except within the roof drain sump areas, which shall taper to the existing roof drain elevations".

AD2.3. Clarification Regarding Security Requirements: The awarded Contractor/Subcontractors shall contact the Nebraska State Patrol and provide proper forms and fees to provide names of employees working within the project site for background check purposes. Delivery personnel are exempt from this security requirement.

AD2.4. Clarification Regarding Site Access: The Contractor may have access to one of the fenced courtyards at any given time, as coordinated with the facility personnel, for any/all access to roof areas for staging, dumpsters, equipment access, etc. but not more than one courtyard area at any given time.

END OF ADDENDUM NO. 2

209 South 9th Street **402.475.1787 Tel.**
Lincoln, Nebraska 68508 **402.475.1800 Fax**