

Replacement of the Roof
for the
State Patrol Trooper E Building

CONTRACT # 039-016-15

ADDENDUM No. 1
January 19, 2017

Bidders are hereby notified that the Contract Documents described in the title of this addendum are hereby modified, corrected and supplemented as follows. Bidders shall make all necessary adjustments to their bids for items listed in the Addendum. This Addendum shall be considered a part of the Contract Documents for this project. Receipt of this Addendum shall be acknowledged on the Bid Form.

1). Reference Section 075323 – Adhered EPDM Roofing:

PART 2 – Products, Paragraph 2.3.A.1.; Add the following as an accepted manufacturer:

- e. Versico Roofing Systems

2). Reference Sheet No. A-2.01, Detail 5 – Aluminum Access Ladder:

- A. The existing dimension from the concrete pavement to the existing top of roof is 13'-8"±. The proposed ladder will be sized based on the proposed top of wall after installation of the new roof including insulation.

3). Clarifications:

Section 075323, Paragraph 2.5.B.2. requires Polyisocyanurate Board Insulation with a compression strength of 25 psi. This is a correct requirement.

The electrical conduit on the south wall of the west section will need to be raised. The conduit supplies power to the red shed southwest of the main building.

Sheet A-2.02, Detail #1 indicates the proposed termination at top of wall. There was a request to revise the detail. At this time, please bid the detail as shown.

For the Nebraska Department of Administrative Services