

ARCHITECTURAL DESIGN ASSOCIATES, P.C.
7501 'O' STREET, SUITE 105
LINCOLN, NE. 68510

March 2, 2017
DIALYSIS CENTER OF LINCOLN
NORTHWEST UNIT
LINCOLN, NEBRASKA

ADDENDA #3 – For Bid Documents Dated 2-15-2017

This addenda is issued by the Architect to all known bidders before receipt of proposals. Bidders shall acknowledge the receipt of this Addendum on their bid form and all information and instructions given herein shall become a part of the Contract Documents.

DRAWINGS:

Item No. 3-1:

Sheet A1.1

- A. On sheet A1.1 add the following general note: Include 5/8 inch type 'X' gyp board at the bottom of all roof truss and roof I-joint framing. Where gyp board is exposed it is to have a level 4 finish. Where gyp board is concealed above ceilings it is to be fire taped only.

SPECIFICATION:

Item No. 3-2:

084113 Aluminum Entrances and Windows

- A. Add Manko as an approved manufacturer for aluminum windows and doors.

See Attached Electrical Addenda items

END OF ADDENDA NO. 3

ADDENDUM



Date: March 2, 2017

Project: NW Dialysis
Salt Creek Circle
Lincoln, NE

To: David Stirtz
Architectural Design Associates
7501 'O' Street, Lincoln, NE 68510
Phone: 402-486-3232
Fax: 402-486-3380

Project No.: 16-113
Addendum No.: 3
CC:

CHANGES TO PROJECT DRAWINGS

All work shall be in accordance with the terms, stipulations, and conditions of the original contract.

Electrical

1. Sheet – E2.1 MAIN FLOOR PLAN-POWER

- a) On E2.1 At the generator renumber circuit LS-59 to LS-25.
- b) Make the same adjustment on the panel schedule LS on E3.1.

2. Sheet – E3.1 and E3.2 for all panels

- a) For all panels with an "O" shown for a 'SPARE' circuit breaker size, revise to "20" amps.

By:

AES

Date:

03/02/2017