



## ADDENDUM #002

DATE: JUNE 22, 2017

6912 NORTH 97TH CIRCLE, SUITE 1 • OMAHA, NEBRASKA 68122 • 402.391.3999  
WEB: WWW.JACKSON-JACKSONASSOCIATES.COM • EMAIL: JACKSON-JACKSON@JJAARCHITECTS.COM

JACKSON  
JACKSON  
& ASSOCIATES, INC.

OWNER: DAS/STATE BUILDING DIVISION  
PROJECT NAME: LRC – BOILER BLDG #11, RE-ROOF  
PROJECT ADDRESS: 801 WEST PROSPECTOR PLAZA, LINCOLN, NE

JJA PROJECT: 3502  
DRAWINGS & SPECIFICATIONS  
DATED: 06/05/17

**The Drawings and Specifications for the above referenced project are hereby amended and the following changes shall be made part of the Contract Documents.**

**ITEM #1**      Refer to the attached Sign-In Sheet for the Pre-Bid Walkthrough occurring on June 22, 2017.

**ITEM #2**      Refer to the Project Specification Manual, Section 07 53 03 - Elastomeric Membrane Roofing - Fully Adhered, Paragraph 2.3.A.7 and the Drawings, Sheet A1.1 - Roof Plan, Roof "A", Keyed Note #3.

- A. Contractor shall remove and replace the two strainer domes located on Roof "A" as they do not lock into the existing clamping ring. Contractor shall provide new cast iron strainer dome that is compatible with the existing clamping ring.

**ITEM #3**      Refer to the Drawings, Sheet A1.1 - Roof Plan, Roof "B", Keyed Note #7.

- A. There are several "Hot Stack" vent pipes on Roof "B". Contractor shall field verify the "Hot Stack" vent pipe locations and shall terminate the new roofing membrane at these locations similar to Firestone Detail P-4 in lieu of the Firestone Detail P-1 that is called out for the standard roof vents.

**End of Addendum #002**

